

Solicitation No. - N° de l'invitation EQ754-162033 /A	Amd. No. - N° de la modif. 004	Buyer ID - Id de l'acheteur pwl012
Client Ref. No. - N° de réf. du client	File No. - N° du dossier	CCC No./N° CCC - FMS No/ N° VME

## **ATTACHMENT No. 005**

### **1.0 Tender Document Clarifications – Bidders’ Questions**

#### **1.1 Question: The drawings 3/A200 section calling for 0.5 “ Densdeck for a concrete deck, is it correct?**

Response: Refer to Solicitation Amendment No.03. This question was answered.

#### **1.2 Question: The drawings 3/A200 and 5/A200 showing “a new insulation board” on perimeter of parapet wall, is it rigid insolation? What is the thickness? And where is shown in the specification?**

Response: Refer to Solicitation Amendment No.03.: Detail 5/A200 was deleted. Refer to Specification Section 07 20 00 Insulation, for requirements of vertical insulation. For dimension of vertical insulation, refer to A-SK-1, issued with this Amendment.

#### **1.3 Question: Structural cut survey need to be done for the concrete condition? and it this cost will be out (contractor) cost or the owner?**

Response: Refer to Drawing A100, Note titled: Structural Survey Locations: **Delete** title, Structural Survey Locations, **Insert:** Survey of Roofs. **Delete** Notes 1, 2, 3. **Insert** the following:

- 1) Before onset of demolition, contractor to conduct survey to determine slope of concrete deck.
- 2) Prepare roof cuts at location of spot elevations shown on 1/A100. Submit survey to Departmental Representatives.
- 3) Survey will be the basis of design for tapered insulation. Submit shop drawings for tapered insulation.
- 4) Fully repair cuts to reinstate waterproof membrane until demolitions.

and **Add** the following note, Structural Condition Survey of the Concrete Roof Deck: Following demolition of the roof assemblies, conduct survey of condition of the concrete deck structure and submit report on condition to Departmental Representative. Identify all locations of damage to existing roof deck that required repair prior to preparation of deck for re-roofing.

#### **1.4 Question: In Section 07.46.00 Parapet restoration under 2.1.1 section “Steel Parapet siding: .076 mm” is it means “a new prefinished steel sheet metal panel” shown on the drawings 3/A200 and 5/A200? and is it have to be a siding or can be a metal sheet?**

Response: Refer to Solicitation Amendment No.03, Detail 5/A200 was deleted. Refer to Specification Section 07 46 00, line 2.1.1, and comply with this section.

#### **1.5 Question: The manufactory warranty is shown 10 years for the roofing membrane in specification under Section 07.52.16 under 1.5. Guaranty ,but material description calling for 20 and up years warranty, is it correct ?Please clarify?**

Response: Refer to Specification Section 07 52 16, line 1.5.1: 10 year warranty. **Delete** all references to 20 years for roofing membrane warranty in the documents.

Solicitation No. - N° de l'invitation EQ754-162033 /A	Amd. No. - N° de la modif. 004	Buyer ID - Id de l'acheteur pwl012
Client Ref. No. - N° de réf. du client	File No. - N° du dossier	CCC No./N° CCC - FMS No/ N° VME

## 2.0 **Drawing Issued with this Amendment**

- 2.1 **Refer to Drawing A200 – Detail 3/A200 has been amended by the attached A-SK-1:  
REVISED 3/A200 DETAIL AT PARAPET WALL**