



- CONCRETE PAD**
- CONCRETE: 35 MPa at 28 DAYS
CLASS C-1 to CSA A23.1-14
5-8% AIR CONTENT
MOIST CURE FOR MINIMUM OF 7 DAYS
 - REINFORCING: DEFORMED BILLET STEEL GRADE 400
 - DRIFT PINS: TO CSA G40.21-300W - SMOOTH RODS
PRE-DRILL 22 mm Ø HOLES IN TIMBERS
 - SURFACE OF CONCRETE TO RECEIVE A BROOM FINISH

revisions		date	
project	HARBOUR IMPROVEMENTS NORTH HEAD AND WHITEHEAD GRAND MANAN, NB CHARLOTTE COUNTY	project	
drawing		designé	
FLAOTING WHARVES SECTIONS			
designed	PWGSC	conçu	
date	DECEMBER 2015		
drawn	PWGSC	dessiné	
date	DECEMBER 2015		
approved		approuvé	
date			
Tender		Sourmission	
PWGSC Project Manager	Administrateur de projets TPSCC		
project number	R.076368.001	no. du projet	
drawing no.	M15	no. du dessin	