



**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
**Bid Receiving Public Works and Government**  
**Services Canada/Réception des soumissions**  
**Travaux publics et Services gouvernementaux**  
**Canada**  
**800 Burrard Street, Room 219**  
**800, rue Burrard, pièce 219**  
**Vancouver**  
**British Columbia**  
**V6Z 0B9**  
**Bid Fax: (604) 775-9381**

**SOLICITATION AMENDMENT**  
**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
Public Works and Government Services Canada -  
Pacific Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> Hatchery Complex Construction	
<b>Solicitation No. - N° de l'invitation</b> F1700-150669/A	<b>Amendment No. - N° modif.</b> 005
<b>Client Reference No. - N° de référence du client</b> F1700-150669	<b>Date</b> 2016-02-03
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-028-7723	
<b>File No. - N° de dossier</b> PWY-5-38345 (028)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2016-02-05</b>	
<b>Time Zone</b> <b>Fuseau horaire</b> Pacific Standard Time PST	
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Lam (PWY), Tian	<b>Buyer Id - Id de l'acheteur</b> pwy028
<b>Telephone No. - N° de téléphone</b> (604) 775-9382 ( )	<b>FAX No. - N° de FAX</b> (604) 775-6633
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> DFO - Snootli Creek Hatchery - Bella Coola, BC	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation No. - N° de l'invitation  
F1700-150669/A

Amd. No. - N° de la modif.  
005

Buyer ID - Id de l'acheteur  
pwy028

Client Ref. No. - N° de réf. du client

File No. - N° du dossier CCC No./N°  
PWY-5-38345

CCC - FMS No./N° VME

---

Please find Addendum #004 herein.  
All other terms and conditions remain unchanged.

THE FOLLOWING CHANGES/CLARIFICATIONS IN THE TENDER DOCUMENTS ARE EFFECTIVE IMMEDIATELY.

“THIS ADDENDUM WILL FORM PART OF THE CONTRACT DOCUMENTS”

ANSWERS TO QUESTIONS RAISED BY BIDDERS

Q1. Drawing EC-101 indicates the limits of the work for contract shown around hatchery complex only. On Drawing C-101 indicates grading and gravel surfacing. Is the grading and gravel surfacing to be included in this contract ?

A1. All site development work other than immediately surrounding the Hatchery Complex Building is excluded.

Q2. What method of fastening is being used to fasten the standing seam roofing to the roof deck ?

A2. Standing-seam roof deck shall be fastened to wood sheathing below with steel roof deck manufacturer's proprietary screws, nylon head, spacing per manufacturer's printed instructions. Fastener proposed shall be part of Shop Drawing Submission. Wood sheathing is fastened to corrugated-metal structural deck by either metal z-bar strips within the insulation, or wood sleepers mechanically fastened.

Q3. Addendum No.3 refer to “13mm tongue and groove pressure treated plywood to replace the OSB on the main assembly detail 4 A-206 & cupola as well. Please advise as to which supplier offers this product, as our supplier has informed us minimum thickness of pressure treated t&g plywood available is 19mm.

A3. Sheathing product within the roof deck shall be 12.5mm softwood ply, sheathing grade, square edge.

Q4. Please clarify the requirement for the 2 ply. Mod. Bit. W.P. membrane, on the roof deck. Membrane thickness and membrane selection.

A4. Modified bitumen membrane shall be SBS single-ply high-heat resistant self-adhesive membrane with 3-ply woven polyethylene surface, 1mm thick x 910mm selvage Lastobond Shield HT or equal.

Q5. The answer to question #4 calls for ‘13 mm ply roof sheathing shall be pressure treated tongue and groove plywood.’ Note: This product is not available, please provide an alternative.

A5. Refer to Q3 above.

Q6. Will the owner be supplying all the structural fill including crush for the hatchery Complex on EC – 101 Shaded (Limit of work) and is the General Contractor therefore responsible for all excavation, compaction, backfill and grading of this area?

A6. Site of the hatchery complex will be prepared by the Owner and ready for the excavation for footings.

END OF ADDENDUM NO.4