

Marginal Wharf Construction
Conne River, NL
721676

Page 1
2016-01-13

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Materials and installation of polymeric geotextiles, purpose of which is to:
 - .1 Separate and prevent mixing of granular materials of different grading.
 - .2 Act as hydraulic filters permitting passage of water while retaining soil strength of granular structure.

1.2 RELATED WORK

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .3 Section 31 53 13 - Timber Cribwork.

1.3 REFERENCES

- .1 American Society for Testing and Materials (ASTM)
 - .1 ASTM D4491-99a(2004)e1, Standard Test Methods for Water Permeability of Geotextiles by Permittivity.
 - .2 ASTM D4595-05, Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method.
 - .3 ASTM D4716-04, Standard Test Method for Determining the (In-Plane) Flow Rate Per Unit Width and Hydraulic Transmissivity of a Geosynthetic Using a Constant Head.
 - .4 ASTM D4751-04, Standard Test Method for Determining Apparent Opening Size of a Geotextile.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-4.2-M88, Textile Test Methods.
 - .2 CAN/CGSB-148.1, Methods of Testing Geotextiles and Geomembranes.
 - .1 No.2-M85, Mass per Unit Area.

Marginal Wharf Construction
Conne River, NL
721676

Page 2
2016-01-13

- .2 No.3-M85, Thickness of Geotextiles.
- .3 No.7.3-92, Grab Tensile Test for Geotextiles.
- .4 No.6.1-93, Bursting Strength of Geotextiles Under No Compressive Load.

- .3 Canadian Standards Association (CSA)
 - .1 CAN/CSA-G40.20-04/G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel.
 - .2 CAN/CSA-G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.

1.4 SAMPLES

- .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit to Departmental Representative the following samples at least 2 weeks prior to commencing work.
 - .1 Minimum length of 1 m of roll width of geotextile.

1.5 MILL CERTIFICATES

- .1 Submit to Departmental Representative a copy of mill test data and certificate at least 2 weeks prior to start of work.

1.6 DELIVERY AND STORAGE

- .1 During delivery and storage, protect geotextiles from direct sunlight, ultraviolet rays, excessive heat, mud, dirt, dust, debris and rodents.

1.7 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

Marginal Wharf Construction
Conne River, NL
721676

Page 3
2016-01-13

- .2 Remove from site and dispose of all packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, and packaging material, in appropriate on-site bins, for recycling in accordance with Waste Management Plan.
- .4 Fold up metal banding, flatten and place in designated area for recycling.

PART 2 - PRODUCTS

2.1 MATERIAL

- .1 Geotextile: woven or non-woven synthetic fibre fabric, supplied in rolls.
 - .1 Width: 3.5 m minimum.
 - .2 Length: 50 m minimum.
 - .3 Composed of: minimum 85% by mass of polyester with inhibitors added to base plastic to resist deterioration by ultra-violet and heat exposure.
- .2 Physical properties:
 - .1 Thickness: to CAN/CGSB-148.1, No.3, minimum 2.5 mm.
 - .2 Mass per unit area: to CAN/CGSB-148.1, No. 2, minimum 400 g/m².
 - .3 Tensile strength and elongation (in any principal direction): to ASTM D4595.
 - .1 Tensile strength: minimum 1200 N, wet condition.
 - .2 Elongation at break: 50 to 100 percent.
 - .3 Seam strength: same as or greater than tensile strength of fabric.
 - .4 Mullen burst strength: to CAN/CGSB-4.2, method 11.1, minimum 3100 kPa.

Marginal Wharf Construction
Conne River, NL
721676

Page 4
2016-01-13

- .3 Hydraulic properties:
 - .1 Apparent opening size (AOS): to ASTM D4751, 50 to 150 micrometres.
 - .2 Permittivity: to ASTM D4491, 0.25 cm per second.
- .4 Securing pins and washers: to CAN/CSA-G40.21, Grade 300W, hot-dipped galvanized with minimum zinc coating of 600 g/m² to CAN/CSA G164.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 For approach crib and marginal cribs, place one (1) layer of geotextile material from base elevation of crib to top of crib and retain in position with securing pins and washers. For uplands slopes, place geotextile full height from bottom of slope to top of slope.
- .2 Place geotextile material by unrolling onto graded surface in orientation, manner and locations indicated and retain in position with securing pins and washers.
- .3 Place geotextile material on sloping surfaces in one continuous length from toe of slope to upper extent of geotextile.
- .4 Place geotextile material smooth and free of tension stress, folds, wrinkles and creases.
- .5 Overlap each successive strip of geotextile 600 mm over previously laid strip.
- .6 Join successive strips of geotextile by sewing.

Marginal Wharf Construction
Conne River, NL
721676

Page 5
2016-01-13

- .7 Pin successive strips of geotextile with securing pins at mid point of lap to satisfaction of Departmental Representative.
- .8 Protect installed geotextile material from displacement, damage or deterioration before, during and after placement of material layers.
- .9 After installation, cover with overlying layer within 4 hours of placement.
- .10 Replace damaged or deteriorated geotextile to approval of Departmental Representative.
- .11 For full cribs, extend geotextile over top of cribwork, in portion of cribwork not containing a concrete deck.

3.2 CLEANING

- .1 Remove construction debris from Project site and dispose of debris in an environmentally responsible and legal manner.

3.3 PROTECTION

- .1 Vehicular traffic not permitted directly on geotextile.