

Marginal Wharf Construction  
Conne River, NL  
721676

Page 1  
2016-01-13

## PART 1 - GENERAL

1.1 GENERAL .1 Rip rap as noted on the drawings for the uplands area between the existing breakwater and end of new marginal wharf will not be measured for payment. Include the costs in the lump sum price.

1.2 REFERENCES .1 American Society for Testing and Materials (ASTM)  
.1 ASTM C117-04, Standard Test Method for Material Finer than 0.075 mm Sieve in Mineral Aggregates by Washing.  
.2 ASTM C136-06, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.  
.2 Canadian General Standards Board (CGSB)  
.1 CAN/CGSB-8.1-88, Sieves, Testing, Woven Wire.  
.2 CAN/CGSB-8.2-M88, Sieves, Testing, Woven Wire, Metric.

1.3 SUBMITTALS .1 Submit to Departmental Representative for approval, 4 weeks before blasting, details of proposed blasting operations showing types and quantities of explosives, loading charges and patterns, type of blasting caps, blasting techniques, blast protection measures, time of blasting and other pertinent details. Submit subsequent changes to Departmental Representative before proceeding.

1.4 REGULATORY REQUIREMENTS .1 Comply with municipal, provincial and national codes and regulations relating to project.

## PART 2 - PRODUCTS

2.1 ROCK MATERIAL .1 Hard, angular rock free from cracks, seams

Marginal Wharf Construction  
Conne River, NL  
721676

Page 2  
2016-01-13

and other defects which may impair durability.

- .2 Relative density, 2.65 minimum.
- .3 Absorption, 1.5 to 2.0% maximum as determined by ASTM C127 test procedure.
- .4 Durability, less than 35% abrasion Wear, ASTM C535 test procedure.
- .5 Sulphate Soundness Determination maximum 12% by ASTM C88.

## 2.2 RIP RAP

- .1 New rip rap to be hard, dense with relative density (formally specific gravity) not less than 2.65, durable quarry stone, free from seams, cracks or other structural defects, to meet following size distribution for use intended.
- .2 Rip-rap stone to be well graded, sizes as indicated on drawings.
- .3 Supply rock spalls to fill open joints.
- .4 Field stones of appropriate sizes are acceptable for hand placed rip-rap.

## PART 3 - EXECUTION

### 3.1 GENERAL

- .1 Take precautions not to damage existing properties during hauling of rock materials. Damage to existing roads or other private or public properties will be repaired at the Contractor's expense.

### 3.2 PREPARATION

- .1 Haul roads: construct and maintain haul roads.

Marginal Wharf Construction  
Conne River, NL  
721676

Page 3  
2016-01-13

### 3.3 RIP RAP

- .1 Place rip-rap as directed to thickness and details indicated or as designated by Departmental Representative.
- .2 Where rip-rap is to be placed on slopes, excavate trench at toe of slope to dimensions as indicated.
- .3 All side slopes to be as shown on the drawings.
- .4 Fine grade area to be rip-rapped to uniform, even surface. Fill depressions with suitable material and compact to provide firm bed.
- .5 Place stones in manner approved by Departmental Representative to secure surface and create a stable mass. Place larger stones at bottom of slopes.
- .6 Hand placing:
  - .1 Use larger stones for lower courses and as headers for subsequent courses.
  - .2 Stagger vertical joints and fill voids with rock spalls or cobbles.
- .7 Finish surface evenly, free of large openings and neat in appearance.