

Marginal Wharf Construction
Conne River, NL
721676

Page 1
2016-01-13

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies the requirements for supply and installation of mooring devices as follows:

.1 Supply and installation of Type "B1" mooring cleats.

1.2 RELATED WORK

- .1 Section 02 41 16 - Sitework, Demolition, and Removal.
- .2 Section 03 10 00 - Concrete Forming and Accessories.
- .3 Section 03 20 00 - Concrete Reinforcing.
- .4 Section 03 30 00 - Cast-in-Place Concrete.

1.3 MEASUREMENT FOR PAYMENT

- .1 Mooring Cleats - Type "B1": The supply and installation of Type "B1" mooring cleats, including pedestal, will be measured by the unit secured in place. Contractor to provide all concrete, reinforcing steel, anchor bolts, nuts, washers, welding, grout, fastenings, plant, equipment, and labour.
- .2 Mooring Rings: The supply and installation of mooring rings will be measured by the unit secured in place.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Mooring Devices:
- .1 Mooring Cleats Type "B1": galvanized cast iron cleats, 36.2kg weight as shown on drawings.

Marginal Wharf Construction
Conne River, NL
721676

Page 2
2016-01-13

- .2 Anchor Bolts and Nuts: to ASTM A307, galvanized.
- .3 Non-Shrink Grout: pre-mixed compound of non-metallic aggregate and plasticizing agents, capable of developing minimum compressive strength of 50 MPa at 28 days.
- .4 Galvanizing: to CSA G164, minimum zinc coating 610 g/m².
- .5 Welding: to CSA W59.
- .6 Sealer: to Section 07 92 10.
- .7 Concrete: to Section 03 30 00.
- .8 Concrete Reinforcement: to CSA G30.12M, Grade 400.
- .9 Mooring rings: mild steel galvanized as shown on drawings.

2.2 SHOP DRAWINGS

- .1 Submit fabricator's shop drawings on cleats in accordance with Section 01 33 00 - Submittal Procedures.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Mooring Cleats - Type "B1":
 - .1 Install Type B1 cleats and pedestals as per the drawings.
 - .2 Install concrete cleat pedestals monolithically with deck.
 - .3 Secure cleats with 25 mm diameter anchor bolts of lengths required complete with associated nuts and washers. After cleat installation is complete, bolt holes in cleats to be filled with approved waterproofing compound.
 - .4 After cleat installation is complete, bolt holes in cleats to be filled with approved waterproofing compound.
- .2 Mooring Rings: Install as per drawings.

Marginal Wharf Construction
Conne River, NL
721676

Page 3
2016-01-13

3.2 GROUT

- .1 Set all mooring cleats at locations and elevations indicated or as directed by the Departmental Representative. Grout under base of cleat using a non-shrink, non-metallic type of grout after tightening of anchor bolts or positioning wedges. Grout must be approved by Departmental Representative. Fill anchor bolt holes with approved sealer. Ensure that temperatures of foundation, air, base and grout are within range specified by grout manufacturers.
- .2 Do not grout until approval given by Departmental Representative.