



**RETURN BIDS TO:
RETOURNER LES SOUMISSIONS A:
Bid Receiving/Réception des
sousmissions**

**RCMP / GRC
Procurement & Contracting services
c/o Commissionaires, F Division
6101 Dewdney Avenue
Regina, SK S4P 3K7**

**Facsimile Number for Amendments:
(306) 780-5232**

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

**The referenced document is hereby
revised; unless otherwise indicated, all
other terms and conditions remain the
same.**

**Ce document est par la présente révisé;
sauf indication contraire, les modalités
de l'invitation demeurent les memes.**

Comments - Commentaries

**Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Facsimile No. - No de télécopieur:

Telephone No. - no de téléphone:

Title-Sujet d'enlèvement des matériaux contaminés, Depot, Regina (SK)	
Solicitation No. - No. de l'invitation M5000-16-5195/A	Date 13 Fevier 2016
Amendment No. - No modif. 01	
Client Reference No. - No. De Référence du Client N/A	
GETS Reference No. - No. de Référence de SEAG N/A	
Solicitation Closes -L'invitation prend fin at - à 2 :00 pm Central Standard Time on - le 22 Fevier 2016	
F.O.B. - F.A.B. Destination	
Address Enquiries to: - Adresser toutes questions à: Teresa Hengen, Agente principale des marchés	
Telephone No. - No de téléphone (306) 780-8179	Fax No. - N° de FAX: (306) 780-5232
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: Gendarmerie royale du Canada 5600 avenue 11th Regina (SK) S4P 3J7	
This document does not contain a PERSONNEL SECURITY Clearance requirements	
Delivery Required - Livraison exigée: See Herein Voir aux présentes	Delivery Offered - Livraison proposée See Herein Voir aux présentes
Name and title of person authorized to sign on behalf of Vendor/Firm Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur	



L'objectif de cette modification est de faire ce qui suit:

- 1) Question: Is it possible to find out if the duct work is insulated?

Answer: The exhaust duct will be removed as per the attached drawing, M1.1 Ventilation Demolition_1, (everything within the bubble is to be removed). The supply duct will be cleaned on the exterior only including the plenum wall on the east side of the range.

- 2) Question: The scope specifies a temporary shower. In order to meet this requirement we will need access to water and a drain.

Answer: The contractor will have to provide a portable facility to accommodate temporary washrooms and showers.

- 3) Question: Are there washroom facilities nearby that staff can use during the remediation?

Answer: No

- 4) Question: Will a security guard be required or is it acceptable to lock up the containment area when we are not there?

Answer: The RCMP will have a commissioner on site at all times while the contractor is working, the building will be locked and alarmed in the evenings, and the work site can be locked in the evening by the contractor if preferred.

- 5) Question: Is the drywall behind the deflection plates being removed or is it just being cleaned?

Answer: We feel that the drywall can be cleaned as with the other non-porous surfaces within the range. Any removal of drywall shall be at the discretion of the RCMP, unless removal is required to access an area that requires abatement. All other drywall may be cleaned in place. The contractor shall ensure that any areas where drywall is removed be sealed with poly sheeting in order to maintain full enclosure.