


Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

[illegible]

1	ISSUED FOR TENDER	Feb 22, 201
revisions	description	date



project	project
---------	---------

REFRIGERATION  
SYSTEM BYPASS, HoC  
FOOD PRODUCTION  
FACILITY

1170 ALGOMA ROAD, OTTAWA, ONT

drawing	dessin
---------	--------

## DRAWING LIST AND LEGEND

Designed By	C. Modrak	Conçu par
Date	October 2015	(yyyy/mm/dd)

Drawn By	G. Tremblay	Dessiné par
Date	October 2015	(yyyy/mm/dd)

Reviewed By	C. Modrak	Examiné par
Date	October 2015	(yyyy/mm/dd)

Approved By	G. Santyr	Approuvé par
Date	October 2015	(yyyy/mm/dd)

Tender	Jordan Cook	Soumission
--------	-------------	------------

Project Manager      Administrateur de projets

Project no.	n° du projet
-------------	--------------

R.034088.027

Drawing no.	n° du dessin
-------------	--------------

1170 ALGOMA ROAD, OTTAWA (ONTARIO)

# MECHANICAL

MECHANICAL DRAWING LIST:

M000	DRAWING LIST AND LEGEND
M100	GROUND FLOOR - KEY PLAN
M101	GROUND FLOOR - NEW EQUIPMENT
M102	ROOF - NEW EQUIPMENT

## GENERAL

\_\_\_\_\_ EXISTING TO REMAIN

NEW TO INSTALL

 DETAIL 1 ON DRAWING M100

CONDENSER

EV-X	<b><u>EVAPORATOR</u></b>
------	--------------------------

## PIPING

—C— PIPING DOWN

—○— PIPING UP

\_\_\_\_\_, CUT ON PIPE

— m — CONDENSATE

RL — LIQUID STATE REFRIGERANT

\_\_\_\_\_ RS \_\_\_\_\_ GAS STATE REFRIGERANT

## ***PLUMBING***

 ROOF DRAIN

HD-X  HUB DRAIN

**CONTROL**

⑦ THERMOSTAT

PHASE	Start	Duration	Task	Access to site	Time	Notes
I	Day of Contract award	11 weeks	Mobilization, shop drawings submission, refrigerant piping sizing, equipment and material delivery	NO	NA	Contractor to assure all required material and equipment is delivered by the end of PHASE I
II	12 weeks after contract award	2 weeks	Roof mounted equipment installation (excluding roof cutting), electrical rough-ins, mechanical rough-ins. All undistructive work	Roof	all time	All work can not affect Food Production Facility (FPF) operation. Work, delivery, hoisting to be coordinated with 48hr advanced notice
				Interior	Fri 21:00 till Sat 15:00	All work to be not intrusive to FPF operation. All work area to be protected prior to commencing site activity and clean, disinfect to food preparation standards before leaving the site. All workers to wear disposable white protective coveralls, gloves and hair nets during PHASE II
III	14 weeks after contract award	2 weeks	Roof cutting, equipment and piping installation, insulation, wiring low and high voltage. Refrigeration work	Interior and roof	all time	All interior will be available for contractor without time restriction. All work area to be protected prior to commencing site activity. Daily cleanup required. Entire area affected by the project to be clean, disinfect to food preparation standards before leaving the site
IV	14 weeks after contract award	2 weeks	Start-up, commissioning, deficiency, identification, close-up	Interior and roof	all time	All work area to be protected prior to commencing site activity and clean, disinfect to food preparation standards before leaving the site. All workers to wear disposable white protective coveralls, gloves and hair nets during PHASE III
	16 weeks after contract award	1 day	Project Close-out	ALL	all time	

C

