



FLOOR PLAN - MAIN LEVEL  
SCALE : 1:100



COLD WATER ENTRANCE ASSEMBLY DETAIL  
NOT TO SCALE

- KEYNOTES**
- 1 NEW 50 DOMESTIC COLD WATER ENTRANCE. REFER TO DETAIL ON THIS DRAWING FOR PIPING ARRANGEMENT.
  - 2 INSTALL REDUCED PRESSURE TYPE BACKFLOW PREVENTERS ON CW AND DHW LINES 1500 ABOVE FLOOR ON WALL. ROUTE TEST DRAINS TO ADJACENT JANITOR'S SINK. REFER TO DETAIL ON DRAWING 2200-3 FOR PIPING ARRANGEMENT.
  - 3 ROUTE TRAP PRIMER PIPING BELOW FLOOR AND UP IN JANITORS ROOM TO WALL MOUNTED TRAP PRIMER STATION (TPS). REFER TO DETAIL ON DRAWING 2200-3 FOR TYPICAL PIPING ARRANGEMENT.
  - 4 ROUTE 20 CW WITHIN SERVICE CHASE TO SERVE HOSE VALVE (HV).
  - 5 ROUTE PIPING THRU CEILING SPACE. COORDINATE ROUTING ON SITE WITH DUCTWORK, LIGHTING, SPRINKLERS, ETC.
  - 6 FIRE STOPPING REQUIRED AT FIRE WALL PENETRATION.
  - 7 MOUNTING HEIGHT FOR EEW TO BE VERIFIED ON SITE WITH DEPARTMENTAL REPRESENTATIVE PRIOR TO INSTALLATION. NOT MORE THAN 825mm ABOVE FLOOR. THIS IS NOT TO BE MOUNTED FOR BARRIER-FREE ACCESS HEIGHT.
  - 8 ROUTE 20 CW, 12 DHW AND 12 DHWR PIPING UP THRU MECHANICAL ROOM FLOOR TO SERVE FIXTURE AS SHOWN. REFER TO DRAWING 2200-1 FOR PIPING CONTINUATION.



- GENERAL NOTES**
1. REFER TO DRAWING 2200-1 FOR LEGEND.



0	RELEASED FOR CONSTRUCTION	01/29/2016
revisions		date

project

**NEW G.O.C.B SAINT-LÉONARD NEW BRUNSWICK**

drawing design

**MAIN FLOOR PLAN CW AND DHW PIPING**

designed	RDD	conçu
date	JANUARY 29, 2016	
drawn	RDD	dessiné
date	JANUARY 29, 2016	
approved	DAG	approuvé
date	FEBRUARY 17, 2016	
Tender		Soumission

PWSSC Project Manager / Administrateur de projets TPSSC  
project number / no. du projet  
**R.069499.001**  
drawing no. / no. du dessin  
**2200-2**