



LEGEND


	PVC (POLYVINYL CHLORIDE) PIPING
	RO/DI WATER TUBING (HIGH DENSITY POLYETHYLENE)
	STAINLESS STEEL TUBING (HYDROGEN PIPING)
	MOTORIZED DAMPER WITH END SWITCH
	PUMP
	SHUT-OFF VALVE
	CHECK VALVE
	BALL VALVE
	PRESSURE GAUGE
	DIRECTION OF FLOW
	THERMAL INSULATION
	EQUIPMENT TAG (REFER TO SCHEDULE)
	DRAWING NOTE TAG
	AIR DUCT RISE/DROP
	AIR RISE/DROP / GRILLE
	DDC TEMPERATURE SENSOR
	FIRE/FLAME SENSOR
	HYDROGEN GAS SENSOR
	HYDROGEN GAS TRANSMITTER
	BACK DRAFT DAMPER
	MANUAL BALANCING DAMPER
	MOTORIZED DAMPER
	FLEXIBLE DUCT CONNECTION
	GRILLE TAG
	RADIATION UNIT TAG
	EQUIPMENT TAG
	ELECTRIC HEATING ELEMENT
	FAN INSIDE A CABINET
	DIFFERENTIAL PRESSURE GAUGE



1 CONTROL ROOM SUPPLY FAN  
M000 N.T.S.



2 ELECTRIC FORCED FLOW HEATERS – CONTROL ROOM  
M000 N.T.S.



3 ELECTRIC PANEL HEATERS – HOGEN ROOM  
M000 N.T.S.

GENERAL NOTES:

1. THE CONTRACTOR SHALL VERIFY EXACT LOCATIONS, SIZES, INVERTS, ETC. PRIOR TO COMMENCEMENT OF WORK. VERIFY ALL CONNECTION POINTS ON SITE.
2. REFER TO ARCHITECTURAL AND ELECTRICAL DRAWINGS FOR COORDINATION PURPOSES.
3. ALL CUTTING & PATCHING OF FLOOR SLABS, WALLS ETC. TO BE PERFORMED BY GENERAL CONTRACTOR.
4. ALL WORK SHALL COMPLY IN EVERY RESPECT WITH ALL NATIONAL, PROVINCIAL AND LOCAL CODES AND BY-LAWS, WHICH SHALL BE CONSIDERED PART OF THE SPECIFICATION. IN THE CASE OF CONFLICTING REQUIREMENTS, BE GOVERNED BY THE MOST STRINGENT REGULATIONS.
5. THE CONTRACTOR SHALL INSTALL WATER SYSTEMS IN COMPLETE ACCORDANCE WITH THE RECOMMENDATIONS OF THE NATIONAL/PROVINCIAL BUILDING CODE, AND ALL AUTHORITIES HAVING JURISDICTION IN THE PROVINCE OF ONTARIO.
6. THE CONTRACTOR SHALL PROVIDE FABRICATION DRAWINGS AND PROVIDE SHOP DRAWINGS FOR ALL EQUIPMENT AND DUCTWORK LAYOUT PRIOR TO ORDERING EQUIPMENT AND FABRICATION OF WORK.
7. THE CONTRACTOR SHALL INSTALL HYDROGEN SYSTEMS IN COMPLETE ACCORDANCE WITH NFPA 2, 50 AND BNQ 1784, THE NATIONAL/PROVINCIAL BUILDING CODE, AND ALL AUTHORITIES HAVING JURISDICTION IN THE PROVINCE OF ONTARIO.
8. COORDINATE THE EXACT LOCATIONS OF EQUIPMENT, DUCT OPENINGS, AND DUCT LOCATIONS WITH THE STRUCTURE. COORDINATE THE EXACT LOCATIONS OF EQUIPMENT WITH ARCHITECTURAL FLOOR PLANS AND DEPARTMENTAL REPRESENTATIVE.
9. COORDINATE THE EXACT LOCATION OF THE MECHANICAL EQUIPMENT ON SITE WITH THE CONTRACTOR, GENERAL CONTRACTOR, ARCHITECTURAL CEILING PLAN, LIGHTING LAYOUT, ETC. TO ENSURE THAT THERE ARE NOT ANY CONFLICTS DURING INSTALLATION.
10. ALL HYDROGEN PIPING TO BE 316 STAINLESS STEEL TUBING AS PER SPECIFICATIONS. (REFER TO SCHEMATIC FOR SIZING). NOTE TUBING SIZES GIVEN IN INCHES.
11. ALL RO/DI WATER TUBING/FITTINGS/VALVES SUPPLIED WITH THE RO SYSTEM, CONTRACTOR IS NOT TO SUBSTITUTE ANY NON-MANUFACTURER SUPPLIED PIPE/VALVED FITTINGS.
12. INFLATION VALVE AND SPARE TO BE MOUNTED IN ACCESSIBLE LOCATION (1200mm) A.F.F. NEAR INFLATION ROOM VIEWING WINDOW.
13. GOVERNMENT FURNISHED EQUIPMENT (GFE) TO BE PROVIDED BY CLIENT AND TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
14. ALL SUPPLY WATER AND RO REJECT WATER PIPING TO BE SCHEDULE 40 PVC. ALL ASSOCIATED VALVES AND FITTINGS TO BE PVC AS PER SPECIFICATIONS.
15. ALL CONTRACTOR SUPPLIED H<sub>2</sub> TUBING AND FITTINGS TO BE SWAGelok AS PER SPECIFICATIONS.
16. HYDROGEN GENERATOR TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
17. PROVIDE ANY SUBMITTAL SUBSTITUTIONS WITH EQUAL PERFORMANCE AS EQUIPMENT SPECIFIED.
18. THE CONTRACTORS ARE RESPONSIBLE FOR THE MUTUAL COORDINATION OF ALL ELECTRICAL REQUIREMENTS OF MECHANICAL EQUIPMENT. COORDINATION IS TO INCLUDE THE COMMUNICATION OF ALL FINAL ELECTRICAL NAMEPLATE INFORMATION BETWEEN THE CONTRACTORS. THE COMMUNICATION OF THE DETAILED CONTROL INFORMATION AS WELL AS ANY ANCILLARY INFORMATION REQUIRED FOR THE FINAL SYSTEMS TO OPERATE AS INTENDED BY THE RESPONSIBLE PROFESSIONAL ENGINEER. THE COORDINATION IS TO OCCUR PRIOR TO THE ORDERING OF EQUIPMENT BY EITHER TRADE. NO EXTRA COMPENSATION WILL BE ALLOWED DUE TO FAILURE TO CARRY OUT THIS COORDINATION. REPORT AT ONCE TO THE CONSULTANT ANY DEFECT, DISCREPANCY, OMISSION OR INTERFERENCE AFFECTING THE SATISFACTORY COMPLETION OF WORK.

GENERAL NOTES: HVAC

1. THE CONTRACTOR SHALL CAREFULLY REMOVE & RELOCATE EXISTING EQUIPMENT AS PER OWNERS REQUIREMENTS.
2. ALL DUCTWORK TO BE OF 100% ALUMINUM CONSTRUCTION AS PER SPECIFICATIONS.
3. ALL MOTORIZED DAMPERS TO BE OF 100% ALUMINUM CONSTRUCTION C/W SPARK PROOF ACTUATOR AS PER SPECIFICATIONS.
4. ALL DUCT DIMENSIONS DENOTE INTERNAL "OPEN" AREA OF THE DUCT.
5. ALL DUCTWORK PENETRATING THE BUILDING THERMAL ENVELOPE SHALL BE INSULATED A MINIMUM 10'-0" BACK FROM THE BUILDING PENETRATION.
6. THE CONTRACTOR SHALL INSTALL HEATING AND VENTILATION SYSTEMS IN COMPLETE ACCORDANCE WITH THE RECOMMENDATIONS OF THE NATIONAL/PROVINCIAL BUILDING CODE, ASHRAE, SMACNA LATEST EDITION DUCT STANDARDS, APPLICABLE NFPA STANDARDS, AND ALL AUTHORITIES HAVING JURISDICTION IN THE PROVINCE OF ONTARIO.
7. ALL INSULATING MATERIALS, METHODS, SIZES AND TYPES OF INSULATION FOR ALL DUCT WORK SHALL BE INSTALLED TO THE REQUIREMENTS OF THE ASHRAE STANDARDS 90.1-2010 "ENERGY STANDARD FOR BUILDING EXCEPT LOW-RISE RESIDENTIAL BUILDINGS", AND THERMAL INSULATION ASSOCIATION OF CANADA (TIAC) STANDARDS.

DRAWING LIST

DRAWING NUMBER	DRAWING TITLE
M000	MECHANICAL LEGEND, DRAWING LIST, GENERAL NOTES AND CONTROL DIAGRAMS
M100	FLOOR PLAN HYDROGEN/WATER SYSTEM
M200	HYDROGEN/WATER SYSTEM SCHEMATIC AND EQUIPMENT SCHEDULE
M201	HYDROGEN/WATER SYSTEM GOVERNMENT FURNISHED EQUIPMENT DETAILS
M300	FLOOR PLAN VENTILATION SYSTEM
M301	VENTILATION SYSTEM DETAILS AND EQUIPMENT SCHEDULE
M400	CONTROL SYSTEM SCHEMATIC AND INPUT/OUTPUT SCHEDULE



FOR BID PURPOSES AND  
NOT FOR CONSTRUCTION


05	ISSUED FOR TENDER	29/01/2016
04	ISSUED FOR 99% PROGRESS SET	04/12/2015
03	ISSUED FOR 66% PROGRESS SET	30/10/2015
02	ISSUED FOR 33% PROGRESS SET	09/10/2015
01	ISSUED FOR CLASS C ESTIMATE	13/05/2015
revision		date

Do not scale drawings.  
Verify all dimensions and conditions on site and immediately  
notify the Departmental Representative of all discrepancies.

	A Detail No.
	B drawing no. — where detail required dessin no. — où détail exigé
	C drawing no. — where detailed dessin no. — où détaillé

project title titre du projet	EGBERT	Ontario
	6248 8TH LINE, L0L 1N0	
	NEW HYDROGEN GENERATION (HOGEN) AND BALLOON LAUNCHING BUILDING	
drawing title titre du dessin	MECHANICAL LEGEND, DRAWING LIST, GENERAL NOTES AND CONTROL DIAGRAMS	
drawn by dessiné par	HB	
designed by conc par	DD	
approved by approuvé par	DD	
bid offre		project manager administrateur de projets
project date date du projet	JAN 29, 2016	
project no. no. du projet	R.071909.001	
drawing no. dessiné no.	M000	





FLOOR PLAN - HYDROGEN/WATER SYSTEM  
SCALE: 1:25

DRAWING NOTES


- FRESH WATER STORAGE TANK TO BE LOCATED AS SHOWN. ENSURE ADEQUATE CLEARANCE FOR PIPING/VALVING BETWEEN FRESH AND WASTE WATER TANKS. WATER SUPPLY PIPE TO CONNECT TO BOTTOM TANK OUTLET. REFER TO SCHEMATIC AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.
- WASTE WATER STORAGE TANK TO BE LOCATED AS SHOWN. ENSURE ADEQUATE CLEARANCE FOR PIPING/VALVING BETWEEN FRESH AND WASTE WATER TANKS. WATER SUPPLY PIPE TO CONNECT TO BOTTOM TANK OUTLET. REFER TO SCHEMATIC AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.
- TANK ISOLATION VALVE TO BE ACCESSIBLE AT FLOOR LEVEL AS SHOWN.
- FRESH AND WASTEWATER STORAGE TANK PIPING TO BE LOW LEVEL AND SUPPORTED FROM FLOOR.
- SECURE THE PIPE TO THE WALL, ON INSIDE OF ROOM, TRANSITION FROM SS TO PVC.
- WATER SUPPLY PIPE TO RISE UP BETWEEN TANKS AS SHOWN. PIPE TO BE FIRMLY SECURED TO CEILING WITH APPROPRIATE CLAMPS. COORDINATE EXACT PLACEMENT ON SITE.
- PUMP SUPPLIED BY CONTRACTOR.
- HYDROGEN GENERATOR (HOGEN UNIT) TO BE LOCATED AS SHOWN. REFER TO SCHEMATIC, DETAILS, AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS. PROVIDE 100MM HIGH CONCRETE HOUSEKEEPING PAD SIZED TO DIMENSIONS OF HOGEN, 97MMX79MM, CONFIRM PRIOR TO FABRICATION.
- R.O. SUPPLY AND RETURN TUBING TO EXTEND SECURED TO CONTROL ROOM WALL AT APPROXIMATELY 1250 MM A.F.F. THROUGH WALL TO HOGEN ROOM AND DROP TO 170 MM A.F.F. AND EXTEND TO REAR OF HOGEN UNIT AS SHOWN. TUBING TO BE SECURED TO HOGEN ROOM WALL. PROVIDE CONNECTION TO HOGEN UNIT, AND APPROPRIATE TUBING SUPPORT FROM FLOOR. REFER TO SCHEMATIC AND DETAILS. PROVIDE PLASTIC ESCUTCHEON AT WALL PENETRATION. USE HDP PIPING.
- VENT VALVE ASSEMBLY TO BE SECURED TO WALL WHERE SHOWN AT 29 MM A.F.F. REFER TO SCHEMATIC, DETAILS, AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.
- HOGEN UNIT REJECT WATER LINE TO EXTEND TO CATCH CAN BENEATH VENT VALVE ASSEMBLY. REFER TO SCHEMATIC AND DETAILS.
- HYDROGEN SUPPLY LINE (FLEXIBLE) TO CONNECT TO HOGEN UNIT AND VENT VALVE ASSEMBLY AS SHOWN. REFER TO SCHEMATIC AND DETAILS.
- HYDROGEN/WATER BYPRODUCT LINE (FLEXIBLE) TO CONNECT TO HOGEN UNIT AND VENT VALVE ASSEMBLY AS SHOWN. REFER TO SCHEMATIC AND DETAILS.
- HEATED WALL VENT ASSEMBLY TO BE LOCATED ON EXTERIOR WALL MOUNT BOTTOM OF ASSEMBLY AT 2500MM A.F.F. WHERE SHOWN. REFER TO SCHEMATIC, DETAILS, AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.
- HYDROGEN/WATER BYPRODUCT LINE TO CONNECT TO VENT VALVE ASSEMBLY. RISE UP TO APPROXIMATELY 455 MM B.O.P. ON INTERIOR WALL AND EXTEND TO TO EXTERIOR WALL AS SHOWN. PROVIDE CONNECTION TO HEATED WALL VENT ASSEMBLY. LINE TO BE SECURED TO INTERIOR WALL USING SWAGelok TUBING SUPPORTS. REFER TO SCHEMATIC AND DETAILS.
- HYDROGEN STORAGE TANK TO BE LOCATED AS SHOWN. REFER TO SCHEMATIC, DETAILS, AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS. COORDINATE EXACT PLACEMENT WITH DEPARTMENTAL REPRESENTATIVE. REFER TO SPECIFICATIONS FOR SEISMIC RESTRAINT REQUIREMENTS.
- HYDROGEN SUPPLY LINE TO CONNECT TO VENT VALVE ASSEMBLY AND EXTEND THROUGH WALL TO HYDROGEN STORAGE TANK ASSEMBLY IN INFLATION ROOM. PROVIDE CONNECTION TO HYDROGEN STORAGE TANK ASSEMBLY. LINE TO BE SECURED TO HOGEN ROOM AND INFLATION ROOM INTERIOR WALLS AND ALUMINUM FRAME EXTENDING FROM INFLATION ROOM WALL USING SWAGelok TUBING SUPPORTS. ALUMINUM FRAME TO BE PROVIDED BY MECHANICAL CONTRACTOR. REFER TO SCHEMATICS AND DETAILS.
- WALL VENT ASSEMBLY TO BE LOCATED ON EXTERIOR WALL, MOUNT BOTTOM OF ASSEMBLY AT 4500MM A.F.F. REFER TO SCHEMATIC, DETAILS, AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.
- HYDROGEN STORAGE TANK VENT LINE TO CONNECT TO VENT OUTLET PIPE AND EXTEND TO EXTERIOR WALL AS SHOWN. PROVIDE CONNECTION TO WALL VENT ASSEMBLY. LINE TO TO BE SECURED TO INTERIOR/EXTERIOR WALL USING SWAGelok PIPE SUPPORTS. REFER TO SCHEMATIC AND DETAILS.
- DISPENSING VALVE ASSEMBLY TO BE SECURED TO WALL WHERE SHOWN. REFER TO SCHEMATIC, DETAILS, AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.
- HYDROGEN SUPPLY LINE TO CONNECT TO STORAGE TANK AND EXTEND TO INTERIOR WALL AS SHOWN. PROVIDE CONNECTION TO DISPENSING VALVE ASSEMBLY. LINE TO BE SECURED TO INTERIOR WALL AND ALUMINUM FRAME EXTENDING FROM INFLATION ROOM WALL USING SWAGelok TUBING SUPPORTS. ALUMINUM FRAME TO BE PROVIDED BY CONTRACTOR. REFER TO SCHEMATIC AND DETAILS.
- HYDROGEN FILL BYPASS LINE TO BE PROVIDED AS SHOWN C/W SHUT OFF VALVE AND QUICK DISCONNECT COUPLER. LINE TO BE ACCESSIBLE AND SECURED TO WALL WHERE SHOWN. REFER TO SCHEMATIC AND EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS. COORDINATE EXACT PLACEMENT WITH DEPARTMENTAL REPRESENTATIVE.
- WASTE WATER REMOVAL PIPE TO EXTEND THROUGH EXTERIOR WALL AT 900 MM ABOVE GRADE. PROVIDE 75 MM FEMALE STAINLESS STEEL LOCKING CAM FITTING C/W PLUG AND CHAIN.
- FRESH WATER PIPE TO EXTEND THROUGH EXTERIOR WALL AT 900 MM ABOVE GRADE. PROVIDE 38 MM MALE STAINLESS STEEL LOCKING CAM FITTING C/W CAP AND CHAIN.
- PIPING TO EXTEND 100 MM INTO THE TANK
- PIPING TO EXTEND 100 MM ABOVE TANK BOTTOM
- PROVIDE FLOAT SWITCH TO BE MOUNTED INSIDE TANK
- PROVIDE PIPE SUPPORTS SUSPENDED FROM STRUCTURE
- PROVIDE FIRESTOPPING MATERIAL AND SEAL TIGHT TO MATCH WALL RATING
- CONTRACTOR TO PROVIDE AND INSTALL COUNTER APPROXIMATELY AS SHOWN. FINAL LOCATION TO BE VERIFIED WITH DEPARTMENTAL REPRESENTATIVE PRIOR TO INSTALLATION
- CONTRACTOR TO PROVIDE HIGH LEVEL ALARM AND INDICATOR LIGHT TO BE LOCATED 2400MM A.F.F. ON EXTERIOR OF THE BUILDING AND TIED TO WASTE WATER
- CONTRACTOR TO PROVIDE HIGH LEVEL ALARM AND INDICATOR LIGHT TO BE LOCATED 2400MM A.F.F. ON EXTERIOR OF THE BUILDING AND TIED TO WASTE WATER



FOR BID PURPOSES AND  
NOT FOR CONSTRUCTION

05	ISSUED FOR TENDER	29/01/2016
04	ISSUED FOR 99% PROGRESS SET	04/12/2015
03	ISSUED FOR 66% PROGRESS SET	30/10/2015
02	ISSUED FOR 33% PROGRESS SET	09/10/2015
01	ISSUED FOR CLASS C ESTIMATE	13/05/2015
revision		date

Do not scale drawings.  
Verify all dimensions and conditions on site and immediately  
notify the Departmental Representative of all discrepancies.



- A Detail No.  
No. du détail  
B drawing no. — where detail required  
dessin no. — où détail exigé  
C drawing no. — where detailed  
dessin no. — où détaillé


project title titre du projet	EGBERT	Ontario
6248 8TH LINE, L0L 1N0		
NEW HYDROGEN GENERATION (HOGEN) AND BALLOON LAUNCHING BUILDING		
drawing title titre du dessin	FLOOR PLAN HYDROGEN/ WATER SYSTEM	
drawn by dessiné par	HB	
designed by conçue par	DD	
approved by approuvé par	DD	
bid offre		project manager administrateur de projets
project date date du projet	JAN 29, 2016	
project no. no. du projet	R.071909.001	
drawing no. dessiné no.	M100	




CONTROL ROOM

HOGEN ROOM


INFLATION ROOM



HYDROGEN / WATER SYSTEM PIPING SCHEMATIC  
SCALE: N.T.S.



NOTES:  
1. SEE HYDROGEN/WATER SYSTEM (DRAWING M100) FOR RO/DI UNIT INSTALLATION DETAIL.



20 COUNTER DETAIL  
N.T.S.

HYDROGEN/WATER SYSTEM EQUIPMENT SCHEDULE				GOVERNMENT FURNISHED EQUIPMENT
EQUIPMENT TAG	DESCRIPTION	MANUFACTURER MODEL NUMBER	NOTES	
1	HYDROGEN GENERATOR	HOGEN S40	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR IN ACCORDANCE WITH MANUFACTURER'S REQUIREMENTS. SEE DETAIL FOR ADDITIONAL INFO.	YES
2	WATER PUMP	SHURFLO 2088-594-144	SUPPLIED AND INSTALLED BY CONTRACTOR. 120V/60HZ/1/8 MOTOR, 75 L/MIN, AT 30 PSI DISCHARGE, BUILT-IN CHECK VALVE, PROVIDE WITH POWER CORD, REFER TO SPECIFICATIONS	
3	VENT VALVE ASSEMBLY MODULE C/W DRAIN PAN	SWAGELOK	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR IN ACCORDANCE WITH INSTALLATION INSTRUCTIONS. SECURE TO WALL (LOCATION SHOWN ON PLAN). MAXIMUM INSTALLATION HEIGHT TO BE 90mm BELOW THE H <sub>2</sub> BY-PRODUCT CONNECTION PORT ON THE HOGEN UNIT. CONNECT ASSEMBLY TO HOGEN H <sub>2</sub> BY-PRODUCT AND BY-PRODUCT PORTS W/ SWAGELOK FJ SERIES METAL HOSE. PIPE ASSEMBLY DRAIN CONNECTION TO DRAIN PAN BENEATH UNIT. SEE DETAIL FOR ADDITIONAL INFO. HOSE PROVIDED BY PWGSC DEPARTMENTAL REPRESENTATIVE.	YES
4	HEATED WALL VENT ASSEMBLY	ENVIRONMENT CANADA	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR IN ACCORDANCE WITH INSTALLATION INSTRUCTIONS. MINIMUM MOUNTING HEIGHT 300mm BELOW GENERATION ROOM CEILING LEVEL. INSTALL W/ A 2° DOWNWARD SLOPE TO THE EXTERIOR. SEAL EXTERIOR WALL PENETRATION W/ EXTERIOR RATED SILICONE CAULKING. SEE DETAIL FOR ADDITIONAL INFO.	YES
7	DISPENSING VALVE ASSEMBLY MODULE	SWAGELOK	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR. SECURE TO WALL (LOCATION SHOWN ON PLAN). CONNECT MODULE TO H <sub>2</sub> STORAGE TANK USING 316SS 1/4", 0.035" WALL TUBING. SEE DETAIL FOR ADDITIONAL INFORMATION, SOLENOID VALVES, FLOW SWITCH, METERING VALVE, SHALL BE SUPPLIED WITH THE ASSEMBLY.	YES
8	STAINLESS STEEL LOCKABLE BALL VALVE (6.5mm)	SWAGELOK 43G SERIES	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR. 316 STAINLESS STEEL CONSTRUCTION, LOCKOFF, 6.5mm UNION.	YES
9	S.S. QUICK CONNECT	SWAGELOK SS-QFIGS-16PF	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR. 25mm (1") 316SS QUICK CONNECT FULL FLOW.	YES
10	HYDROGEN STORAGE TANK ASSEMBLY	INOX INDUSTRIES INC. P13-023-1	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR. ALL VALVES, GAUGES, FITTINGS, WILL BE PREASSEMBLED WITH TANK. SEE DETAIL FOR ADDITIONAL INFO.	YES
11	WALL VENT ASSEMBLY	SWAGELOK	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR IN ACCORDANCE WITH INSTALLATION INSTRUCTIONS. ASSEMBLY FLANGE TO BE MOUNTED, SEAL FLANGE WITH EXTERIOR RATED SILICONE CAULKING.	YES
12	WATER STORAGE TANK	EQUINOX E-323WS	SUPPLIED AND INSTALLED BY CONTRACTOR. 1476L POLYETHYLENE WATER STORAGE TANK, 1525mm X 750mm X 1500mm(H), POLYETHYLENE LID, 12mm THREADED PVC OUTLET AT NEAR THE OF BOTTOM OF TANK. REFER TO SPECIFICATIONS.	
13	RO/DI WATER PURIFICATION SYSTEM	AQUA SOLUTIONS H-40-C	SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. INSTALLED BY CONTRACTOR IN ACCORDANCE WITH MANUFACTURER'S REQUIREMENTS. SEE DETAIL FOR ADDITIONAL INFO.	YES
14	ACCUMULATE TANK	SHURFLO	SUPPLIED AND INSTALLED BY CONTRACTOR. 8L STAINLESS STEEL, 20 PSI PRECHARGE PRESSURE. REFER TO SPECIFICATIONS.	
15	WATER FILTER HOLDER	---	SUPPLIED AND INSTALLED BY CONTRACTOR. C/W WALL BRACKET, PROVISIONS FOR MOUNTING A PRESSURE DIFFERENTIAL SENSING GAUGE. HOLDS 62.5mm DIA. x 250mm FILTER CARTRIDGE. REFER TO SPECIFICATIONS.	
16	SAMPLING VALVE	---	SUPPLIED AND INSTALLED BY CONTRACTOR. 1/4 TURN PVC VALVE. REFER TO SPECIFICATIONS.	
17	STAINLESS STEEL 38 MM MALE LOCKING CAM FITTING	---	STAINLESS STEEL CONSTRUCTION, MALE COUPLER WITH FEMALE NPT, C/W CAP AND RETENTION CHAIN. SUPPLIED AND INSTALLED BY CONTRACTOR.	
18	STAINLESS STEEL 75 MM FEMALE LOCKING CAM FITTING	---	STAINLESS STEEL CONSTRUCTION, FEMALE COUPLER WITH FEMALE NPT, C/W PLUG AND RETENTION CHAIN. SUPPLIED AND INSTALLED BY CONTRACTOR.	
19	CONTROL TABLE CONSOLE	HAMMOND 1471C36	SUPPLIED AND INSTALLED BY CONTRACTOR. 1220mm X 460mm X 915mm CABINET. REFER TO SPECIFICATIONS.	
20	COUNTER	--	SUPPLIED AND INSTALLED BY CONTRACTOR. PROVIDE 304 STAINLESS STEEL COUNTER TOP REFER TO SPECIFICATIONS AND DETAIL.	



FOR BID PURPOSES AND NOT FOR CONSTRUCTION

05	ISSUED FOR TENDER	29/01/2016
04	ISSUED FOR 99% PROGRESS SET	04/12/2015
03	ISSUED FOR 66% PROGRESS SET	30/10/2015
02	ISSUED FOR 33% PROGRESS SET	09/10/2015
01	ISSUED FOR CLASS C ESTIMATE	13/05/2015
revision		date

Do not scale drawings.  
Verify all dimensions and conditions on site and immediately notify the Departmental Representative of all discrepancies.

A	Detail No.
B	No. du détail
C	drawing no. — where detail required dessin no. — où détail exigé
C	drawing no. — where detailed dessin no. — où détaillé


project title  
titre du projet  
**EGBERT** Ontario  
6248 8TH LINE, L0L 1N0  
**NEW HYDROGEN GENERATION (HOGEN) AND BALLOON LAUNCHING BUILDING**  
drawing title  
titre du dessin  
**HYDROGEN/WATER SYSTEM SCHEMATIC & EQUIPMENT SCHEDULE**

drawn by  
dessiné par  
HB  
designed by  
conçue par  
DD  
approved by  
approuvé par  
DD  
bid  
offre  
project manager  
administrateur de projets  
project date  
date du projet  
JAN 29, 2016  
project no.  
no. du projet  
R.071909.001  
drawing no.  
dessiné no.  
M200



HYDROGEN STORAGE TANK NOTES:


1. HYDROGEN STORAGE TANK AND INSTRUCTIONS PROVIDED BY DEPARTMENTAL REPRESENTATIVE. CONTRACTOR TO INSTALL IN STRICT ACCORDANCE WITH INSTRUCTIONS.
2. ALL DIMENSIONS SHOWN ARE FOR REFERENCE ONLY.
3. INSTALLATION CLEARANCES MUST BE OBSERVED TO MAINTAIN ACCESS FOR SERVICING. REFER TO DETAIL.
4. REFER TO INSTALLATION INSTRUCTIONS CONNECTION POINTS AND ADDITIONAL DETAILS.
5. HYDROGEN STORAGE TANK WEIGHT; 357KG.



10 DETAIL - HYDROGEN STORAGE TANK  
N.T.S.

HYDROGEN GENERATOR (HOGEN) NOTES:

1. HYDROGEN GENERATOR (HOGEN) AND MANUFACTURER'S INSTRUCTIONS PROVIDED BY DEPARTMENTAL REPRESENTATIVE. CONTRACTOR TO INSTALL IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
2. ALL DIMENSIONS SHOWN ARE FOR REFERENCE ONLY.
3. INSTALLATION CLEARANCES MUST BE OBSERVED TO MAINTAIN ACCESS FOR SERVICING. REFER TO DETAIL.
4. REFER TO HOGEN S-40 INSTALLATION MANUAL FOR CONNECTION POINTS AND ADDITIONAL DETAILS (PD-0100-0001 REV M).
5. AC POWER FEED REQUIRES AIR TIGHT CONNECTION TO MAINTAIN PURGE PRESSURE IN CABINET. COORDINATE WITH ELECTRICAL CONTRACTOR.
6. HOGEN WEIGHT; 216KG. SHIPPING WEIGHT 295 KG.




1 DETAIL - HYDROGEN GENERATOR (HOGEN)  
N.T.S.

HEATED WALL VENT ASSEMBLY NOTES:

1. HEATED WALL VENT ASSEMBLY AND INSTALLATION INSTRUCTIONS PROVIDED BY DEPARTMENTAL REPRESENTATIVE. CONTRACTOR TO INSTALL IN STRICT ACCORDANCE WITH INSTALLATION INSTRUCTIONS.
2. HEATED WALL VENT ASSEMBLY TO BE INSTALLED IN EXTERIOR WALL OF HOGEN ROOM. REFER TO DRAWINGS.
3. HEATED WALL VENT ASSEMBLY TUBE TO BE SLOPED TOWARDS BUILDING EXTERIOR AT ANGLE SHOWN WITH REFERENCE TO TRUE LEVEL.
4. SEALANT TO BE APPLIED AT POINTS B, C, AND D. SEALANT TYPE: RTV SILICONE.
5. POWER WIRING TO BE CONNECTED THROUGH COUPLING ON TOP OF CONTROL BOX TO LABELED WIRES. USE 20AWG WIRE. CONNECTION TO BE APPROVED FOR USE IN A CLASS 1, ZONE 2, GROUP IIC ENVIRONMENT.
6. CONTROL WIRING TO BE CONNECTED THROUGH COUPLING ON TOP OF CONTROL BOX TO LABELED WIRES. USE 20AWG WIRE. CONNECTION TO BE APPROVED FOR USE IN A CLASS 1, ZONE 2, GROUP IIC ENVIRONMENT.
7. SWAGelok FITTINGS MAY BE POSITIONED ROTATIONALLY PRIOR TO TIGHTENING.

POWER SUPPLY, 115VAC, 12mm (1/2") FNPT EXPLOSION PROOF CONNECTION (HOGEN Room Wall Vent Heater)

10K THERMISTOR, 24VAC, 12mm (1/2") FNPT EXPLOSION PROOF CONNECTION (HOGEN Rm Wall Vent Temperature)




4 DETAIL - HEATED WALL VENT ASSEMBLY  
N.T.S.

VENT VALVE ASSEMBLY NOTES:

1. VENT VALVE ASSEMBLY TO BE PROVIDED BY DEPARTMENTAL REPRESENTATIVE, AND INSTALLED BY CONTRACTOR.
2. ALL DIMENSIONS SHOWN ARE FOR REFERENCE ONLY.
3. VENT VALVE ASSEMBLY MUST BE LOCATED TO THE RIGHT SIDE OF THE HOGEN AS SHOWN ON DRAWINGS.
4. VENT VALVE ASSEMBLY TO BE MOUNTED TO WALL AND FLOOR USING APPROPRIATE HARDWARE.
5. ACTUAL MOUNTING POINTS MAY VARY SLIGHTLY.

HYDROGEN PRODUCT INLET – 6.5mm (1/4") 316–SS TUBING CONNECTED TO SWAGelok 6.5mm (1/4") FJ SERIES HOSE SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. HOSE TO CONNECT TO HOGEN HYDROGEN OUTLET. REFER TO DRAWINGS.


HYDROGEN BYPRODUCT INLET – 12mm (1/2") 316–SS TUBING CONNECTED TO SWAGelok 12mm (1/2") FJ SERIES HOSE SUPPLIED BY DEPARTMENTAL REPRESENTATIVE. HOSE TO CONNECT TO HOGEN HYDROGEN BYPRODUCT OUTLET. REFER TO DRAWINGS.



3 DETAIL - VENT VALVE ASSEMBLY  
N.T.S.

DISPENSING VALVE ASSEMBLY NOTES:


1. DISPENSING VALVE ASSEMBLY TO BE PROVIDED BY DEPARTMENTAL REPRESENTATIVE, AND INSTALLED BY CONTRACTOR.
2. ALL DIMENSIONS SHOWN ARE FOR REFERENCE ONLY.
3. CONNECTIONS TO BOTH SOLENOID VALVES AND FLOW SWITCH TO BE MADE WITH FLEXIBLE CONDUIT APPROVED FOR USE IN A CLASS 1, ZONE 1, GROUP IIC ENVIRONMENT.
4. DISPENSING VALVE ASSEMBLY TO BE MOUNTED TO WALL AND FLOOR USING APPROPRIATE HARDWARE.
5. ACTUAL MOUNTING POINTS MAY VARY SLIGHTLY.



7 DETAIL - DISPENSING VALVE ASSEMBLY  
N.T.S.

RO/DI WATER PURIFICATION SYSTEM NOTES:

1. WATER PURIFICATION UNIT AND MANUFACTURER'S INSTRUCTIONS PROVIDED BY DEPARTMENTAL REPRESENTATIVE. CONTRACTOR TO INSTALL IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
2. ALL DIMENSIONS SHOWN ARE FOR REFERENCE ONLY.
3. PURITY METER SENSOR (NOT SHOWN) MOUNTED ABOVE PORTS ON RIGHT SIDE OF CABINET.
4. REFER TO AQUA SOLUTIONS OPERATING MANUAL FOR CONNECTION POINTS AND ADDITIONAL DETAILS (MODEL H-40-C).




13 DETAIL - RO/DI WATER PURIFICATION SYSTEM  
N.T.S.



FOR BID PURPOSES AND  
NOT FOR CONSTRUCTION

05	ISSUED FOR TENDER	29/01/2016
04	ISSUED FOR 99% PROGRESS SET	04/12/2015
03	ISSUED FOR 66% PROGRESS SET	30/10/2015
02	ISSUED FOR 33% PROGRESS SET	09/10/2015
01	ISSUED FOR CLASS C ESTIMATE	13/05/2015
revision		date

Do not scale drawings.  
Verify all dimensions and conditions on site and immediately  
notify the Departmental Representative of all discrepancies.



- A Detail No.
- B drawing no. – where detail required
- C drawing no. – where detailed

project title  
titre du projet  
**EGBERT** Ontario

6248 8TH LINE, LOL 1N0

**NEW HYDROGEN GENERATION (HOGEN)  
AND BALLOON LAUNCHING BUILDING**

drawing title  
titre du dessin  
**HYDROGEN/WATER SYSTEM  
GOVERNMENT FURNISHED  
EQUIPMENT DETAILS**

drawn by  
dessiné par **HB**

designed by  
conçue par **DD**

approved by  
approuvée par **DD**


bid  
offre project manager  
administrateur de projets

project date  
date du projet **JAN 29, 2016**

project no.  
no. du projet **R.071909.001**

drawing no.  
dessiné no. **M201**





#### DRAWING NOTES:

- 1 PROVIDE AND INSTALL IN LINE SPARK PROOF EXHAUST FAN AS SHOWN C/W FLEXIBLE DUCT CONNECTIONS AND MOUNTING BRACKETS. FAN TO BE SUSPENDED FROM UNDERSIDE OF CEILING. REFER TO DETAIL, EQUIPMENT SCHEDULE, AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 2 PROVIDE AND INSTALL IN LINE SUPPLY FAN AS SHOWN C/W FLEXIBLE DUCT CONNECTIONS AND MOUNTING BRACKETS. FAN AND DUCTWORK TO BE SUSPENDED FROM UNDERSIDE OF CEILING MINIMUM OF 2500MM TO BOTTOM OF THE UNIT AND ASSOCIATED DUCTWORK
- 3 BACK DRAFT DAMPER OF ALL ALUMINUM CONSTRUCTION TO BE LOCATED AS SHOWN.
- 4 DUCT WORK TO BE OF ALL ALUMINUM CONSTRUCTION AND BE SUPPORTED FROM UNDERSIDE OF STRUCTURE AS SHOWN WITH BOTTOM. PROVIDE OF DUCT AT 2443 MM A.F.F. PROVIDE THERMAL INSULATION OVER ENTIRE LENGTH DOWNSTREAM OF SPARK PROOF EXHAUST FAN.
- 5 EXHAUST DUCT MAIN TO EXTEND THROUGH EXTERIOR WALL AT HIGH LEVEL AS SHOWN. DUCT TO TURN DOWN A MINIMUM OF 1200MM ON BUILDING EXTERIOR C/W WITH ALUMINUM BIRD SCREEN AT DUCT OPENING. INSULATE BACK FROM WALL PENETRATION AS SHOWN. REFER TO DETAIL.
- 6 PROVIDE AND INSTALL 120V MOTORIZED DAMPER OF ALL ALUMINUM CONSTRUCTION WITHIN DUCT AS SHOWN C/W SPARK PROOF ACTUATOR. REFER TO DETAILS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 7 RECIRCULATION DUCT DROP TO BE LOCATED AS SHOWN, AND OFFSET TO BE TIGHT AGAINST WALL. DOWNSTREAM OF MOTORIZED DAMPER, DUCT TO EXTEND TO 450MM ABOVE FINISHED FLOOR C/W ALUMINUM WIRE MESH GRILLE AT OPENING. REFER TO DETAIL.
- 8 EXHAUST DUCT INTAKE TO TURN UPWARDS TO FACE CEILING AS SHOWN. PROVIDE ALUMINUM WIRE MESH GRILLE AT EXHAUST DUCT OPENING. DUCT OPENING TO BE A MINIMUM OF 100 MM BELOW CEILING.
- 9 SUPPLY AIR DUCT TO EXTEND THROUGH EXTERIOR WALL AT HIGH LEVEL AS SHOWN. DUCT TO TURN DOWN AND EXTEND TO A MAXIMUM HEIGHT OF 1200MM ABOVE GRADE ON BUILDING EXTERIOR C/W ALUMINUM BIRD SCREEN AT DUCT OPENING. REFER TO DETAIL.
- 10 SUPPLY AIR DUCT TO TURN DOWN ON BUILDING INTERIOR AND EXTEND TO 450MM ABOVE FINISHED FLOOR C/W ALUMINUM WIRE MESH GRILLE AT DUCT OPENING. PROVIDE MOTORIZED DAMPER AND FILTER BANK OF ALL ALUMINUM CONSTRUCTION ON DUCT DROP. TRANSITION DUCT TO 175MM ROUND BELOW FILTER BANK TO ALLOW INSTALLATION OF AIRFLOW MEASUREMENT STATION. INSULATE OVER ENTIRE LENGTH BACK FROM WALL PENETRATION AS SHOWN. REFER TO DETAIL.

- 11 RELIEF AIR DUCT TO EXTEND THROUGH EXTERIOR WALL AT HIGH LEVEL AS SHOWN. DUCT TO TURN DOWN AND EXTEND TO A MAXIMUM HEIGHT OF 1200MM ABOVE GRADE ON BUILDING EXTERIOR C/W ALUMINUM BIRD SCREEN AT DUCT OPENING.
- 12 RELIEF AIR DUCT WITH BAROMETRIC DAMPER SET TO 0.1" W.G. TO OPEN DUCT TO BE TIGHT TO INTERIOR WALL. PROVIDE 25MM DUCT INSULATION OVER ENTIRE LENGTH THROUGH THE PENETRATION, FROM INTERIOR TO EXTERIOR. TERMINATE INSULATION OUTSIDE AT WALL EDGE AND PROVIDE WATER TIGHT SEAL.
- 13 CONTRACTOR TO PROVIDE AND INSTALL SPARK PROOF ELECTRIC HEATER OF SIZE INDICATED AS SHOWN. CONTROL WIRING TO BE BY CONTRACTOR. COORDINATE INSTALLATION WITH ELECTRICAL. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 14 DUCT TO BE ROUTED EXACTLY AS SHOWN, INCLUDING A MINIMUM 1400MM STRAIGHT SECTION TO ACCOMMODATE AIR FLOW MEASUREMENT SENSOR. REFER TO SECTION FOR ADDITIONAL DETAILS.
- 15 PROVIDE OPEN-ENDED DUCT WITH 12MMX12MM MESH COVER.
- 16 MOUNT EXTERIOR WARNING LIGHTS PER MANUFACTURER RECOMMENDATION COORDINATE INSTALLATION WITH DEPARTMENTAL REPRESENTATIVE PRIOR TO INSTALL PROVIDE A NEMA 4 ENCLOSURE, 250V(X)150(H)X150(D) SEPARATE EACH ENCLOSURE BY 75MM AND DIVISION 26 TO PROVIDE CONDUIT TO BEACONS AND HORN
- 17 PROVIDE AND INSTALL NEW ALUMINUM GRAVITY VENT C/W ALUMINUM BIRD SCREEN ON ROOF OVER EXISTING ROOF PENETRATION. MODIFY ROOF OPENING TO SUIT. REFER TO EQUIPMENT SCHEDULES.
- 18 PROVIDE A 300X300X25 DISPOSABLE PANEL MERV 8 FILTER C/W FILTER RACK.
- 19 CONTRACTOR TO PROVIDE AND INSTALL NEW ELECTRIC FORCE FLOW HEATER OF SIZE INDICATED AS SHOWN. CONTROL WIRING BY CONTRACTOR. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS. MOUNT BOTTOM 250MM A.F.F.
- 20 HOGEN ROOM REMOTE HYDROGEN GAS SENSOR TO BE MOUNTED ON ARM OF ALL ALUMINUM CONSTRUCTION ABOVE HOGEN UNIT AS SHOWN, WITHIN 150MM OF CEILING. ARM TO BE SECURED TO INTERIOR WALL. EXACT LOCATION TO BE CONFIRMED WITH DEPARTMENTAL REPRESENTATIVE. REFER CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 21 HOGEN ROOM HYDROGEN GAS TRANSMITTER TO BE MOUNTED AT EYE LEVEL AS SHOWN. EXACT LOCATION TO BE CONFIRMED WITH DEPARTMENTAL REPRESENTATIVE. REFER CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 22 INFLATION ROOM REMOTE HYDROGEN GAS SENSOR TO BE MOUNTED ON ARM OF ALL ALUMINUM CONSTRUCTION, APPROXIMATELY 300MM ABOVE TOP OF HYDROGEN STORAGE TANK AS SHOWN. ARM TO BE SECURED TO INTERIOR WALL. EXACT LOCATION TO BE CONFIRMED WITH DEPARTMENTAL REPRESENTATIVE. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.


- 23 INFLATION ROOM HYDROGEN GAS TRANSMITTER TO BE MOUNTED AT EYE LEVEL AS SHOWN. EXACT LOCATION TO BE CONFIRMED WITH DEPARTMENTAL REPRESENTATIVE. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 24 PROPOSED LOCATION FOR CONTROL SYSTEM LCD PANEL. REFER TO CONTROL DRAWING AND CONTROL TABLE CONSOLE DETAIL.
- 25 DDC TEMPERATURE SENSOR TO BE LOCATED ON WALL AS SHOWN. REFER CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 26 FIRE AND FLAME SENSOR TO BE LOCATED ON WALL AT 2800MM A.F.F. TO PROVIDE UNOBSTRUCTED VIEW OF HYDROGEN STORAGE TANK AND DISPENSING VALVE ASSEMBLY. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 27 SMOKE DETECTOR TO BE LOCATED APPROXIMATELY AS SHOWN. COORDINATE EXACT LOCATION ON SITE. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 28 FIRE AND FLAME SENSOR TO BE LOCATED ON WALL AT SUITABLE HEIGHT TO PROVIDE UNOBSTRUCTED VIEW OF HOGEN UNIT, VENT VALVE ASSEMBLY, AND HEATED WALL VENT ASSEMBLY. REFER TO CONTROL SCHEMATICS AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 29 CONTRACTOR TO PROVIDE AND INSTALL CONTROL TABLE CONSOLE, APPROXIMATELY AS SHOWN. COORDINATE FINAL LOCATION WITH DEPARTMENTAL REPRESENTATIVE. REFER TO EQUIPMENT TAG 19 ON M-200 FOR ADDITIONAL DETAILS
- 30 PROVIDE OUTSIDE AIR TEMPERATURE SENSOR MOUNTED 2032MM ABOVE GRADE WITH SHIELD WIRED TO THE BAS
- 31 PROVIDE OPEN RETURN DUCT DOWN, EXTEND MINIMUM 150MM BELOW BOTTOM OF DUCT AND PROVIDE MOTORIZED MODULATING DAMPER WITH 12MMX12MM MESH SCREEN OVER OPENING.
- 32 SUPPLY DUCT MAIN TO EXTEND THROUGH EXTERIOR WALL AT HIGH LEVEL AS SHOWN. DUCT TO TURN DOWN A MINIMUM OF 1200MM ON BUILDING EXTERIOR C/W WITH ALUMINUM BIRD SCREEN AT DUCT OPENING. INSULATE BACK FROM WALL PENETRATION AS SHOWN.
- 33 PROVIDE END SWITCH ON DAMPER, INTERLOCK WITH SF-1, PROVIDE CONTROL RELAY FROM 24V TRANSFORMER PROVIDED BY MANUFACTURER OF SF-1
- 34 MOUNT EXTERIOR AUDIBLE HORN IN THE CENTER OF THE WARNING LIGHTS INSTALL PER MANUFACTURER'S RECOMMENDATION



FOR BID PURPOSES AND  
NOT FOR CONSTRUCTION

05	ISSUED FOR TENDER	29/01/2016
04	ISSUED FOR 99% PROGRESS SET	04/12/2015
03	ISSUED FOR 66% PROGRESS SET	30/10/2015
02	ISSUED FOR 33% PROGRESS SET	09/10/2015
01	ISSUED FOR CLASS C ESTIMATE	13/05/2015
revision		date

Do not scale drawings.  
Verify all dimensions and conditions on site and immediately  
notify the Departmental Representative of all discrepancies.



- A Detail No.  
No. du détail  
B drawing no. — where detail required  
dessin no. — où détail exigé  
C drawing no. — where detailed  
dessin no. — où détaillé

project title titre du projet	EGBERT	Ontario
6248 8TH LINE, L0L 1N0		
NEW HYDROGEN GENERATION (HOGEN) AND BALLOON LAUNCHING BUILDING		
drawing title titre du dessin	FLOOR PLAN VENTILATION SYSTEM	
drawn by dessiné par	HB	
designed by conc par	DD	
approved by approuvé par	DD	
bid offre		project manager administrateur de projets
project date date du projet	JAN 29, 2016	
project no. no. du projet	R.071909.001	
drawing no. dessiné no.	M300	




TAG	LOCATION	MAKE	MODEL	TYPE	DRIVE	FLOW (CFM)	FLOW (L/S)	E.S.P. (IN. H2O)	E.S.P. (Pa)	SPEED (RPM)	ELECTRICAL KW/VOLTS	SOUND	NOTES
EF-1	HOGEN ROOM	MARC	ISFX160	INLINE, BACKWARD INCLINED	DIRECT	150	71	1.0	249	2750	0.13/120	-	PLASTIC CONSTRUCTION, CSA CERTIFICATION FOR CLASS 1, ZONE 2, GROUP IIC OPERATION, C/W INDOOR MOUNTING BRACKET
EF-2	HOGEN ROOM	MARC	ISFX160	INLINE, BACKWARD INCLINED	DIRECT	150	71	1.0	249	2750	0.13/120	-	PLASTIC CONSTRUCTION, CSA CERTIFICATION FOR CLASS 1, ZONE 2, GROUP IIC OPERATION, C/W INDOOR MOUNTING BRACKET
SF-1	CONTROL ROOM	N/A	N/A	INLINE CABINET	DIRECT	200	94.4	0.6	150	1681	0.19/120	1.4 SONES	GALVANIZED STEEL CONSTRUCTION, ACUSTICALLY LINED CABINET, C/W EC MOTOR WITH EXTERNAL SPEED CONTROL, PROVIDE WITH 24 VOLT TRANSFORMER





POINT ADDRESS	POINT NAME/FUNCTION	INPUT	OUTPUT	BINARY	ANALOG	MULTI-STATE	ALARM INDICATION	NOTES
300.BI1	Control Room Smoke Det	X		X			X	WIRE TO CONTROL ROOM SMOKE DETECTOR. REFER TO DRAWINGS FOR SMOKE DETECTOR LOCATION.
300.BI2	Control Room Emerg Stop Button	X		X			X	WIRE TO CONTROL ROOM EMERGENCY STOP BUTTON. REFER TO CONTROL TABLE CONSOLE DETAIL FOR EMERGENCY STOP BUTTON LOCATION.
300.BI3	Control Room Dispense Enable Button	X		X			X	WIRE TO CONTROL ROOM DISPENSE BUTTON. REFER TO CONTROL TABLE CONSOLE DETAIL FOR DISPENSING BUTTON LOCATION.
300.MI4	HOGEN Status	X				X	X	DB9 (RS 232) CONNECTOR AT REAR OF HOGEN. HOGEN PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.BI5	HOGEN Fault Alarm	X		X			X	DB9 (RS 232) CONNECTOR AT REAR OF HOGEN. HOGEN PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.MI6	HOGEN Room Flame Detector	X			X		X	WIRE TO HOGEN ROOM HONEYWELL FLAME SENSOR. REFER TO DRAWINGS FOR FLAME SENSOR LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.AI7	HOGEN Room Gas Level	X			X		X	WIRE TO HOGEN ROOM HONEYWELL GAS TRANSMITTER. REFER TO CLASS 1 ZONE 2 GROUP IIC.
300.BI8	HOGEN Rm H2 Gas Sensor Fault	X		X			X	WIRE TO HOGEN ROOM HONEYWELL GAS TRANSMITTER. REFER TO DRAWINGS FOR TRANSMITTER LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.AI9	HOGEN Rm Wall Vent Temperature	X			X		X	WIRE TO HEATED WALL VENT ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.AI10	HOGEN EF1 Amps	X			X			WIRE TO EF-1 CURRENT SENSOR. FOR GRAPHICAL DISPLAY.
300.AI11	HOGEN EF2 Amps	X			X			WIRE TO EF-2 CURRENT SENSOR. FOR GRAPHICAL DISPLAY.
300.AI12	HOGEN Rm Fresh Air Flow	X			X		X	WIRE TO HOGEN ROOM AIRFLOW SENSOR. REFER TO DETAIL FOR AIRFLOW STATION LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.AI13	HOGEN Room Temperature	X			X		X	WIRE TO HOGEN ROOM TEMPERATURE SENSOR. REFER TO DRAWINGS FOR SENSOR LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.BI14	Inflation Room Hydrogen Flow	X		X			X	WIRE TO FLOW SWITCH ON DISPENSING VALVE ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.AI15	Inflation Room Hydrogen Pressure	X			X			WIRE TO PRESSURE TRANSDUCER ON HYDROGEN STORAGE TANK ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.MI16	Inflation Room Flame Detector	X				X	X	WIRE TO INFLATION ROOM HONEYWELL FLAME SENSOR. REFER TO DRAWINGS FOR FLAME SENSOR LOCATION. CLASS 1 ZONE 1 GROUP IIC.
300.AI17	Inflation Room Gas Level	X			X		X	WIRE TO INFLATION ROOM HONEYWELL GAS TRANSMITTER. REFER TO DRAWINGS FOR TRANSMITTER LOCATION. CLASS 1 ZONE 1 GROUP IIC.
300.BI18	Inflation Rm H2 Gas Sensor Fault	X		X			X	WIRE TO INFLATION ROOM HONEYWELL GAS TRANSMITTER. REFER TO DRAWINGS FOR TRANSMITTER LOCATION. CLASS 1 ZONE 1 GROUP IIC.
300.BI19	Operations Bldg Emerg Discharge Button	X		X			X	WIRE TO EMERGENCY DISCHARGE VALVE ACTUATOR ON HYDROGEN STORAGE TANK ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. WIRE TO EMERGENCY DISCHARGE BUTTON LOCATED ON PANEL 200 EXTERIOR IN OPERATIONS BUILDING. REFER TO DETAIL.
300.BI20	HOGEN Room Smoke Det	X		X			X	WIRE TO HOGEN ROOM SMOKE DETECTOR. REFER TO DRAWINGS FOR SMOKE DETECTOR LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.BI21	Light-Horn Test	X		X				WIRE TO TEST BUTTON LOCATED WITHIN PANEL 300 IN CONTROL ROOM.
300.AI22	Control Room Temperature	X			X		X	WIRE TO CONTROL ROOM TEMPERATURE SENSOR/THERMOSTAT. REFER TO DRAWINGS FOR SENSOR LOCATION.
300.BO1	Exterior Red Light		X	X				WIRE TO EXTERIOR RED LIGHT. REFER TO DRAWINGS FOR LOCATION. 24V LED.
300.BO2	Exterior Yellow Light		X	X				WIRE TO EXTERIOR YELLOW LIGHT. REFER TO DRAWINGS FOR LOCATION. 24V LED.
300.BO3	Exterior Green Light		X	X				WIRE TO EXTERIOR GREEN LIGHT. REFER TO DRAWINGS FOR LOCATION. 24V LED.
300.BO4	Exterior White Light		X	X				WIRE TO EXTERIOR WHITE LIGHT. REFER TO DRAWINGS FOR LOCATION. 24V LED.
300.BO5	Exterior Blue Light		X	X				WIRE TO EXTERIOR BLUE LIGHT. REFER TO DRAWINGS FOR LOCATION. 24V LED.
300.BO6	Exterior Horn		X	X				WIRE TO EXTERIOR AUDIBLE ALARM. REFER TO DRAWINGS FOR EXTERIOR ALARM LOCATION.
300.BO7	Control Room Red Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
300.BO8	Control Room Yellow Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
300.BO9	Control Room Green Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
300.BO10	Control Room White Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
300.BO11	Control Room Blue Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
300.BO12	Control Room Horn		X	X				WIRE TO AUDIBLE ALARM BUILT INTO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION.
300.BO13	Hydrogen Dispensing Light (Button)		X	X				WIRE TO CONTROL ROOM DISPENSE BUTTON. REFER TO CONTROL TABLE CONSOLE DETAIL FOR DISPENSING BUTTON LOCATION.
300.BO14	Control Room Heater1		X	X				WIRE TO CONTROL ROOM FORCE FLOW HEATER. REFER TO DRAWINGS FOR HEATER LOCATION.
300.BO15	Control Room Heater2		X	X				WIRE TO CONTROL ROOM FORCE FLOW HEATER. REFER TO DRAWINGS FOR HEATER LOCATION.
300.BO16	HOGEN Enable		X	X				DB9 (RS 232) CONNECTOR AT REAR OF HOGEN. HOGEN PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.BO17	HOGEN Room Wall Vent Heater		X	X				WIRE TO HEATED WALL VENT ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.BO18	HOGEN Room Heater1		X	X				WIRE TO HOGEN ROOM EXPLOSION PROOF HEATER. REFER TO DRAWINGS FOR HEATER LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.BO19	HOGEN Room EF1 Start/Stop		X	X				WIRE TO EF-1 FAN STARTER. FAN STARTER TO BE LOCATED IN CONTROL ROOM.
300.BO20	HOGEN Room EF2 Start/Stop		X	X				WIRE TO EF-2 FAN STARTER. FAN STARTER TO BE LOCATED IN CONTROL ROOM.
300.BO21	HOGEN Rm Mixed Air Dampers		X		X			WIRE TO HOGEN ROOM MOTORIZED DAMPER ACTUATORS. REFER TO DRAWINGS FLR LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.BO22	Hydrogen Valve1		X	X				WIRE TO MASTER DISPENSING VALVE SOLENOID ON DISPENSING VALVE ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.BO23	Hydrogen Valve2		X	X				WIRE TO SECONDARY DISPENSING VALVE SOLENOID ON DISPENSING VALVE ASSEMBLY PROVIDED BY DEPARTMENTAL REPRESENTATIVE. REFER TO DRAWINGS FOR LOCATION. REFER TO DETAIL.
300.BO24	Control Room Heater3		X	X				WIRE TO CONTROL ROOM FORCE FLOW HEATER. REFER TO DRAWINGS FOR HEATER LOCATION.
300.BO25	HOGEN Room Heater2		X	X				WIRE TO HOGEN ROOM EXPLOSION PROOF HEATER. REFER TO DRAWINGS FOR HEATER LOCATION. CLASS 1 ZONE 2 GROUP IIC.
300.BO26	HOGEN Room Heater3		X	X				WIRE TO HOGEN ROOM EXPLOSION PROOF HEATER. REFER TO DRAWINGS FOR HEATER LOCATION. CLASS 1 ZONE 2 GROUP IIC.
200.BI1	Operations Bldg Emerg Stop Button	X		X			X	WIRE TO OPERATIONS BUILDING EMERGENCY STOP BUTTON. REFER TO OPERATIONS BUILDING DETAIL FOR EMERGENCY STOP BUTTON LOCATION.
200.BO1	Operations Bldg Red Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
200.BO2	Operations Bldg Yellow Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
200.BO3	Operations Bldg Green Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
200.BO4	Operations Bldg White Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
200.BO5	Operations Bldg Blue Light		X	X				WIRE TO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION. 24V LED.
200.BO6	Operations Bldg Horn		X	X				WIRE TO AUDIBLE ALARM BUILT INTO CONTROL ROOM STACK LIGHT. REFER TO CONTROL TABLE DETAIL FOR STACK LIGHT LOCATION.



DETAIL - OPERATIONS BUILDING  
N.T.S.

DETAIL - CONTROL ROOM  
SCALE: N.T.S.



FOR BID PURPOSES AND NOT FOR CONSTRUCTION

05	ISSUED FOR TENDER	29/01/2016
04	ISSUED FOR 99% PROGRESS SET	04/12/2015
03	ISSUED FOR 66% PROGRESS SET	30/10/2015
02	ISSUED FOR 33% PROGRESS SET	09/10/2015
01	ISSUED FOR CLASS C ESTIMATE	13/05/2015
revision		date

Do not scale drawings. Verify all dimensions and conditions on site and immediately notify the Departmental Representative of all discrepancies.

A B C	A	Detail No.
	B	No. du détail
	C	drawing no. — where detail required dessin no. — où détail exigé

project title  
titre du projet  
**EGBERT** Ontario  
6248 8TH LINE, LOL 1N0

**NEW HYDROGEN GENERATION (HOGEN) AND BALLOON LAUNCHING BUILDING**

drawing title  
titre du dessin  
**CONTROL SYSTEM SCHEMATIC & INPUT/OUTPUT SCHEDULE**

drawn by  
dessiné par  
**HB**

designed by  
conc par  
**DD**

approved by  
approuvé par  
**DD**

bid  
offre

project manager  
administrateur de projets

project date  
date du projet  
**JAN 29, 2016**

project no.  
no. du projet  
**R.071909.001**

drawing no.  
dessiné no.  
**M400**