



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

**Bid Receiving Public Works and Government
Services Canada/Réception des soumissions
Travaux publics et Services gouvernementaux
Canada**

800 Burrard Street, Room 219

800, rue Burrard, pièce 219

Vancouver

British Columbia

V6Z 0B9

Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

**Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution

Public Works and Government Services Canada -
Pacific Region

800 Burrard Street, Room 219

800, rue Burrard, pièce 219

Vancouver

British C

V6Z 0B9

Title - Sujet Back Up Generator Installation	
Solicitation No. - N° de l'invitation F1700-150949/A	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client F1700-150949	Date 2016-03-11
GETS Reference No. - N° de référence de SEAG PW-\$PWY-033-7755	
File No. - N° de dossier PWY-5-38406 (033)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-03-15	
Time Zone Fuseau horaire Pacific Daylight Saving Time PDT	
F.O.B. - F.A.B.	
Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Siopongco, Philip PWY	Buyer Id - Id de l'acheteur pwy033
Telephone No. - N° de téléphone (604) 775-9385 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DFO - Victoria Coast Guard Base 25 Huron Street Victoria, BC V8VV9	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

N° de l'invitation - Sollicitation No.	N° de la modif - Amd. No.	Id de l'acheteur - Buyer ID
F1700-150949/A	005	PWY033
N° de réf. du client - Client Ref No.	N° du dossier - File No.	FMS No./N°VME - CCC No./N° CCC
	PWY-38406	

Les documents français seront disponibles sur demande.
Les autres conditions ne changent pas.

Amendment 005 has been raise to:

A. Provide clarification / answer to questions received from bidders

The following changes / clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.

A. Questions received from the bidders and the corresponding answers are provided in the attachment.

1. The second last line of the skid description reads “configurable gland plates on both sides of load center enclosure c/w: 1- 200A 3 Phase & C”. Is there a second panel board or are they referring to the skid as a whole? What is “200A 3 Phase & C?”

2. The spec calls for an aluminum enclosure with a steel frame. Which one is it?

3. Please clarify the location in the main electrical room as to where the location of the 25KVA transformer for the generator panel is located.

Toutes les autres conditions demeurent les mêmes.

1. Portable Transformer Clarifications:

300kVA skid type portable power transformer, 600 Volt primary to 460/480 Volt multi-tap secondary, Nema 3R rated enclosure with carbon steel protective cage with four casters.

The 300kVA skid type configuration shall include:

400 Amp rated 16 series camlok input with color coded snap covers to match the voltage used.

200A, 3P, 600 VAC 80% main breaker on the primary side

400 A, 3p, 600 VAC 80% main breaker on the 460/480 volt secondary side as a part of new 400A, 480V, Nema 3R rated panel.

The Panel on secondary shall contain:

1-400A, 3 phase, Moulded case breaker

1-200A, 3 phase, Moulded case breaker

1-100A, 3 phase, Moulded case breaker

Each breaker will feed a receptacle/connection mounted on the Skid as per the following:

1-200A, 3 phase, 4-pole, style 2 crouse-hinds ARL 2040 type receptacle c/w housing and cap fed from the 200A breaker from the secondary side panel

1-400A, 3 phase 16 series camlok connections for future dual line connection fed from the 400A breaker from the secondary side panel.

1-100A, 3 phase, 4-pole, style 2 crouse-hinds AR 1042 type receptacle c/w housing and cap fed from the 200A breaker from the secondary side panel.

NEMA 3R rated enclosure with bottom access trap door (hardwire out access)

Heavy duty carbon steel frame with forklift pockets and lifting eyelets.

Configurable gland plates on secondary side load center.

- Refer to attached sketch for the SLD

