

Project No.:

March 17, 2016

The following changes to the tender documents are effective immediately and will form part of the contract documents for **PHASE 1**:

**1. ADDENDUM 3 Clarifications:**

- **PHASE I - Question 2** - Question and Answers
- Further clarification on the grade elevations and top of floor slab elevation: the existing grade (graded, compacted fill) is at 583.71. The top of the concrete slab at the Header House shall be at 584.10. Thus, the top-of-slab shall be at 0.30 m (approximately 13") above the existing grade.

**2. APPROVED EQUALS:**

<b>APPROVED AS EQUALS</b>	<b>SPECIFIED</b>
Section 076100 Standing Seam Metal Roof Agway AR-38 1 ½" Standing Seam	VicWest Weatherloc / SSR

**3. QUESTIONS AND ANSWERS (PHASE 1):**

**QUESTION 1:** *Are the pile loads indicated in S5.1 in KIPS?*

**ANSWER: YES. THE LOADS INDICATED AT PILES ARE IN KIPS.**

END OF ADDENDUM No. 4 (PHASE 1)