

PART 1 - GENERAL

1.1 SECTION  
INCLUDES

- .1 Barriers.
- .2 Environmental Controls.
- .3 Traffic Controls.
- .4 Fire Routes.

1.2 RELATED  
SECTIONS

- .1 Section 01 50 00 - Temporary Facilities and Controls.

1.3 REFERENCES

- .1 Canadian General Standards Board (CGSB):
  - .1 CAN/CGSB-1.189-2000, Exterior Alkyd Primer for Wood.
  - .2 CAN/CGSB-1.59-97, Alkyd Exterior Gloss Enamel.
- .2 Canadian Standards Association (CSA):
  - .1 CSA-O121-08, Douglas Fir Plywood.

1.4 INSTALLATION  
AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.5 HOARDING

- .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m o.c. Provide one lockable truck gate. Maintain fence in good repair.
- .2 Provide barriers around trees and plants designated to remain. Protect from damage by equipment and construction procedures.

1.6 GUARD RAILS AND  
BARRICADES

- .1 Provide secure, rigid guard rails and barricades around open excavations.

- |   |    |   |
|---|----|---|
| <u>1.6 GUARD RAILS AND BARRICADES</u><br>(Cont'd)       | .2 | Provide barricades along wharf structure when wheelguard is removed.  |
|   | .3 | Provide as required by governing authorities as indicated.  |
| <u>1.7 ACCESS TO SITE</u>                               | .1 | Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.  |
| <u>1.8 PUBLIC TRAFFIC FLOW</u>                          | .1 | Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect the public. |
| <u>1.9 FIRE ROUTES</u>                                  | .1 | Maintain access to property including overhead clearances for use by emergency response vehicles.   |
| <u>1.10 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY</u> | .1 | Protect surrounding private and public property from damage during performance of Work.   |
|   | .2 | Be responsible for damage incurred.   |

PART 2 - PRODUCTS

- |                     |    |           |
|---------------------|----|-----------|
| <u>2.1 NOT USED</u> | .1 | Not Used. |
|---------------------|----|-----------|

PART 3 - EXECUTION

- |                     |    |           |
|---------------------|----|-----------|
| <u>3.1 NOT USED</u> | .1 | Not Used. |
|---------------------|----|-----------|