



- PIPING SCHEMATICS NOTES:**
- EXISTING PIPING FROM PROPANE-FIRED HOT WATER HEATER TO BE DISCONNECTED AT VALVE. EXACT LOCATIONS OF VALVES TO BE VERIFIED ON SITE.
 - EXISTING THERMOMETER TO BE DISCONNECTED AND REMOVED.
 - NEW THERMOMETER TO BE INSTALLED AT LOCATION SHOWN.
 - NEW PG, HWS, HWR, & DHW PIPING TO BE CONNECTED TO PIPE UNION AND RUN TO NEW PROPANE-FIRED HOT WATER HEATER CONNECTIONS.
 - EXISTING CONDENSATE DRAIN PIPING TO BE RE-CONNECTED TO NEW PROPANE-FIRED HOT WATER HEATER THROUGH NEW ACID NEUTRALIZATION CARTRIDGE AND EXHAUST VENT CONDENSATE PIPE CONNECTIONS.

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada

NORTH

M&R ENGINEERING LIMITED
5531 Cornwallis St., Halifax, NS, B3K 1B3
Tel: (902) 422-7393, Fax: (902) 423-4945
Website: www.mreng.ca

GENERAL NOTES:

DO NOT SCALE THIS DRAWING FOR CONSTRUCTION PURPOSES. USE FIGURED DIMENSIONS AS NOTED.

THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS AND GENERAL CONTRACTUAL CONDITIONS.

ALL DIMENSIONS AND CONDITIONS ARE TO BE VERIFIED ON SITE. ALL DISCREPANCIES ARE TO BE REPORTED TO THE DEPARTMENTAL REPRESENTATIVE AND AGREED UPON WITH THEM IN WRITING BEFORE PROCEEDING WITH WORKS.

INFORMATION ON THESE DRAWINGS IS TO BE USED FOR THIS PROJECT ONLY AND SHALL NOT BE USED FOR ANY OTHER PURPOSE.

ISSUED FOR TENDER 01/16

REPLACE GAS-FIRED HOT WATER HEATERS

NOVA INSTITUTION, TRURO, NOVA SCOTIA

PROGRAM BUILDINGS AND BUILDING 'G' MECHANICAL ROOMS 1103 AND 116

designed MAC

date JANUARY 2016

drawn MAC

date JANUARY 2016

approved ARS

date JANUARY 2016

Tender

PWGSC Project Manager Administrateur de projets TPSGC

project number no. du projet

R.061886.001

drawing no. no. du dessin

H301

E-DRW/GDD-E: 533680