


- PIPING SCHEMATICS NOTES:**
- EXISTING PIPING FROM PROPANE-FIRED HOT WATER HEATER TO BE DISCONNECTED AT VALVE. EXACT LOCATIONS OF VALVES TO BE VERIFIED ON SITE.
  - EXISTING THERMOMETER TO BE DISCONNECTED AND REMOVED.
  - NEW THERMOMETER TO BE INSTALLED AT LOCATION SHOWN.
  - NEW PG, HWS, HWR, & DHW PIPING TO BE CONNECTED TO PIPE UNION AND RUN TO NEW PROPANE-FIRED HOT WATER HEATER CONNECTIONS.
  - EXISTING CONDENSATE DRAIN PIPING TO BE RE-CONNECTED TO NEW PROPANE-FIRED HOT WATER HEATER THROUGH NEW ACID NEUTRALIZATION CARTRIDGE AND EXHAUST VENT CONDENSATE PIPE CONNECTIONS.



Public Works and Government Services Canada

NORTH

**M&R ENGINEERING LIMITED**  
5531 Cornwallis St., Halifax, NS, B3K 1B3  
Tel: (902) 422-7393, Fax: (902) 423-4945  
Website: www.mreng.ca

**GENERAL NOTES :**

DO NOT SCALE THIS DRAWING FOR CONSTRUCTION PURPOSES. USE FIGURED DIMENSIONS AS NOTED.

THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH SPECIFICATIONS AND GENERAL CONTRACTUAL CONDITIONS.

ALL DIMENSIONS AND CONDITIONS ARE TO BE VERIFIED ON SITE. ALL DISCREPANCIES ARE TO BE REPORTED TO THE DEPARTMENTAL REPRESENTATIVE AND AGREED UPON WITH THEM IN WRITING BEFORE PROCEEDING WITH WORKS.

INFORMATION ON THESE DRAWINGS IS TO BE USED FOR THIS PROJECT ONLY AND SHALL NOT BE USED FOR ANY OTHER PURPOSE.

1	ISSUED FOR TENDER	01/16
revisions		date
project	project	
<b>REPLACE GAS-FIRED HOT WATER HEATERS</b>		
<b>NOVA INSTITUTION, TRURO, NOVA SCOTIA</b>		
drawing	dessin	
<b>RESIDENTIAL UNITS 1, 2, AND 3 MECHANICAL ROOM 210</b>		
designed	MAC	
date	JANUARY 2016	MAC
drawn	MAC	
date	JANUARY 2016	MAC
approved	ARS	
date	JANUARY 2016	ARS
Tender	Soumission	
PWOSC Project Manager	Administrateur de projets TPSGC	
project number	no. du projet	
<b>R.061886.001</b>		
drawing no.	no. du dessin	
<b>H304</b>		