

**Part 1            General**

**1.1            RELATED SECTIONS**

- .1            Section 01 74 21 – Construction/Demolition Waste Management and Disposal.

**1.2            SECTION INCLUDES**

- .1            Barriers.

**1.3            INSTALLATION AND REMOVAL**

- .1            Provide temporary controls in order to execute Work safely and expeditiously.
- .2            Remove from site all such work after use.

**1.4            HOARDING**

- .1            Erect temporary site enclosure using new 1.2M high snow fence wired to rolled steel “T” bar fence posts spaced at 2.4 meters.

**1.5            GUARD RAILS AND BARRICADES**

- .1            Provide secure, rigid guard rails and barricades around deep excavations, open edges of deck , etc.
- .2            Provide as required by governing Authorities.

**1.6            ACCESS TO SITE**

- .1            Provide and maintain access to adjacent facilities.

**1.7            FIRE ROUTES**

- .1            Maintain access to property.

**1.8            PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1            Protect surrounding private and public property from damage during performance of Work.
- .2            Be responsible for damage incurred.

**1.9            WASTE MANAGEMENT AND DISPOSAL**

- .1            Separate waste materials for reuse and recycling. Refer to Section 01 74 21 – Construction/Demolition Waste Management and Disposal.

Change Island Wharf  
Wharf Reconstruction  
Change Islands, NL  
SCH Project No.: 710689

TEMPORARY BARRIERS &  
ENCLOSURES

Section 01 56 00  
Page 2  
2016-03-14

**Part 2          Products**

**2.1              NOT USED**

.1      Not Used.

**Part 3          Execution**

**3.1              NOT USED**

.1      Not Used.

**END OF SECTION**