


A SOUTH (SIDE) ELEVATION
DEMOLITION
1:75



B SOUTH (SIDE) ELEVATION
CONSTRUCTION
1:75

NOTES

D XXX SELECTIVE DEMOLITION

- D 1.00 REMOVE AND DISCARD EXISTING LIGHTNING PROTECTION SYSTEM, INCLUDING ASSOCIATED CABLES
D 1.01 REMOVE AND DISCARD EXISTING RAINWATER LEADER SYSTEM INCLUDING HARDWARE AND FASTENERS.
D 1.02 REMOVE AND DISCARD EXISTING ASPHALT SHINGLES, FELT UNDERLAY, SELF-ADHERING MEMBRANE AND ASSOCIATED PRE-PAINTED METAL FLASHINGS. DISMANTLE EXISTING WOOD ROOF DECKING TO FRAMING AND SALVAGE AS SPECIFIED WHERE FREE OF DEFECTS FOR RE-USE.
D 1.03 REMOVE AND DISCARD EXISTING ROOFING MEMBRANE, SHEATHING, STRAPPING, SUPPORTS, ASSOCIATED FLASHING, TO FRAMING.
D 1.04 REMOVE AND DISCARD EXISTING METAL FLASHINGS.
D 1.05 CUT EXISTING OPENING AS REQUIRED TO FRAME AND CREATE ATTIC ACCESS HATCH.
D 1.06 REMOVE AND DISCARD EXISTING SUNROOM FASCIA.
D 1.07 DISMANTLE EXISTING EAVES TO THE FRAMING INCLUDING FASCIA, SOFFIT AND OUTRIGGER ELEMENTS.
D 1.08 SALVAGE EXISTING GABLE END PANNELLING FOR REUSE - RESTORE IN SHOP.
D 1.09 REMOVE AND DISCARD EXISTING GABLE RAKE FASCIA.
D 1.10 RESTORE EXISTING GABLE RAKE SOFFIT IN SITU.
D 1.11 REMOVE AND DISCARD EXISTING DORMER CHEEK PANNELLING.
D 1.12 SALVAGE EXISTING DORMER GABLE END PANNELLING FOR REUSE - RESTORE IN SHOP.
D 1.13 RESTORE EXISTING DORMER CHEEK FASCIA IN SITU.
D 1.14 RESTORE EXISTING DORMER RAKING SOFFIT, FASCIA AND MOULDING IN SITU.
D 1.15 RESTORE EXISTING FLAT ROOF FASCIA IN SITU.
D 2.00 REMOVE AND DISCARD EXISTING WOOD CLADDING (CLAPBOARDS & SHINGLES) AND WOODWORK WITH THE EXCEPTION OF ELEMENTS INDICATED FOR SALVAGE OR RESTORATION IN SITU.
D 2.01 AT SUNROOM (ROOF LEVEL), REMOVE ASPHALT SHINGLES AND ASSOCIATED MEMBRANE & FLASHINGS.
D 2.02 REMOVE AND DISCARD EXISTING TEMPORARY PLYWOOD CLADDING.
D 2.03 REMOVE AND DISCARD EXISTING METAL FLASHING.
D 2.04 REPLACE WALL SHEATHING AT EXISTING EXPLORATORY OPENINGS.
D 2.05 REMOVE AND DISCARD EXISTING WINDOW AND FRAME.
D 2.06 REMOVE AND DISCARD EXISTING DOOR AND FRAME.
D 2.07 SALVAGE EXISTING MIDDLE BAND COURSE AND ASSOCIATED MOULDING FOR REUSE - RESTORE IN SHOP.
D 2.08 SALVAGE EXISTING CORNER BOARDS FOR REUSE - RESTORE IN SHOP.
D 2.09 REMOVE AND DISCARD EXISTING FRAMING AND BLOCKING AT OPENINGS.
D 2.10 SALVAGE EXISTING WINDOW CASINGS AS INDICATED FOR REUSE - RESTORE IN SHOP.
D 2.11 SALVAGE EXISTING HOOD BRACKETS AND ASSOCIATED MOULDINGS FOR REUSE - RESTORE IN SHOP.
D 2.12 REMOVE AND DISCARD EXISTING HOOD, SOFFIT AND ASSOCIATED MOULDINGS.
D 2.13 REMOVE AND DISCARD EXISTING FRAMING AND BLOCKING AT OPENINGS; DISCONNECT EXISTING EQUIPMENT, SEE MECHANICAL.
D 3.00 REMOVE AND DISCARD EXISTING METAL STAIRS; CONSERVE CONCRETE PAD.
D 3.01 REMOVE AND DISCARD EXISTING AIR CONDITIONING UNIT, BRACKETS & RELATED HARDWARE AND FASTENERS, SEE ELECTRICAL.
D 3.02 REMOVE EXISTING LIGHT AND CAP REMAINING WIRES, SEE ELECTRICAL. PLACE EQUIPMENT IN STORAGE ON CEF AS DIRECTED BY DEPARTMENT REPRESENTATIVE.
D 3.03 EXISTING SIGNAGE, REMOVED BY OTHERS - N.I.C.
D 3.04 REMOVE AND DISCARD EXISTING ELECTRICAL BOX, SEE ELECTRICAL.
D 3.05 REMOVE AND DISCARD EXISTING AERIAL ANTENNA AND ASSOCIATED WIRING, HARDWARE AND FASTENERS, SEE ELECTRICAL.
D 4.00 CONSERVE EXISTING VERANDAH WOODWORK.
D 4.01 NEW VERANDAH POST - N.I.C.
D 4.02 EXISTING HOSE BIBB TO BE REMOVED BY OTHERS - N.I.C.
D 4.03 EXISTING GAS REGULATOR TO BE SECURED BY OTHERS - N.I.C., SEE MECHANICAL.
D 4.04 PROTECT EXISTING ELECTRICAL SERVICE ENTRY DURING WORK.

X XXX CONSTRUCTION

- 1.00 NEW LIGHTNING PROTECTION SYSTEM, SEE ELECTRICAL.
1.01 CUSTOM FABRICATED MATTE FINISH S/S RAINWATER LEADER SYSTEM.
1.02 WESTERN RED CEDAR SHINGLES.
1.03 MATTE FINISH S/S ROOF.
1.04 MATTE FINISH S/S FLASHINGS.
1.05 REPAIR PLASTER TO MAKE GOOD SURFACE AT OPENING. FIT ATTIC ACCESS HATCH WITH CLOSURE PANEL AND TRIM.
1.06 NEW SUNROOM FASCIA.
1.07 REBUILD EAVES INCLUDING FASCIA & SOFFIT, FOR OUTRIGGER ELEMENTS SEE STRUCTURE.
1.08 RESTORED GABLE END PANNELLING.
1.09 NEW GABLE RAKE FASCIA.
1.10 RESTORED GABLE RAKE SOFFIT.
1.11 NEW DORMER CHEEK PANNELLING.
1.12 RESTORED DORMER GABLE END PANNELLING.
1.13 RESTORED DORMER CHEEKS FASCIA.
1.14 RESTORED DORMER RAKING SOFFIT, FASCIA AND MOULDING.
1.15 RESTORED FLAT ROOF FASCIA.
1.16 WESTERN CEDAR RIDGE CAP WITH MATTE FINISH S/S FLASHING.
2.00 INSTALL NEW WOOD CLADDING (CLAPBOARDS & SHINGLES) AND NEW AND/OR RESTORED WOODWORK.
2.01 NEW METAL CLADDING.
2.02 NEW DOOR.
2.03 INTRODUCE MATTE FINISH S/S FLASHING ABOVE OPENINGS.
2.04 RESERVED.
2.05 NEW WINDOW AND FRAME.
2.06 MAKE DOOR TEMPORARILY INOPERABLE AND INSTALL "OUT OF ORDER" SIGN. COVER EXISTING RELATED "EXIT" SIGNS.
2.07 RESTORED MIDDLE BAND COURSE AND ASSOCIATED MOULDING.
2.08 RESTORED CORNER BOARDS.
2.09 NEW WINDOW, FRAME, STORM AND SCREEN - RESTORED SASH.
2.10 RESTORED WINDOW CASINGS.
2.11 RESTORED HOOD, BRACKETS AND ASSOCIATED MOULDINGS.
2.12 REPRODUCTION HOOD, BRACKETS AND ASSOCIATED MOULDINGS.
2.13 NEW LOUVER; CONNECT EQUIPMENT, SEE MECHANICAL.
3.00 NEW STAIRS - N.I.C.
4.00 REFINISH VERANDAH WOODWORK IN SITU.
4.01 PAINT NEW VERANDAH POST AS SPECIFIED FOR BARE WOOD.
TYP. TYPICAL
N.I.C. NOT IN CONTRACT
S/S STAINLESS STEEL


LEGEND

- # DOOR NUMBER
WINDOW NUMBER
EXISTING ASPHALT ROOF SHINGLES
EXISTING ROOF MEMBRANE
CEDAR ROOF SHINGLES
SALVAGE EXISTING FOR REUSE
RESTORE EXISTING IN SITU
REFINISH EXISTING IN SITU
LIGHTNING PROTECTION GROUND
EXISTING EXPLORATORY OPENING

Canada



Public Works and
Government Services
Canada
Travaux publics et
services gouvernementaux
Canada
DEPARTMENT
OF AGRICULTURE
AND AGRI-FOOD
CANADA
AGRICULTURE ET
AGROALIMENTAIRE
CANADA



GRAPHIC NORTH NORD GRAPHIQUE

architect architecte

**FURNIER
GERSTLITZ
MOREL
DUBLET
ARCHITECTES**
1435 RUE SAINT-ALEXANDRE, BUREAU 1000, MONTREAL, QC H2A 0S4
TELEPHONE: 514-384-0400 TELECOPIER: 514-384-0401
info@fgrmd.com

structural engineer ingénieur en structure

Adejeian Allen Rubeli
Consulting Engineers
75 Albert Street, Ottawa, Ontario
tel: (613) 232-5786
aar@aar.on.ca

electrical engineer ingénieur en électricité

PAGEAUMOREL
Pageau Morel et associés inc.
365, rue Saint-Jacques, 302
Gatineau (Québec) J8T 5K3
T 819-776-4665
F 819-776-4775
www.pageaumorel.com

Contractor to verify all dimensions & conditions on site and immediately notify the department representative of all discrepancies.



1 ISSUED FOR TENDER 2016/03/29

revisions description date

A detail no.
no. du détail
B location drawing no.
sur dessin no.
C drawing no.
dessin no.

project project

**BUILDING ENVELOPE
CONSERVATION**

BUILDING #54, CENTRAL EXPERIMENTAL FARM,
MAPLE AVENUE, OTTAWA, ONTARIO

drawing dessin

SOUTH ELEVATION

Designed By E.B. / J.D. Conçu par

Date 2015/12/23 (yyyy/mm/dd)

Drawn By P.B./M.P. Dessiné par

Date 2015/12/23 (yyyy/mm/dd)

Reviewed By E.B. Examiné par

Date 2016/02/12 (yyyy/mm/dd)

Approved By J.D. / J.G. Approuvé par

Date 2016/03/05 (yyyy/mm/dd)

Tender Soumission

LAUREN GRUSZECKI

Project Manager Administrateur de projets

Project no. No. du projet

R.076826.001

Drawing no. No. du dessin

A-304