


- NOTES:
1. CONTRACTOR TO LOWER NEW ELECTRICAL EQUIPMENT DOWN IN SUMP PIT/WELL EITHER BY CRANE OR BOOM TRUCK.
 2. ALL SWITCHBOARD SECTIONS TO BE SHIPPED IN SINGLE SECTION. CONTRACTOR TO TILT SWITCHBOARD SECTION AS PER OEM INSTRUCTIONS FOR DELIVERY TO 201 ELECTRICAL ROOM FROM SUMP/WELL PIT.
 3. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND CLEARANCES FOR NEW ELECTRICAL EQUIPMENT PRIOR TO RELEASE FOR PRODUCTION AND SHIP TO SITE.
 4. ANY PIPE, MOTOR OR EQUIPMENT NEED TO BE TEMPORARILY REMOVED FOR DELIVERY OF ELECTRICAL EQUIPMENT WILL BE DONE UPON APPROVAL BY THEIR FORCES.




Publics Works and
Government Services
Canada

Real Property
Branch

Travaux publics et
services gouvernementaux
Canada

Direction générale
des biens immobiliers

LEGEND



Goodkey Weedmark
Consulting Engineers

GOODKEY WEEDMARK & ASSOCIATES LIMITED
1688 Woodward Dr.
Ottawa Ontario
Canada K2C 3R8

613 727-5111 Voice
613 727-5115 Fax
www.gweli.com Web



HHAngus

HHAngus & Associates Limited Consulting Engineers
1127 Leslie Street, Toronto, ON, M3C 2J6 Canada
www.hhangus.com | T 416 443 8200 | F 416 443 8290



Stamp

Stamp

2016/04/27	Issued for Tender
2016/04/25	Issued for Tender
2016/03/30	Issued for Tender
2016/03/11	Re-Issued for 100% Review and Translation
2016/02/26	Issued for 100% Review and Translation
2016/02/19	Issued for Tender
Date	Revision

Stamp

project

projet

CFIA

Olf Electrical Upgrades

drawing

dessin

ROUTING FOR
ELECTRICAL
EQUIPMENT DELIVERY
– PHASE 2

Drawn By: S.S.	
Date 2016-01-25	
Reviewed By: P.I.	
Date 2016-01-25	
Project no. M10139	No. du projet
Drawing no. E2-08	No. du dessin