


NEW CONSTRUCTION /
REFLECTED CEILING BUILDING #32 & #34



TYPE A: STEEL DOOR C/W
METAL DOOR BOX (T.Y.P.)


DOOR TYPES
1 : 50

HARDWARE GROUPS


- GROUP 1:
 1 1/2 PRS. HINGES, HAGER, BB1191/SS-32D,NRP-C15, 114mm x 101mm
 1 CLOSER, LCN 1461-H, ALUMINUM FINISH C/W ADAPTOR PLATE, PARALLEL ARM AND HOLD OPEN.
 1 LOCKSET AU5402LN x AGUSTA x US26D
 1 THRESHOLD, ZERO, #565, ALUMINUM FINISH
 1 SET WEATHERSTRIPPING, ZERO, #328 MILL FINISH

- GROUP 2:
 1 1/2 PRS. HINGES, HAGER, BB1279, 114MM X 101MM - C26D
 1 LOCKSET AU5405LN x AGUSTA x US26D
 1 CLOSER, LCN 1461-H, ALUMINUM FINISH C/W ADAPTOR PLATE, PARALLEL ARM AND HOLD OPEN.

- GROUP 3:
 1 1/2 PRS. HINGES, HAGER, BB1191/SS-32D,NRP-C15, 114mm x 101mm
 1 CLOSER, LCN 1461-H, ALUMINUM FINISH C/W ADAPTOR PLATE, PARALLEL ARM AND HOLD OPEN.
 1 LOCKSET AU5405LN x AGUSTA x US26D
 1 THRESHOLD, ZERO, #565, ALUMINUM FINISH
 1 SET WEATHERSTRIPPING, ZERO, #328 MILL FINISH



NEW CONSTRUCTION /
REFLECTED CEILING BUILDING #38



DOOR SCHEDULE

| Number | OPENING | | | DOOR | | | | FRAME (or screen) | | Fire Label or Grill | HARDWARE GROUP | REMARKS |
|--------|---------|--------|-------|------|----------|--------|-------|-------------------|--------|------------------------|-------------------|---------|
| | Width | Height | Thick | Type | Material | Finish | Glass | Type | Finish | | | |
| 100x | 914 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 1 | |
| 101 | 762 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 2 | |
| 102 | 762 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 2 | |
| 103x | 914 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 1 | |
| 104x | 914 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 3 | |
| 105x | 914 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 1 | |
| 106x | 914 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 1 | |
| 107x | 914 | 2032 | 45 | A | IHM | PT. | - | PS | PT. | - | 3 | |

1. ALL DOOR FRAMES TO BE 16 GA. WELDED FRAMES.
 2. ALL DOORS TO BE PRE-MACHINED FOR DOOR HARDWARE.

ROOM FINISH SCHEDULE

| ROOM NAME | FLOOR NUMBER | FLOOR FINISH | WALLS | | | CEILING | | | REMARKS |
|----------------|-----------------|-----------------|-------|----------|--------|----------|--------|--------|--|
| | | | BASE | MATERIAL | FINISH | MATERIAL | FINISH | HEIGHT | |
| FEMALE LAV. | 100 | TILE | - | PLY. | TILE | PLY. | PAINT | VARIES | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| FEMALE SHOWERS | 101 | TILE | - | PLY. | TILE | PLY. | PAINT | VARIES | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| MALE LAV. | 102 | TILE | - | PLY. | TILE | PLY. | PAINT | VARIES | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| MALE SHOWERS | 103 | TILE | - | PLY. | TILE | PLY. | PAINT | VARIES | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| SERVICE ROOM | 104 | PAINT | - | PLY. | PAINT | PLY. | PAINT | VARIES | |
| STORAGE | 105 | PAINT | - | PLY. | PAINT | PLY. | PAINT | VARIES | |
| FEMALE LAV. | 106 | TILE | - | PLY. | TILE | PLY. | PAINT | 2440± | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| FEMALE SHOWERS | 107 | TILE | - | PLY. | TILE | PLY. | PAINT | 2440± | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| SERVICE ROOM | 108 | PAINT | - | PLY. | PAINT | PLY. | PAINT | 2440± | |
| MALE LAV. | 109 | TILE | - | PLY. | TILE | PLY. | PAINT | 2440± | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |
| MALE SHOWERS | 110 | TILE | - | PLY. | TILE | PLY. | PAINT | 2440± | SEE A-1.07 FOR DETAILS ON FLOOR AND WALL TILES |

GENERAL NOTES:

- ALL DIMENSIONS ARE APPROXIMATE AND ARE TO BE SITE VERIFIED. ALL DIMENSIONS ARE IN MILLIMETERS.
- ALL EXISTING STRUCTURE DAMAGED / DISTURBED DURING DEMOLITION / CONSTRUCTION TO BE REPAIRED TO THE SATISFACTION OF PWGSC.
- OTHER CONTRACTS MAY BE LET DURING THE PERIOD THAT THIS CONTRACT IS IN PROGRESS. COOPERATE WITH OTHER CONTRACTORS IN CARRYING OUT RESPECTIVE WORKS AND CARRY OUT ALL INSTRUCTIONS FROM THE PWGSC IN THIS REGARD. CONNECT PROPERLY AND COORDINATE WORK WITH THAT OF OTHER CONTRACTORS. IF ANY PART OF THE WORK UNDER THIS CONTRACT DEPENDS FOR ITS PROPER EXECUTION OR RESULT UPON THE WORK OF ANOTHER CONTRACTOR, REPORT PROMPTLY TO THE PWGSC, IN WRITING, ANY DEFECTS IN THE WORK OF SUCH OTHER CONTRACTORS AS MAY INTERFERE WITH THE PROPER EXECUTION OF THIS WORK.
- REMOVE EXISTING TILE FLOORS.
- REMOVE EXISTING CONCRETE STEP @ URINALS.
- MAKE GOOD CONCRETE FLOOR FROM DEMOLITION/EXCAVATION TO ACCEPT TILE FINISH.
- INSTALL 75MM INTERIOR WOOD CASING (PAINTED) AROUND ALL WINDOW / VENTILATION PANEL OPENINGS.
- INSTALL ALL APPLICABLE BLOCKING TO ACCOMMODATE FIXTURES, ACCESSORIES, WASHROOM PARTITIONS, CURTAIN TRACKS, AND MILLWORK.

LEGEND:

- EXISTING DOOR
- NEW DOOR / NUMBER
- EXISTING DOOR TO BE REMOVED
- ROOM NUMBER
- NOTE (REFER TO NOTES THIS SHEET ONLY)
- WALL TYPE REFERENCE
- HD ELECTRIC HAND DRYER
- SD SOAP DISPENSER
- M MIRROR
- CH COAT HOOK
- GB GRAB BAR
- SND SANITARY NAPKIN DISPOSAL
- TTD TOILET TISSUE DISPENSER
- WR WASTE RECEPTACLE (WALL MOUNT)
- GWB(P.T) GYPSUM WALL BOARD "GREENBOARD" PAINTED
- FD FLOOR DRAIN
- WH HOT WATER TANK
- FS FOLDING SEAT
- BCS BABY CHANGE STATION

LEGEND

- CEILING MOUNTED FLOURESCENT LIGHT FIXTURE
- CEILING MOUNTED RECESSED FORCED FAN HEATER,
- CEILING MOUNTED INCANDESCENT LIGHT FIXTURE
- EMERGENCY LIGHTING BATTERY UNIT WITH TWO HEADS
- CEILING OR WALL MOUNTED EXIT LIGHT
- MOTION DETECTOR LIGHT SWITCH
- CEILING MOUNTED MOTION DETECTOR LIGHT SWITCH
- SINGLE OR DOUBLE HEADED EMERGENCY LIGHT

NOTES:

- EXISTING VENTILATION PANEL TO BE PAINTED; COLOUR TO BE SELECTED.
- WALL TYPE "A" THROUGHOUT. SEE FINISH SCHEDULE A04 (SERVICE ROOM NOT INCLUDED).
- TILE FINISH NOT PRESENT IN THIS AREA.



| | | |
|----|-------------------|------------|
| 1. | ISSUED FOR TENDER | 2016/03/04 |
|----|-------------------|------------|

| | |
|-----------|------|
| revisions | date |
|-----------|------|

project
 WASHROOM BUILDING
 RECAPITALIZATION
 BUILDING 32, 34, & 38
 NEWMAN SOUND CAMPGROUND
 TERRA NOVA
 NATIONAL PARK, NL

drawing no. / dessin no.

REFLECTED CEILING PLAN
 & SCHEDULES
 BUILDING #32,34
 &38

designed / conçu

date 2015/3/23

drawn / dessiné

date 2015/3/23

approved / approuvé

date 2015/3/23

Tender / Submission

PWGSC Project Manager / Administrateur de projets TPSGC

project number / no. du projet

R-079272-001

drawing no. / no. du dessin

A- 1.05