

PART 1 - GENERAL

- | | | |
|------------------------------------|----|--|
| <u>1.1 DESCRIPTION
OF WORK</u> | .1 | In general, work of this section consists of all electrical, materials and equipment to be removed as required to perform work of Division 26 and other Divisions. |
| <u>1.2 REFERENCES</u> | .1 | Do electrical removal work in accordance with the safety standards outlined in the Canadian Electrical Code. |
| <u>1.3 DISPOSAL</u> | .1 | Owner has first right of refusal of all materials and equipment removed under work of this section. |
| | .2 | All existing equipment will be returned to the Departmental Representative at the site specified by the Departmental Representative. |
| | .3 | All materials and equipment refused by the Departmental Representative will become the property of the Contractor and will be removed from site. |

PART 2 - PRODUCTS

Not Applicable

PART 3 - EXECUTION

- | | | |
|---------------------------------|----|--|
| <u>3.1 GENERAL
REMOVALS</u> | .1 | Remove obsolete wiring and devices as indicated. |
| | .2 | Remove all existing materials or equipment to allow installation of new construction. |
| | .3 | Coordinate work of this section with general building removals and with architectural construction. |
| | .4 | Be responsible for the removal or relocation of electrical equipment affected by construction of other trades. |

PWGSC
Atlantic Region
Renovations to AAFC Lab
Bldg 25, SJRDC, St. John's, NL
Project No. R078141.001

ELECTRICAL REMOVALS

Section 26 05 02
Page 2

March 2016

3.1 GENERAL
REMOVALS
(Cont'd)

- .5 Schedule all removal of work with the Departmental Representative. Do not disrupt plant operations except as permitted by the Departmental Representative.