

PART 1 - GENERAL

- 1.1 USE OF SYSTEMS .1 Use of new and or existing permanent heating and or ventilating systems for supplying temporary heat or ventilation is permitted only under following conditions:.
- .1 Entire system is complete, pressure tested, cleaned, flushed out.
 - .2 Building has been closed in, areas to be heated/ventilated are clean and will not thereafter be subjected to dust-producing processes.
 - .3 There is no possibility of damage.
 - .4 Supply ventilation systems are protected by 60 % filters, inspected daily, changed every week 2 weeks or more frequently as required.
 - .5 Return systems have approved filters over openings, inlets, outlets.
 - .6 Systems will be:
 - .1 Operated as per manufacturer's recommendations and instructions.
 - .2 Operated by Contractor.
 - .3 Monitored continuously by Contractor.
 - .7 Warranties and guarantees are not relaxed.
 - .8 Regular preventive and other manufacturers recommended maintenance routines are performed by Contractor at own expense and under supervision of Departmental Representative.
 - .9 Refurbish entire system before static completion; clean internally and externally, restore to "as- new" condition, replace filters in air systems.
- .2 Filters specified in this Section are over and above those specified in other Sections of this project.
- .3 Exhaust systems are not included in approvals for temporary heating ventilation.

PWGSC
Atlantic Region
Renovations to AAFC Lab
Bldg 25, SJRDC, St. John's, NL
Project No. R078141.001

USE OF HVAC SYSTEMS
DURING CONSTRUCTION

Section 23 05 01
Page 2

March 2016

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.