

TO BE NOTED:

44KV SUPPLY PREFERRED LINE IS  
205-M25  
SET AUTOMATICALLY VIA TRANSFER RELAY  
SYSTEM IN CELL #11

NOTE

(67-B) DIFFERENTIAL RELAY  
INSTALLED IN CELL # 11

(27-1) UNDERVOLTAGE RELAY  
INSTALLED IN CELL # 11

(27-2) UNDERVOLTAGE RELAY  
INSTALLED IN CELL # 11

(47-T1) PHASE SEQUENCE VOLTAGE RELAY PROTECTION FOR TRANSFORMER T1  
OPERATE BREAKER 205T1-OB  
INSTALLED IN CELL # 11

(47-T2) PHASE SEQUENCE VOLTAGE RELAY PROTECTION FOR TRANSFORMER T2  
OPERATE BREAKER 205T2-OB  
INSTALLED IN CELL # 11

