

1. General

1.1 Section Includes

- 1.1.1 This section provides guidelines for the progressive, day to day cleaning of the work site as well as the final cleaning requirements by the contractor in preparation for Release of Holdback.

1.2 References

- 1.2.1 Occupational Health and Safety Act, Government of Newfoundland and Labrador.

2. Products

- 2.1 Not Used.

3. Execution

3.1 Project Cleanliness

- 3.1.1 The Contractor and its employees shall adhere to all regulations under the Occupational Health and Safety Act, Government of Newfoundland and Labrador and all regulatory bodies having jurisdiction, more stringent conditions to apply.
- 3.1.2 Maintain the Work and Work Site in a neat and tidy condition at all times, free from accumulation of waste products and debris.
- 3.1.3 Store materials and equipment to be used in the construction of the Work in a location designated for this purpose and previously agreed upon with the Departmental Representative.
- 3.1.4 Perform a daily cleanup of the site and discard all waste materials from site into the proper containers assigned for this purpose.
- 3.1.5 The supply of approved storage containers shall be by the Contractor.
- 3.1.6 The removal of filled containers to an approved landfill off-site shall be by the Contractor.
- 3.1.7 Store volatile and petroleum based waste products in covered storage containers specifically designed and approved for this purpose. All such waste to be removed from the site on a daily basis unless otherwise directed by the Departmental Representative.
- 3.1.8 Schedule and perform, in conjunction with the Departmental Representative, a weekly inspection tour of the site specifically for the task of reviewing safe storage and disposal procedures implemented. Immediately remediate any and all areas noted as being deficient or as directed by the Departmental Representative.

- 3.1.9 Use marked separate bins for recycling. Bins shall be supplied by the Departmental Representative.

3.2 Final Cleaning

- 3.2.1 When Work is Substantially Performed, remove from site all surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- 3.2.2 Remove waste products and debris other than that caused by others, and leave work and site in a clean, neat and tidy manner.
- 3.2.3 Schedule and perform, in conjunction with the Departmental Representative, a final inspection tour of the site specifically for the task of reviewing removal and disposal procedures implemented. Immediately remediate any and all areas noted as being deficient as directed by the Departmental Representative. After remediation or cleanup perform subsequent inspection with Departmental Representative in preparation for Release of Holdback.

4. Measurement and Basis for Payment

4.1 Measurement for Payment

- 4.1.1 This item will not be measured for payment.

4.2 Basis for Payment

- 4.2.1 No separate or direct payment will be made for work under this Section, which will be considered incidental to work under this Contract. Costs will be deemed to be included in the unit and lump sum prices quoted in the Schedule of Quantities and Prices.