

**Part 1 General**

**1.1 REFERENCES**

- .1 Canadian General Standards Board (CGSB)
- .2 Canadian Standards Association (CSA International)

**1.2 INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

**1.3 HOARDING**

- .1 Erect temporary site enclosures using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m on centre. Maintain fence in good repair.
- .2 Provide barriers around trees and plants designated to remain. Protect from damage by equipment and construction procedures.

**1.4 GUARD RAILS AND BARRICADES**

- .1 Provide as required by governing authorities.

**1.5 ACCESS TO SITE**

- .1 Provide and maintain access to Work.

**1.6 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for reuse and recycling.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**Part 4            Measurement and Basis for Payment**

**4.1                Measurement for Payment**

- .1        This item will not be measured for payment.

**4.2                Basis for Payment**

- .1        No separate or direct payment will be made for work under this Section, which will be considered incidental to work under this Contract. Costs will be deemed to be included in the unit and lump sum prices quoted in the Schedule of Quantities and Prices.