

Fisheries and Oceans Canada

Project #: 714114

File #FP802-160056

Wharf Construction - Dover, NL

(a) The Price per Unit and the Total Price must be entered for each Item Listed.

(b) Work included in each item is as described in the referenced specification section and project drawings.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity	Price per Unit GST/HST extra	Total Price GST/HST extra
1	03 30 00	Concrete deck	m ²	140		
2	03 30 00	Thickened slab for future jib crane	Unit	1		
3	31 23 25	Gravel fill – approach road	m ³	80		
4	31 36 19	Dredging prior to rock mattress placement	m ³	2,200		
5	31 36 19	Rock Mattress	CMPM	1,200		
6	31 53 13	Treated timber cribwork (see Note 1)	m ³	1,180		
7	31 53 16	Treated dimension timber	m ³	6		
8	31 53 16	Untreated dimension timber	m ³	14		
9	32 11 23	Class “A” granular base	m ³	40		
10	32 11 23	Class “B” granular sub-base	m ³	50		
11	35 31 24	Rock fill core –approach road	CMPM	4,000		
12	35 31 24	Filter stone (400-600kg) – approach road	CMPM	1,000		
13	35 31 24	Armour stone (4-6 tonne) approach road	CMPM	1,000		
14	35 59 29	Mooring cleats – type “A”	Unit	10		
Subtotal (Unit price Items)						
Subtotal (Lump Sum items) - see Note Below:						

TOTAL CONSTRUCTION COST:	
---------------------------------	--

NOTE:

1. Canada will supply the following timber for this project (to be picked-up by the Contractor at DFO's warehouse located in 121 Glencoe Drive, Mount Pearl, NL):
 - **550 pieces of 200mm X 200mm crib timbers at 6.1m lengths. Note that the crib timbers supplied by Canada is not a complete list of crib timber required to complete the work.**
 - **240 pieces of 100mm X 150mm fenders at 3.6m lengths. Note that the fenders supplied by Canada is not a complete list of fenders required to complete the work.**

2. Lump sum items include all items required to complete the project in accordance with the drawings and specifications (which are not measured for payment), including, but not limited to:
 - Mobilization/demobilization
 - Demolition
 - Inspector's room and board
 - Scour protection on rock mattress
 - Provisions for electrical
 - Other/contingency/unknowns