



The **Lump Sum** amount in **Section 13. COMBINED PRICE SCHEDULE** page 4 of 5 of the **Construction Tender Form** is to include:

- Mobilization and Demobilization
- Removal of existing wheel guards, mooring cleats, reinforced concrete wharf deck, wood decking, wood support beams, coping, horizontal Wales, vertical closed face fenders as shown on drawings and dispose off site.
- Removal of existing wood cross bracing including bolting system as shown on drawings and remove from site.
- Removal of existing steel angle cross bracing and steel bracket as shown on drawings and dispose off site.
- Remove existing rubber tires and attachments and reattach at new location as shown on drawings.
- Remove existing mooring rings and reinstall as shown on drawings.
- Installation of new concrete wall as shown on drawings.
- Supply and installation of bollards (Two Types) as indicated on construction drawings.
- Temporary support for the Existing electrical panel, existing electrical conduits and utility pole.