

PART 1 - GENERAL

- |   |  |
|---|--|
| <u>1.1 SECTION<br/>INCLUDES</u>           | .1 Barriers.   |
|   | .2 Traffic Controls.   |
| <u>1.2 INSTALLATION<br/>AND REMOVAL</u>   | .1 Provide temporary controls in order to<br>execute work expeditiously.   |
|   | .2 Remove from site all such work after use.   |
| <u>1.3 HOARDING</u>                       | .1 Erect temporary site enclosure using new<br>1.2 m high snow fence wired to rolled steel<br>"T" bar fence posts spaced at 2.4 m centres.<br>Provide one lockable truck gate. Maintain<br>fence in good repair. |
| <u>1.4 GUARD RAILS<br/>AND BARRICADES</u> | .1 Provide secure, rigid guard rails and<br>barricades around open excavations.  |
|   | .2 Provide barricades along wharf structure when<br>wheelguard is removed.   |
|   | .3 Provide as required by governing authorities.   |
| <u>1.5 ACCESS TO SITE</u>                 | .1 Provide and maintain access to adjacent<br>harbour facilities.  |
| <u>1.6 PUBLIC<br/>TRAFFIC FLOW</u>        | .1 Provide and maintain competent signal flag<br>operators, traffic signals, barricades and<br>flares, lights, or lanterns as required to<br>perform work and protect the public.                                |
| <u>1.7 FIRE ROUTES</u>                    | .1 Maintain access to property including   |

Wharf Construction  
Harbour Breton, NL  
R.081991.001

overhead clearances for use by emergency  
response vehicles.

1.8 PROTECTION FOR  
OFF-SITE AND PUBLIC  
PROPERTY

- .1 Protect surrounding private and public  
property from damage during performance of  
work.
- .2 Be responsible for damage incurred.