
**Washroom Buildings Recapitalization
Buildings 32, 34 & 38
Newman Sound Campground
Terra Nova National Park, NL
Proj. No.: R.079272.001**

Addendum No. 1

Page 1 of 3

PART 1 SPECIFICATION

- .1 Reference Specification Section 08 11 14 – Metal Doors and Frames;
 - .1 Delete Section 08 11 14 – Metal Doors and Frames and replace with new Section 08 11 14 – Metal Doors and Frames attached to this addendum.
- .2 Reference Specification Section 08 71 10 – Door Hardware – General;
 - .1 Delete Section 08 71 10 – Door Hardware – General and replace with new Section 08 71 10 – Door Hardware – General attached to this addendum.
- .3 Reference Specification Section 10 21 20 - Solid Plastic Toilet Partitions;
 - .1 Delete Section 10 21 20 - Solid Plastic Toilet Partitions and replace with new Section 10 21 20 - Solid Plastic Toilet Partitions attached to this addendum.
- .4 Reference Specification Section 10 28 00 Toilet and Bath Accessories;
 - .1 Delete Section 10 28 00 Toilet and Bath Accessories and replace with new Section 10 28 00 Toilet and Bath Accessories attached to this addendum.

PART 2 DRAWINGS

- .1 Reference Drawing A-1.05 – Reflected Ceiling Plan & Schedules, Buildings 32, 34 and 38;
 - .1 Delete Drawing A-1.05 – Reflected Ceiling Plan & Schedules, Buildings 32, 34 and 38 and replace with new Drawing A-1.05 – Reflected Ceiling Plan & Schedules, Buildings 32, 34 and 38 attached to this addendum.
- .2 Reference Mechanical Drawing M-1 – Existing and New Floor Plan Building #32, #34 & #38 – Plumbing Layout;
 - .1 Demolition notes to be revised to read as follows:

“Note 10. Existing tempering valve to be replaced.”
 - .2 General notes to be revised as follows:

“Note 1: All hot, cold and tempering water piping to be sloped back to water entry point to allow complete drawing of plumbing system for winter shut down. Contractor to include all necessary drain valves and vent valves to accommodate this and be able to demonstrate the process during final commissioning or handover.”

**Washroom Buildings Recapitalization
Buildings 32, 34 & 38
Newman Sound Campground
Terra Nova National Park, NL
Proj. No.: R.079272.001**

Addendum No. 1

Page 2 of 3

“Note 2: Provide drain and vent valves, as many as required, to facilitate winter shut down as noted in note 1.”

.3 Mechanical Drawing M-2 Existing and New Floor Plan Building #32, #34, & #38
– Propane & Ventilation Layout;

1. Delete reference to CO2 valve, and provide propane shut off valve.

2. New Propane Notes to be revised as follows:

“Note 1: Propane Contractor shall install two 420lb cylinders on a concrete pad as shown c/w high pressure regulator and associated piping. Cylinders to be supplied by Propane Utility in coordination with the owner/ TN Park.”

3. New Ventilation Notes to be revised as follows:

“Note 1: Existing Fans, Ductwork, & Wall Cap c/w Birdscreen to be replaced. Thermally insulate rigid ductwork. Paint wall cap to match final siding color. New Fans to be equal to F-1 as indicated on M-3.”

“Note 2: Existing Fans, Ductwork, & Wall Cap c/w Birdscreen to be replaced. Thermally insulate rigid ductwork. Paint wall cap to match final siding color. New Fans to be equal to F-1 as indicated on M-3.”

.3 Reference Mechanical Drawing M-3 Plumbing Schedules and Details

.1 See attached sketch MSK-1 for revised Plumbing Schedules.

.4 Reference Mechanical Drawing M-5 Plumbing Schedules and Details

.1 Delete detail 2/M-5. Propane piping shall be ran above grade to building c/w adequate support and blocking to fully secure piping.

.5 Reference Electrical Drawings

.1 In EACH building, Electrical contractor to supply and install one each 120V, 15A circuit c/w breaker and wiring in conduit to provide power to the controls transformer that services the shower control valves. Controls transformer to be located in the service room or similar location. Coordinate with the Mechanical Trade onsite.

**Washroom Buildings Recapitalization
Buildings 32, 34 & 38
Newman Sound Campground
Terra Nova National Park, NL
Proj. No.: R.079272.001**

Addendum No. 1

Page 3 of 3

PART 3 ATTACHMENTS

- .1 Section 08 11 14 – Metal Doors and Frames
- .2 Section 08 71 10 – Door Hardware-General
- .3 Section 10 21 20 - Solid Plastic Toilet Partitions
- .4 Section 10 28 00 Toilet and Bath Accessories
- .5 A-1.05 – Reflected Ceiling Plan & Schedules, Buildings 32, 34 and 38
- .6 MSK-1 – Plumbing Schedules

END OF ADDENDUM NO. 1