






- WHEELHOUSE, FOC'SLE DECK & BOAT DECK - SUBCOAT/UNDERLAY AND GOOD QUALITY COMMERCIAL CARPET, CARPET TO RUN UP BHD. APPROX. 150mm OVER A GENEROUS RADIUS COVE SECURED W/MOULDING. DETAILS OF CARPET & FIRE TEST PARTICULARS TO BE SUBMITTED TO CCG, SHIP SAFETY.
- MAIN DECK - FIRE STANDARD A-60-ISOLAMIN FLOATING FLOOR FF73-COVERED W/UNDERLAY & GOOD QUALITY COMMERCIAL CARPET. CARPET TO RUN UP BHD. 150mm OVER A GENEROUS RADIUS COVE SECURED W/MOULDING.
- VINYL ASBESTOS TILE APPROX. 3mm (1/8") THICK OVER UNDERLAYMENT. LAID W/WATERPROOF CEMENT. 100mm VINYL COVE Moulding SHALL BE APPLIED @ ALL BOUNDARIES.
- MAIN DECK - FIRE STANDARD A-60-ISOLAMIN FLOATING FLOOR FF73-COVERED W/A SUBCOAT AND VINYL ASBESTOS TILE W/100mm COVE Moulding APPLIED TO ALL BHDs.
- TROWEL APPLIED EPOXY BASE MATERIAL - DEX-O-TEX "NEOTEX" APPLIED W/GENEROUS RADIUS IN ALL CORNERS & COVERED APPROX. 100mm UP ALL BHDs.
- FIRE STANDARD A-60-INSULITE II FLOORING TROWELED TO STEEL DECK & 100mm UP BHDs. WITH TROWELED APPLICATION OF EPOXY BASE MATERIAL - DEX-O-TEX "NEOTEX" OVER.
- MAIN DECK-GALLEY - NON-SKID QUARRY TILE APPLIED OVER FIRE STANDARD A-60-INSULITE II - FLOORING ON METAL CLIPS WELDED TO STEEL DECK & 100mm UP BHDs.

NOTE - ALL SHOWER STALLS TILED



B	CONVERTED TO CAD FORMAT	SK	08-08-03
rev	description	by	date
drawing - design			
CCGS SAMUEL RISLEY			
DECK COVERING PLAN			
drawn - design		date	
		02-05-84	
checked - verify		date	
approved - approval		date	
reference - reference		scale - scale	
161-320-7		1:100	
drawing no. - no du dessin		sheet - feuille	
CNS30-117-MI		1/2	