

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 The work specified in this section comprises the provision of all plant, labour, material and equipment and the performance of all work necessary for mobilization/demobilization to and from the work site.
- .2 Mobilization shall include transportation to the site of contractor's plant, labour, material and equipment in readiness to start the work all in accordance with the approved work schedule.
- .3 Demobilization shall include final site cleaning and transportation from the site of contractor's plant, labour, material and equipment at the completion of the required work.
- 1.2 SCHEDULE OF WORK .1 No work can commence on site until September 6th, 2016. The Contractor shall utilize time between contract award and on-site mobilization to have all submittals reviewed and returned and materials ordered and shipped to coincide with mobilization or as needed to respect the project schedule.
- 1.3 MEASUREMENT FOR PAYMENT .1 Include all costs for Mobilization/Demobilization in Lump Sum portion of the work on the Bid and Acceptance Form.