

DRAWING NOTES: (X)

- 1. EXISTING FIRE ALARM PANEL EST QUICKSTART. PROVIDE PROGRAMMING AND VERIFICATION UPON JOB COMPLETION. UPDATE M-1 FIREWORKS TO REFLECT ALL CHANGES.
- 2. PROVIDE DCL CLASS A LOOP TO ELEVATOR MACHINE ROOM AND TIE INTO CONTROLLER. KEEP 1200mm SPACE IN BETWEEN LOOP CONDUITS.
- 3. PROVIDE SMOKE DETECTOR ON EACH FLOOR, ON TOP OF ELEVATOR SHAFT AND IN ELEVATOR MACHINE ROOM. CONNECT ALL NEW DEVICES TO NEW CLASS A LOOP.
- 4. PROVIDE CORE DRILL AND RUN CONDUITS AND WIRING TO FORM THE COMPLETE CLASS A LOOP. SEAL OPENINGS UPON JOB COMPLETION.

ASPM 11x17

| Indicated Research Council Connoise Administrative Services and Property Idenogement Brunch | Indicated Research Council Connoise Administrative Services and Property Idenogement Brunch | Indicated Research Council Connoise | Indicated Research Council Cou