



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions
Travaux publics et Services gouvernementaux
Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Sikanni Remediation & Relocation	
Solicitation No. - N° de l'invitation EZ897-170083/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client	Date 2016-06-01
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-7791	
File No. - N° de dossier PWY-6-39018 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-06-13	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 658-2755 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC - Sikanni Maintenance Camp - km 254 Alaska Highway, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ897-170083/A
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
004
File No. - N° du dossier
pwy-6-39018

Buyer ID - Id de l'acheteur
pwy019
CCC No./N° CCC - FMS No/ N° VME

Les documents français seront disponibles sur demande.

This Solicitation Amendment 004 is raised to extend the bid closing date, to incorporate Questions & Answers received to date, and to amend the wording of Article SI04 in the Invitation To Tender document.

Extension of Time

**Sikanni Remediation & Building Relocation
– Sikanni Maintenance Camp, Alaska Highway, BC**

Solicitation No: EZ87-170083/A

Notice is hereby given that the time for reception of tenders previously due at
2:00 p.m. P.D.T. on June 7, 2016 is hereby extended to
2:00 p.m. P.D.T. on June 13, 2016.

NOTE TO BIDDERS: Use the mailing label below and affix it securely to the outside of the envelope or package containing your bid. For revisions to bids submitted by facsimile (fax # (604) 775-9381), use this sheet as the cover sheet. Always ensure your company name, return address, tender number and closing date appear legibly on the outside of your bid submission.

**REAL PROPERTY CONTRACTING
Public Works & Government Services Canada
Room 219 - 800 Burrard Street
Vancouver, B.C. V6Z 0B9**

Requisition No.: EZ897-170083/A
Tender Closing Date & Time: June 13th, 2016 @ 1400 P.D.T.
Project Description: Sikanni Remediation & Building Relocation
– Sikanni Maintenance Camp, Alaska Highway, BC

KN

Q1: Are the bids evaluated based on the combined price of the Base Work and the Optional Work, even though the Optional Work may not be awarded?

A1: Yes.

Q2: Can the Contractor charge for the mobilization, demobilization, and site facilities provision line items in the Optional Work if the Optional Work is continuous with the Base Work and no mobilization, demobilization, or new site facilities are incurred?

A2: No.

Q3: Is it possible that a portion of the Optional Work would be completed this year and the balance completed next year (with a break in between)?

A3: Yes.

Q4: Does the Sep 15 date referred to in the Specifications (eg Section 01 32 16.07 1.6.2) apply only to the Base Work and not the Optional Work?

A4: Yes.

Q5: Does the Unit Price item for addressing Hazardous Building Material (HBM) Concerns apply only to HBM identified in the Appended reports?

A5: Yes. If additional HBM are encountered that must be addressed as part of the building move then these would be subject to a Change Order. Note that the intent is not to remove all HBM.

Q6: Is the Contractor responsible for removing and moving the unattached contents of the Maintenance Garage?

A6: No. All loose tools, equipment, and furniture will be removed by others prior to the work commencing. Note that fixtures, siding, insulation, and the door and associated mechanism are part of the move.

Q7: The oil-water separator at the new Maintenance Garage is not shown on the drawings; is it the responsibility of the Contractor to design and place this?

A7: Yes.

Q8: Is the backfilling for the new location of the Maintenance Garage to be brought up to existing grade?

A8: Yes.

Q9: There are several sources of backfill; where are they and will they be placed in any specific order?

A10: The location of the available backfill will be provided by the Departmental Representative and the Departmental Representative will determine the order in which the backfill is to be placed.

Q11: Are there known places to patch the biocell?

A11: No, the biocell patches are to be made available as a contingency.

Q12: Does the biocell need preparation work.

A12: Yes. In addition to patching any holes discovered, the bedding sand needs to be levelled and covered with plywood prior to placing contaminated soil.

Q13: What is the thickness of the biocell liner that may need to be patched?

A13: the liner is 40 mil.

Q14: Is there presently any contaminated soil in the biocell?

A14: No, there is no contaminated soil in the biocell prior to work. Currently there is approximately 30 cm of bedding material on top of the liner.

Q15: Will the AST tanks being moved in line item 11 be emptied by the owner prior to moving?

A15: Yes, the tanks will be emptied before the contractor has to move them.

On page 4 of 28 in the Invitation To Tender document, under Article SI04 – MANDATORY SITE VISIT;

DELETE: Bidders who have not signed the attendance sheet will not considered non-compliant.

INSERT: **Bidders who have not signed the attendance sheet will be considered non-compliant.**

All other terms and conditions remain unchanged.