

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 51 00 – Temporary utilities
- .2 Section 01 52 00 – Construction facilities
- .3 Section 01 56 00 – Temporary barriers and enclosures
- .4 Section 01 74 11 – Cleaning
- .5 Section 01 74 21 – Construction-demolition waste management and disposal

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.3 SITE FENCE

- .1 Raise a temporary tough, resistant and well attached security fence of 1.83m high (6') around the site and all works and storage areas.
- .2 For each of the fenced areas, provide a pedestrian access route that can be locked. Provide locks/padlocks and keys for access routes. Give three (3) copies of each key to the Departmental Representative.
- .3 About thirty (30) "New Jersey" type concrete barriers of approximately 4 meters long, topped by posts and a chain link fence with an approximate height of 1.2 meters will be available. See Appendix 4 for a picture of assemblies.
- .4 The *barriers* will be provided free of charge by the Departmental Representative but the Contractor shall receive them at the site and mount them around the site. At the end of the project, or at the request of the Departmental Representative, the Contractor shall dismantle the site fence and place the assemblies at the same place where he received them at the beginning of the project.
- .5 The Departmental Representative cannot confirm the exact quantity of barriers available for the project. If he wishes to use them, the Contractor will confirm the quantity available onsite.
- .6 If the quantity of *barriers* available and provided by the Department is insufficient to effectively delimit the whole area, the Contractor shall, at his own expense, place an order, install, maintain and dismantle the temporary fencing.

1.4 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around deep excavations or others.
- .2 Provide as required by governing authorities.

1.5 ACCESS TO SITE

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work, ensure maintenance and dismantling at the end of the project.

1.6 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect public.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 ACCESS TO BUILDINGS

- .1 Ensure free public access to buildings adjacent to the project area, especially to the Marinard plant and La Marinière fish shop.
- .2 Do not obstruct or restrict deliveries and shipments for the Marinard plant through its Northeast access point. Entry through that route should be free at all times.

1.9 PROTECTION OF SURROUNDING PUBLIC AND PRIVATE PROPERTIES

- .1 Before work begins, carry out a joint inspection with the Departmental Representative and the Contractor to identify and list all existing damage to public and private properties. Take photographs to serve as records.
- .2 Protect surrounding public and private properties against any damage that could occur as a result of works.
- .3 Pay particular attention to the protection of finished surfaces of buildings close to the project site. Provide screens, tarpaulins and barriers needed for protection.
- .4 Pay particular attention to the protection of the asphalt covering of access routes and parking lots.
- .5 If necessary, take full responsibility for damages.
- .6 Identify public services, protect them and take responsibility for damages due to the lack of protection or inadequate protection.
- .7 Take full responsibility for damages to the structures due to the lack of protection or inadequate protection.

1.10 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse/recycling or elimination in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 NOT USED

.1 Not used.

Part 3 Execution

3.1 NOT USED

.1 Not used.

END OF SECTION