

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 74 21 – Construction-demolition waste management and disposal
- .2 Section 02 41 16.01 – Structure demolition – short form

1.2 REFERENCES

- .1 Not used.

1.3 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, including that caused by subcontractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Clear snow and ice from access to construction site, bank/pile snow in designated areas only and remove from site if required.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris.
- .6 Provide and use marked separate bins for recycling. Refer to Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .7 Eliminate waste materials outside of the construction site according to the regulations.
- .8 Store volatile waste in covered metal containers, and remove from premises at end of each working day.

1.4 SEA BED CLEANING

- .1 Sea bed cleaning must be done before dredging's activities.
- .2 An inspection of the sea bed was realized in 2015. During this inspection, divers' team listed several waste reposing on the sea bed who must be removed before the dredging.
- .3 The inspection of the sea bed in 2015 was made on a distance of 15 meters from the existing quay by following the axes of piles. More than 165 locations containing waste material was found. The objects found containing reinforcing bars, steel cables, rope, few defenses of quay (tire or tubular), some wood, sheets of steel and others
- .4 For informational purposes, the appendix 5 presents a summary of waste listed in 2015. This summary is not restrictive and other articles could be there.
- .5 Eliminate waste materials from sea bed cleaning outside of the construction site according to the regulations.

- .6 Remove waste materials from sea bed cleaning at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.

1.5 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris including that caused by subcontractors.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .8 Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds.
- .9 Remove dirt and other disfiguration from exterior surfaces.
- .10 Remove snow and ice from access to building.

1.6 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse/recycling or elimination in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION