

Solicitation No. - N° de l'invitation
EQ447-170175/A

Client Ref. No. - N° de réf. du client
R.013137.006

Amd. No. - N° de la modif.
005

File No. - N° du dossier

Buyer ID - Id de l'acheteur
pwl012

CCC No./N° CCC - FMS No/ N° VME

Attachment 15

Question and Answer

Q1: I confirmed with MTO that we are not allowed to haul soaking wet material on the road. The specification calls for us to directly load material .5 meters below the ground water. This material will have to be stockpiled on site with other "dry" material and manipulated to let the water drain from the pile, prior to any hauling off site. In addition the landfills will not accept soaking wet contaminated soil.

A1: The contractor can stockpile the wet and dry soils from "smear zone" area and allow them to drain back into the excavation prior to disposal off site. Alternatively, the contractor could add stabilizer (i.e. sawdust or equivalent) to reduce the saturation in the soil, if required. Any costs associated should be added into the Lump Sum Amount.