

FUEL STORAGE AND DISPENSING SYSTEM

1. ALL CONSTRUCTION AND MATERIALS TO BE IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, SPECIFICATIONS AND AS SHOWN ON THESE DRAWINGS.
2. PERFORM WORK IN ACCORDANCE WITH THE MOST RECENT EDITIONS OF: NATIONAL BUILDING CODE, NATIONAL FIRE CODE, CCME, CEPA AND CAN/CSA-B139, STORAGE TANK TO CAN/ULC-5001-14.
3. CEPA REGULATIONS REQUIRE ALL PETROLEUM INSTALLATION AND DECOMMISSIONING TO BE COMPLETED BY A CERTIFIED PETROLEUM INSTALLER REGISTERED IN THE PROVINCE OF SASKATCHEWAN.
4. LOCATION OF ALL EXISTING SERVICES, FEATURES AND APPURTENANCES SHOWN ON THE DRAWINGS ARE TO BE CONSIDERED APPROXIMATE ONLY. VERIFY ALL LOCATIONS IN THE FIELD PRIOR TO CONSTRUCTION.
5. CONTRACTOR TO OBTAIN ALL REQUIRED PERMITS.
6. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND CO-ORDINATING THE VARIOUS PARTS OF THE WORK.
7. DISPOSE OF ALL EXCAVATED MATERIAL UNSUITABLE FOR REUSE AT A SUITABLE OFF-SITE DISPOSAL AREA, IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS.
8. ANY DAMAGE TO EXISTING SERVICES OR UTILITIES SHALL BE REINSTATED TO AS-FOUND OR BETTER CONDITION.
9. ALL SITES AFFECTED BY CONSTRUCTION SHALL BE RESTORED TO AS FOUND OR BETTER CONDITION.
10. CAREFULLY RELOCATE EXISTING LANDSCAPE FEATURES AND SITE FEATURES TO ACCOMMODATE CONSTRUCTION WORK. ALL SUCH ITEMS SHALL BE REPLACED TO ORIGINAL OR BETTER CONDITION, TO THE APPROVAL OF THE CONTRACT ADMINISTRATOR.
11. ALL DEBRIS AND EQUIPMENT FROM DEMOLITION AND CONSTRUCTION TO BE DISPOSED OF AT AN OFFSITE LOCATION APPROVED BY THE CONTRACT ADMINISTRATOR.

drawing index			
title	dwg no.	rev.	sht no.
COVER SHEET	G101	2	1
SITE PLAN, TANK AND PIPING DETAILS	M101	2	2
ELECTRICAL	E101	2	3