



**Addendum / Addenda**

No./N<sup>o</sup>  
2

Project Description / Description de projet <b>NRC Uplands - Building U89B Utility Supply Upgrade</b>		
Solicitation No./ No de sollicitation <b>16-22027</b>	Project No./N <sup>o</sup> de projet <b>4056</b>	W.O. No./N <sup>o</sup> d'ordre de travail <b>A1-005791</b>
Departmental Representative / représentant ministériel <b>Mark O'Connor</b>		Date <b>June 14, 2016</b>
<b>Notice:</b> This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.		<b>Nota:</b> Cet addenda fait partie intégrale des dossiers d'appel d'offres; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.

**DESCRIPTION OF WORK**

1. Refer to drawing 4056 – E05 Note 12: The note has been changed from 4x(3/C – 500MCM 600V, AIRGUARD, CU) cables to 4x(4/C - 500MCM 600V, AIRGUARD, CU) cables. Refer to attached drawing.
2. In specification Table of Contents delete reference to cabinet section 260531.
3. Specification Section 260527. Delete specification parts indicated below:
  - a. Part 3.5
  - b. Part 3.3.3
  - c. Part 3.2.4
4. Specification Section 260527. Modify Part 3.3.1 as indicated below:
  - a. Install grounding connections as indicated to typical station equipment including: Non current carrying parts of: transformers and current transformers. Cable sheaths, raceways, pipe work, screen guards, switchboards, potential transformers. Meter and relay cases. Any exposed building metal, within or forming part of station enclosure.
5. Clarification/Response to questions.
  - a. What is the volume of oil within the new 1000kVA transformer?  
The transformer contains 2182L of oil.
6. Site visit attendance attached.

END

Issued by:

  
\_\_\_\_\_  
Signature

June 14, 2016

\_\_\_\_\_  
Dated

Copies to: Christopher Day – [Chris.Day@nrc-cnrc.gc.ca](mailto:Chris.Day@nrc-cnrc.gc.ca); Derek van Gaal – [Derek.vanGaal@Stantec.com](mailto:Derek.vanGaal@Stantec.com)

4056-E05

DRAWING NOTES:



12 CONTRACTOR TO SUPPLY, INSTALL, AND TERMINATE NEW 4x(4/C - 500MCM 600V, AIRGUARD, CU) AT SECONDARIES OF TRANSFORMERS AND AT 1200A SWITCHBOARD.

\\\\CD1218-F02\\work\_group\\01-633\\active\\163302049\_NRC\_U89B\_Electrical\_Supply (DVG)\\drawing\\163302049\_3Layouts.DWG

ORIGINAL SHEET - ISO B4

June, 2016  
163302049



400 - 1331 CLYDE AVENUE  
OTTAWA, ON CANADA K2C 3G4  
www.stantec.com

Client/Project

NATIONAL RESEARCH COUNCIL  
BUILDING U89B  
SERVICE ENTRANCE UPGRADE

Figure No.

ADD2 - ESK1

Title

ELECTRICAL  
SITE LAYOUT

## Mandatory Site Visit Attendance

Project Description / Description de projet		Project No./No de projet		Closing Date		Closing time	
U89B Utility Supply Upgrade		4056		June 28, 2016		2:00 PM	
Solicitation No./N° de sollicitation		16-22027		1st Showing		June 7, 2016	
Departmental Representative / représentant		Signature		2nd Showing		June 9, 2016	
Mark O'Connor		June 13, 2016		Question Deadline		June 19, 2016	
Alternante deadline		June 13, 2016		Question Deadline		June 19, 2016	
Closing Date		June 28, 2016		Closing Date		June 28, 2016	
Showing Time		9:00 AM		Showing Time		9:00 AM	

  

COMPANY	NAME	SIGNATURE	PHONE	FAX	EMAIL
Broder Electric	Gary Morris		852-3200		gary@broderelectric.ca
Greely Construction	Ysmye Smye		822-0500		ysmye@greely.com
Fredrick Kowal	Seamus Morris		819-213-0210		F.kowal@sequimorris.com
<del>114275 Tam Inc</del>	Selva Kankarand		819-776-3939		F.kankarand@outlook.com
GALET Electric	Natana LeTouss		413 852 5403		michael@galet.ca
END OF SHOWING #1					
Black and McDonald	Ben Berner		613-979-4961		bberner@blackandmcdonald.ca
Melwood Agg	Shawn Foley		613 880 5548		Melwood @ Symphree.ca
Savant Electric	Paul J. (CAO)		613 285-3537		Paul@SavantElectric.com
Swallow Valley Const.	Sharon Best		613 223 9475		Sharon@deltaforce.ca
ARVICILITY	ISMAIL OZERDINC		613 229-2059		ismail@atautility.com
Static	Rory McCallum		613-447-0315		Rory.mccallum@hottintanec.com
Stank	Derek van Gool		613-286-7987		derek.vanpool@stank.com
TERAFLEX	Simon Gormer		613 736 6987		sgormer@teraflex.ca

