# **TECHNICAL SPECIFICATION FOR**

Installation of 33.5m MF Tower Receive Antenna System Hopedale Hill, Hopedale, Labrador 55° 27' 52" N 60° 13' 13" W Project # F6839-165008

DFO Contract # FP802-160094

Fisheries & Oceans Canada / Pêches et Océans Canada P.O.Box 5667 St. John's, Nfld. and Labrador / Saint Jean, Terre Neuve et Labrador A1C 5X1

> PROJECT NO. F6839-165008 DATE: May 2016

#### CANADIAN COAST GUARD

# **TABLE OF CONTENTS**

Section 01010	Summary of Work	Pages 1-5
Section 01300	Submittals	Pages 1-1
Section 01400	Quality Control	Pages 1-2
Section 01500	Temporary Facilities	Pages 1-2
Section 01545	Safety Requirements	Pages 1-4
Section 01561	<b>Environmental Protection</b>	Pages 1-3
Section 01600	Materials and Equipment	Pages 1-2
Section 01710	Clean Up	Pages 1-1
Section 05020	Tower Structure	Pages 1-2
Section 05121	Auxiliary Facilities	Pages 1-3
Section 05200	Dismantle Existing Tower	Pages 1-1
Section 16450	Grounding	Pages 1-3
Section 16500	Lighting and Power Supply	Pages 1-2
Section 16785	Electrical Antenna	Pages 1-2
Appendix A	Site Location Map	
Appendix B	Drawings	
Appendix C	Site Survey	
Appendix D	Existing MF Tower Information	
Appendix E	Site Photos	
Appendix F	List of Materials Supplied by CCG	

**Summary of Work** 

Project: F6839-165008

### 1.0 General

The work covered under this project consists of the **installation** of a MF Broad Band MF Tower Antenna System for the CCG at the **Hopedale Hill, Hopedale, Labrador** site. A **33.50 m MF Broad Band MF Tower Transmit Antenna System** has been designed and fabricated (See Appendix B). Additionally, civil work completed includes installation of tower base, guy anchors, antenna anchors and grounding rods as per attached drawings in Appendix C.

Work for this contract shall include but not be limited to the following:

- Installation of a **33.50 m MF Broad Band MF Tower Transmit Antenna System**, guys (structural and curtain), guy insulators, guy hardware, required antenna matching unit, base insulator, lighting system, antenna system and antenna/tower interface components. Refer to general arrangement and site layout drawings in Appendix B.
- CCG will supply the tower system, anchors, antenna tuning unit and ground screen materials for this site (see Appendix F). Materials will be available in Hopedale, Labrador.
- Tower and anchor layout in accordance with approved engineering drawings. Actual layout shall be subject to the approval of Owner prior to commencement of any work.
- Installation of the antenna tuning system (curtain guys) including transmission lines, in accordance with the manufacturer's instructions and specifications. Contractor is responsible to interface appropriately, the antenna systems and transmission lines to the tower.
- Installation of auxiliary facilities such as ladders, safety rails, ice guards, ATU Enclosure, and platforms.
- Design, installation and supply of an approximately 115m long above ground cable tray from transmitter building to antenna. Installation to meet all applicable standards including the Canadian Electrical Code.
- Contractor shall be responsible for checking all material against the material list and protection of the material until it is installed and accepted by Owner.
- Contractor will be responsible for arranging all snow clearing requirements as necessary. Snow clearing will be based on actual rates and in addition to base bid costs.
- Transportation of all materials and equipment to the site as required.
- Contractor shall be responsible for the dismantling of existing tower refer to Section 05200.
- All materials used on this project are to be of specification grade, meaning complete dimensional, manufacturing, technical/engineering specifications and standards information must be available for all materials to ensure "fit for use" compliance.
- Contractor is to receive all materials for the project on behalf of the Owner as required and to ensure and be responsible for safe keeping until completion inspection.
- Clean up of site following completion of all work.

• Tuning and testing of MF-RX Antenna System not part of this contract.

#### 2.0 <u>Definitions</u>

"Owner" means: Fisheries and Oceans Canada, Canadian Coast Guard (CCG)

"Engineering Consultant" means: for this project, to be determined at a later date.

#### 3.0 Existing Site

- 3.1 The Contractor should note that this site is owned by NavCanada and is on the site of existing operational towers. Refer to site surveys appended to this Specification for location of existing facilities, property boundaries and new tower location.
- 3.2 Before tendering the Contractor should familiarize themselves with the remote location, scope of work, site restrictions, short construction season and temporary measures required to complete work as specified. No after claim will be allowed for any work or material necessary for proper execution and completion of the contract.
- 3.3 Site is located at 55° 27' 52" N (latitude) and 60° 13' 13" W (Longitude), at the existing NavCan site at **Hopedale Hill, Hopedale, Labrador**. This site is 106m above sea level. Refer to Appendix A for site location.
- 3.4 Any dimensions given in this Specification or appended drawings are approximate and are for guidance only. Exact dimensions and layouts to be determined by the Contractor in the field.
- 3.5 Rock anchor foundations for proposed 33.5m MF all-weld guyed communication tower will be in place. This includes tower base, guy anchors, antenna anchors and grounding rods refer to Appendix B.

### 4.0 <u>Contractor Qualifications</u>

- 4.1 All work to be carried out by a qualified contractor with proven experience completing projects of similar nature.
- 4.2 Site foreman to have a minimum of 5 years' experience working on projects of similar nature.
- 4.3 Submit details of contract quote as per tender submission required in section 1300.

#### Summary of Work

Project: F6839-165008

#### 5.0 <u>Site Access</u>

5.1 Normal site access is by 2WD on 2Km gravel from the town. Winter access is by snowmobile or helicopter. Access to the site should be arranged by contacting the Owner. Contractor is responsible for access to the proposed tower location. This involves the construction of a suitable construction access road to base and anchor locations and a 14 m X 14 m tower compound.

#### 6.0 <u>Completion Schedule</u>

- 6.1 All work on this contract shall be completed within the time indicated in the tender document.
- 6.2 Tender submission shall include a schedule of all Contractors activities including transportation and installation. Installation to be completed by September 30, 2016.

#### 7.0 <u>Existing Site Conditions</u>

- 7.1 Contractors should note that there are restrictions at this location with regard to:
  - access to current site
  - the available space
  - location of cable trenches
  - location of overhead power conductors
  - location of buildings
  - location of other substation equipment

It shall be the Contractor's responsibility to locate and protect all buried cables and other underground or overhead structures. Any damage to such structures shall be the responsibility of Contractor. Where unknown services are encountered Contractor to log location and advise Owner immediately.

#### 8.0 Work Commencement

- 8.1 Contractor is to **provide an updated detailed schedule and** commence work immediately upon award of contract and after review and approval of all submittals.
- 8.2 The weather conditions, short construction season and site remoteness may require the use of longer work days and additional work force to complete the project within the scheduled completion date.

8.3 The Contractor is to make every effort to ensure sufficient material and equipment is delivered to site at the earliest time possible upon award of the contract.

#### 9.0 <u>Site Operations</u>

- 9.1 Arrange for sufficient space adjacent to project site for conduct of operations storage of material etc. Exercise care so as not to obstruct or damage public or private property in area. Do not interfere with normal day-to-day operations at site. All arrangements made for space, access and security shall be made by the Contractor.
- 9.2 At completion of work restore area to its original condition. The Contractor must repair damage to ground and property. Remove all construction materials, residue, excess etc., and leave site in a condition acceptable to Owner.

#### 10.0 <u>Project Meetings</u>

- 10.1 Owner will arrange and give notice of all project meetings. Contractor is responsible for any expenses related to attending these meetings.
- 10.2 All project meetings will take place at site of work unless otherwise directed by the Owner.
- 10.3 Prior to commencement of work there will be a Project "Kick-Off" Meeting. The Contractors Project Manager (at their own expense), the Owner and the Engineering Consultant will be in attendance. The meeting will be held in St. John's, NL.

Data and an agenda will be distributed prior to the meeting and the following agenda discussed at the initial meeting;

- Introduction of all key personnel participating in the meeting and the project and names of responsible individuals.
- Establishing limits on work hours, access, movements, security on site, etc.
- Organizational arrangement of the contractor's forces and personnel as well as those of the sub-contractors and material suppliers.
- Chain of command, channels and procedures for communication.
- Detailed work breakdown structure (WBS) of the construction schedule, including sequence of critical work.
- Contract documents, including distribution of required copies of original documents and amendments.

- Processing of shop drawings and other data submitted as directed by the Engineer of Record.
- Processing of bulletins, field decisions, and change orders.
- Site procedures for Occupational Health and Safety, First Aid, security, quality control, housekeeping and other related matters.
- Other items as required.
- 10.4 Owner/Engineering Consultant will be responsible for recording minutes and distribution.
- 10.5 Contractor to have a responsible representative present at all job meetings and to the maximum extent possible, this should be the same person.

### 11.0 <u>Protection of Materials and Equipment</u>

11.1 Store all materials and equipment to prevent theft or damage. Repair or replace all material or equipment damaged in transit or storage to the satisfaction of and to no cost to the Owner.

### 12.0 Documents Required on Site

- 12.1 Contractor to maintain on site one copy of the following:
  - Health and Safety Plan
  - First Aid Kit
  - Contract drawings and specifications
  - Addenda
  - Reviewed shop drawings
  - Change Orders
  - Other modifications to Contract
  - Field test reports
  - Copy of approved work schedule
  - Manufactures installation and application instructions
  - Copies of tower climbers certification and qualifications
  - Contact information for Owner and Engineering Consultant
  - Tower rescue kit
  - Other items as requested

### 13.0Taxes and Permits

13.1 Contractor to obtain all Federal, Provincial and Municipal permits and pay all applicable taxes.

### 1.0 <u>Tender Submission</u>

- 1.1 The Tenderer shall include the following documentation with the tender submission:
  - a) List and description of previous projects completed which are of a similar nature.
  - b) List of subcontractors proposed complete with the work items there will be performed
- 1.2 Questions pertaining to any of the above or other items in the specification documents MUST be addressed to the Contracting Officer for this project as indicated in the Tender documents

#### 2.0 <u>Contract Technical Submission</u>

- 2.1 On acceptance of Tender, the Contractor shall submit for review:
- 2.1.1 Contractor shall submit a detailed work schedule including all project milestones. This schedule shall be maintained and updated. Each revision shall be submitted to the Owner/Engineering Consultant for review.

#### 3.0 <u>As Built Drawings</u>

3.1 Upon completion of all work, and prior to release of contract holdback, the Contractor shall issue a full set of As Built drawings, which reflect any and all changes from the original contract drawings. These drawings shall be stamped AS BUILT DRAWINGS and shall be sealed by a Professional Engineer in accordance with the requirements of this specification. Submit a full set of stamped drawings and on CD in AutoCAD format.

#### 4.0 <u>Inspection Reports</u>

4.1 The Contractor is to submit two (2) copies of all quality control test reports required by this specification immediately upon completion of testing.

#### 5.0 <u>Safety Plan</u>

5.1 The Contractor is to submit two (2) copies of their project and site specific Safety Plan, general work site safety, hazardous material safety (WHMIS), site security, public safety, etc. and emergency response plans, for review prior to commencement of work on site.

### **Quality Control**

Project: F6839-165008

Page 1

### 1.0 <u>Completion Inspection</u>

- 1.1 A completion inspection is to be carried out by the Engineering Consultant. The completion inspection does not relieve the Contractor of his responsibility to execute the work in a quality fashion as per the project specifications and industry standards. The Contractor is to inform the Owner by letter stating that the installation is completed and is ready for inspection. The Contractor shall have sufficient crew on site during the inspection to correct deficiencies identified. Contractor to advise Owner **ONE WEEK** in advance to completion of the tower to permit scheduling of this inspection.
- 1.2 The completion inspection by the Engineering Consultant will be the Owner's expense. All costs incurred by the Contractor during the acceptance inspection shall be at the Contractor's expense.
- 1.3 All work must be completed and satisfactory prior to the Engineering Consultant's completion inspection. Any deficiencies should be reported prior to the inspection teams mobilization to site. The Contractor will be responsible for the costs of all repeat completion inspections necessitated by work, which is considered by the Engineering Consultant to be incomplete or deficient.
- 1.4 Any adjustments to tension, twist or alignment shall be made by Contractor in consultation with the owner to ensure affects on signal coverage can be reviewed and monitored.
- 1.5 After any adjustment measures are carried out to the tower, the Contractor shall, as required, under the direction of the Owner, reorient any antennas.
- 1.6 An as-built tension pulse charts with actual measured guy lengths, radii and anchor elevations along with initial design guy tensions, must be provided prior to the inspection.

### **Quality Control**

Project: F6839-165008

Page 2

### 2.0 <u>Post Erection Inspection</u>

- 2.1 Not less than six (6) months and not more than one (1) year after the completion inspection, the Engineering Consultant shall re-inspect the tower. At this time the Contractor shall have a minimum crew of two present and carry out any adjustments necessary to ensure the structure meets the requirements of CSA S37- 13 standard. The posterection inspection by the Engineering Consultant will be at the Owner's expense. All costs incurred by the Contractor during the Post Erection Inspection shall be at the Contractor's expense.
- 2.2 Owner to advise Contractor at least ONE WEEK in advance of the post erection check in order to facilitate scheduling.
- 2.3 Any adjustments to the tension, twist or alignment shall be made by the Contractor in consultation with the owner to ensure affects on signal coverage can be reviewed and monitored.
- 2.4 After any adjustment measures that are carried out on the tower, the Contractor shall, as required, under the direction of the Owner, reorient any antennas.

### 3.0 <u>Conformance Letter</u>

Upon completion of the installation stage of the project the Contractor is to provide the Owner with a Conformance Certification Letter stating that the tower has been designed, fabricated and installed as per the Project Specifications.

### **Temporary Facilities**

Project: F6839-165008

### 1.0 Access

- 1.1 Access to the tower site is available as described in Section 01010. When appropriate, maintain this access during the construction period. Contractor is responsible for providing their own site office and accommodations.
- 1.2 The owner must approve any temporary roads planned. A plan for remediation must be included.
- 1.3 If authorized to use existing roads for access to the project site, maintain such roads for the duration of the Contract and make good damage resulting from Contractor's use of roads.
- 1.4 Any damages as a result of Contractor's activities to existing roadways, property, adjacent property shall be returned to original condition at Contractors expense.

### 2.0 Sanitary Facilities

- 2.1 Provide sanitary facilities for work force in accordance with regulations and ordinances.
- 2.2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

### <u>3.0</u> Power

- 3.1 Contractor to provide own temporary power during construction.
- 3.2 If connection to CCG power source is available all connections to power supply must be in accordance with Canadian Electrical Code

### 4.0 Drainage

- 4.1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- 4.2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.

4.3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements and any other applicable Federal or Provincial requirements.

#### Safety Requirements

Project: F6839-165008

#### 1.0 Summary

- 1.1 This section describes specific safety requirements to be observed and enforced during the scope of this work.
- 1.2 Inclusion of these safety requirements shall not constitute a relief of the Contractors responsibility but is a precaution against oversight and errors.
- 1.3 The Contractor is solely responsible for safety procedures necessary to, meet the requirements of these specifications and to ensure the safety of workers and the general public.

### 2.0 Construction Safety

- 2.1 The Contractor shall prepare a written project/site specific Construction Safety Plan outlining all procedures and safe work practices which must be followed by all personnel working on the construction site. This plan is to be developed in conjunction with all subcontractors who will be working on site. It is the Contractor's responsibility to become familiar with all safety laws and regulations applicable to the type of work to be undertaken. These safety laws and regulations shall be addressed in the safety plan as clear and specific safety rules, procedures and work practices. The Contractor shall ensure that all of his workers and his subcontractors, as well as any other authorized persons working or circulating in the construction work area, have been briefed and are familiar with the safety rules and measures indicated in the Safety Plan and understand that these measures are mandatory at the construction site. Regular Site Safety Meetings and daily tailgate/job assessment meetings hall be held and minuted by the Contractor.
- 2.2 Provide all workers, including sub-trades, with adequate and appropriate safety regulations prior to commencement of their duties. Ensure all workers comply with all safety regulations required by Federal and Provincial Regulations, Worker's Compensation Board and municipal statutes. Take all precautions and provide all required protection to ensure the safety of the general public and the workers in accordance with the current edition of the Occupational Health and Safety Act and Regulations such as but not limited to The Canada Labour Code, The Provincial Workers Compensation Regulations, Health and Welfare Canada Safety Code 6.

Canadian Coast Guard

Project: F6839-165008

- 2.3 In the event of conflict between any provisions of the above authorities the most stringent shall govern.
- 2.4 Provide health and safety protection required by the manufacturer's printed literature and ensure that all workers are trained in the safe use of health and safety equipment and the handling of materials. Ensure that at least one-person remains on site at all times who is properly trained in the first aid aspects required to deal with emergency situations that may arise. The safety person should be trained in the proper use of climbing harnesses and equipment.
- 2.5 A first aid station must be maintained on site, available to workers at all times.
- 2.6 Protect all utilities and services against damage or interruption. Any claims resulting from damage will be the Contractor's responsibility. The possible location of any underground cables must be established and marked prior to any excavation.
- 2.7 Post "NO SMOKING" signage where flammable materials are being used. Do not allow use of spark producing equipment during application of flammable materials. Ensure that at least one site person is trained to deal with emergency situations that may arise due to fire.
- 2.8 Take all required precautions, including those recommended by the manufacturers printed instructions, to protect persons and property, including vehicles from over-spray of materials.
- 2.9 Contractors' Safety Plan shall incorporate the following;
  - a) Continuous attachment at all times while on the tower. No unattached climbing will be permitted at any time
  - b) Use of CSA approved; full body harness, belts, lanyards, trolleys, safety hats, safety boots, and other equipment used to complete the job.
  - c) Only experienced personnel with previous training and demonstrated experience working on similar structures and heights to work on the project.
  - d) Not allowing personal to use equipment winches for transport of personnel.
  - e) The ability for any worker to discuss issues that they feel affects workers safety.
  - f) Tailgate/job assessment forms to be completed daily and made available upon request.

g) All tower climbing personel shall be properly trained in fall arrest techniques and have tower climbing certification and tower rescue training.

### 3.0 Fire Safety

3.1 Comply with the latest requirements of standard for Building Construction Operations FCC, No. 301, (Latest Edition) issued by the Fire Commissioner of Canada.

### 4.0 Falsework and Scaffolding

Design and construct all falsework as per CSA S269.1 (latest edition) and scaffolding as per CSA S269.2 (latest edition).

### 5.0 Overloading

Ensure no part of the work is subject to load(s) which endanger safety or will cause permanent deformations.

### 6.0 Signage and Barriers

- 6.1 The contractor is to maintain necessary signage to ensure workers, people accessing the site and the general public is aware of any hazards or potential hazards. Barriers are to be provided as required by regulation to ensure access to work by the general public is restricted.
- 6.2 The Safety Plan must be placed on the Construction Site in a common area visible to all workers and other persons accessing the site. All employees are to be advised of the Safety Plan. The Safety Plan shall also address the means to communicate the intent to all persons.
- 6.3 Submission of a Safety Plan to the Engineering Consultant and Owner does not relieve the Contractor of any legal obligations for the provision of construction safety as specified by Federal and/or Provincial Safety Acts or Regulations.
- 6.4 Contractor shall ensure compliance with the Safety Plan. The Owner or authorised representative reserves the right to demand removal of any person(s) not complying. Any person removed shall not be permitted reentry to the site.

6.5 Provide Safety Plan immediately upon award of contract. The Safety Plan shall be submitted to the Owner for review prior to commencement of work. Work shall not be allowed to begin until safety plan has been submitted. Revise Safety Plan as required for changes in work procedures or when directed by Owner, Safety Officer or authority.

### 7.0 Hazardous Products

- 7.1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials, and regarding labelling and provision of material safety data sheets acceptable to Labour Canada and Health and Welfare Canada.
- 7.2 Deliver copies of WHMIS data sheets to Owner on delivery of materials.
- 7.3 All data sheets must be posted on site in a common area visible to all workers and subcontractors.
- 7.4 Make all efforts to select and use materials (i.e. adhesives, solvents, cleaners etc.) for the type and nature of work being performed which are the least hazardous products available, of low VOC content or low toxicity type products and emitting low noxious odours. Select products known to be friendly to the environment and to human health. Communicate this intent to all subcontractors, suppliers and manufacturers.
- 7.5 Where the use of hazardous and toxic products can not be avoided:
  - 1) Advise Owner beforehand of the product(s) intended to be used. Submit WHMIS data sheets as per requirements above.
  - 2) Schedule in conjunction with the Owner, to carry out the work during "Off Hours" where workers and employees have left the site.

#### **Environmental Protection**

### 1.0 Summary

- 1.1 This section describes environmental protection requirements to be observed and enforced during the progress of the Work.
- 1.2 Inclusion of these environmental requirements shall not constitute a relief of the Contractor's responsibility but is a precaution against oversight or errors.
- 1.3 The Contractor is solely responsible for all environmental protection procedures deemed necessary by the Contractor to meet the requirements of these Specifications. Contractor shall comply with all applicable Federal, Provincial and Municipal regulatory requirements.
- 1.4 Contractor is fully responsible for all costs associated with required remediation occurring from contractors work on site.

### 2.0 Fires

2.1 Fires and burning of rubbish on site are not permitted.

### 3.0 Disposal of Waste

- 3.1 Do not bury rubbish or waste materials on site.
- 3.2 Do not dispose of waste or volatile materials such as mineral spirit, oil or paint thinner, into waterways, storm or sanitary sewers.

### 4.0 Pollution Control

- 4.1 Control emissions from equipment and plant to governing authorities' emission control requirements.
- 4.2 Prevent dust and debris from demolition operations and other extraneous materials from contaminating air beyond application area by providing temporary enclosures.
- 4.3 Cover or wet down dry materials and rubbish to prevent blowing dust and debris.
- 4.4 Contractor is to ensure all equipment is in good repair and no fuels or fluids are leaking from it. Equipment in disrepair will be removed

from site. Basic petroleum spill clean up equipment should be on site.

- 4.5 No maintenance, beyond that of a required daily routine nature shall be performed on equipment while on site. No refueling to be completed within 30 m of a water body.
- 4.6 No bulk storage of fuel or hazardous products will be permitted on site.
- 4.7 Work should be scheduled to avoid periods of heavy precipitation. Erosion control structures such as temporary matting, geotextile filter-fabric are to be used, as appropriate, to prevent erosion and silt runoff during the construction phase.
- 4.8 Construction waste material such as pre-treated wood must be disposed of in an appropriate manner and shall not be incinerated onsite. Construction waste material such as aluminum, steel, iron, etc. should be recycled through a metal recycler.
- 4.9 All exposed soil should be minimized by limiting the area that is exposed at any one time and by limiting the time that any one area is exposed. Stockpiled soil must be covered and/or dyked to prevent erosion or silt runoff from leaving the site.
- 4.10 All spills or leaks should be promptly contained, cleaned up and reported to the <u>CCG - Traffic Center at 709-772-2083</u> and notification given to the Project Officer handling the job.
- 4.11 Any and all stipulations of federal, provincial, or municipal authorities must be strictly followed.
- 4.12 During the constructional and operational phases of the project, limit or prohibit any activities on any of the surrounding wetland/bog (i.e. Heavy Equipment).
- 4.13 During constructional phase of the project, target areas for excavation should be limited to areas that are not considered a wetland/bog.

#### **Environmental Protection**

Project: F6839-165008

Page 3

### 5.0 Drainage

- 5.1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water at all times.
- 5.2 Do not pump water suspected of containing suspended materials into waterways, sewer or drainage systems.

### Materials and Equipment

Project: F6839-165008

### 1.0 Submittals

- 1.1 Within five working days of written request by the Owner, submit following information for any and all materials and products proposed for use:
  - name and address of all manufacturers and suppliers
  - trade name, model and catalogue number
  - performance, descriptive and test data
  - manufacturer's installation or application instructions
  - evidence of arrangements to procure
  - conformance to applicable standards

### 2.0 Supply and Use

- 2.1 Use new material and equipment unless otherwise specified.
- 2.2 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- 2.3 Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.

### 3.0 Manufacturer's Instructions

- 3.1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods.
- 3.2 Prior to use of product or material, notify Owner in writing of any conflict between these specifications and manufacturer's instructions. Owner will designate which document is to be followed.

### 4.0 Conformance

4.1 When material or equipment is specified by standard or performance specification, upon request of Owner, obtain from manufacturer and independent testing laboratory report stating that materials or equipment meets or exceeds specified requirements. Trace-ability of all materials is to be performed.

Canadian Coast Guard

#### Materials and Equipment

Project: F6839-165008

### 5.0 Substitution

- 5.1 Owner is not obligated to consider any substitutes or changes after contract award. Contractor is responsible for all costs associated with reviewing requested changes.
- 5.2 Proposals for substitution after Contract Award must include, all documentation and information required as part of this contract and statements of respective cost differences of items originally specified and proposed substitutions.
- 5.3 Should proposed substitution be accepted either in part or in whole, contractor will assume full responsibility and costs when substitution affects other work on project and pay for design or drawing changes required as result of substitution.
- 5.4 Amount of credits arising from approval of substitutions will be determined by the Owner and the Contract Sum will be reduced accordingly. No substitutions will be permitted without prior written approval from Owner.

Clean Up

Project: F6839-165008

### 1.0 Clean Up

- 1.1 Upon completion of the work, or sooner if ordered by the Owner, remove all temporary structures and clear away all rubbish, equipment, surplus and waste material remaining on or about the site, and attributable to this Contact, and place the site in a neat and tidy condition.
- 1.2 Under no circumstances will burning of construction refuse be allowed on the Owner's site. Remove all waste materials from the site to an approved dumping area as designated by local authority.
- 1.3 If the Contractor fails to clean up the site and restore to an acceptable condition, the Owner shall initiate completion of the work and deduct for same from monies due to the Contractor.

**Tower Structure** 

Project: F6839-165008

Page 1

### 1.0 General

1.1 The installation of the tower shall be in accordance with the latest version of but not limited to the codes and standards identified in Section 01010 Summary of Work and as per the detailed design tower drawings that will be provided.

### 2.0 Connections

2.1 Make all bolted connections with high strength bolts clearly marked A325 conforming to A.S.T.M. Standard Specification A325. Place a hardened washer in under the bolt element (nut or bolt head) turned in tightening the bolt. Tighten all bolts by the turn of the nut method as specified in CSA Standard S16.

### 3.0 Workmanship

- 3.1 Materials shall be handled and stored on the job site in such a manner that no damage shall be done to the materials of any existing building or structure. Special care shall be taken to ensure that galvanizing, priming, or painting is not damaged during handling and erection of materials. Storage of materials on the site will be the responsibility of the Contractor.
- 3.2 Coating Protection
- 3.2.1 The tower shall be erected in a manner that will not bend, scrape, distort, or injure the component parts of the galvanizing.
- 3.2.2 Any areas damaged during transit or erection shall be cleaned and touched up with new Zinc rich primers and/or paint as directed by the Project Engineer.

### 4.0 Tower Erection

- 4.1 Upon award of contract, Contractor is to provide a detailed Erection Plan to include the use of gin poles, winches, cranes and erection equipment.
- 4.2 The use of iron sledges for hammering or driving any members will not be tolerated. All hammering is to be done with wooden mauls or hammers of plastic, lead or other soft material.
- 4.3 Every failure of the material to join together properly shall be reported to the Owner.

#### **Tower Structure**

Project: F6839-165008

- 4.4 The Contractor shall be responsible to ensure that no members of the tower are over stressed during erection. Any members damaged during erection shall be replaced. The Contractor shall be responsible for any damages done to the work of others, or to adjoining structures and property during erection.
- 4.5 The guy tensions shall be adjusted to within +15% and -5% of the stipulated design tensions noted in the design drawings and as per the requirements of CSA S37-13. The tension calculations shall consider the ambient temperature at the time of adjustment. Full consideration of anchor location with respect to the tower base must be incorporated into the calculation of correct guy tensions. It shall be the Contractor's responsibility to obtain accurate measurements pertaining to elevation differences between the tower base and guy anchors.
- 4.6 The Contractor shall use a three-transit set up to complete final adjustment of vertical alignment and twist and to ensure it meets the requirements of CSA S37-13for vertical alignment and twist.
- 4.7 Contractor is responsible for establishing temporary obstruction lighting in accordance with Transport Canada requirements.

### 5.0 Cathodic Protection of Anchor Shafts

5.1 All anchor shafts are to be protected from deterioration and/or corrosion by a properly installed cathodic protection system designed by the Contractor. Anodes to be zinc or magnesium and to last the performance life of the tower.

### **Auxiliary Facilities**

Project: F6839-165008

### **1.0 Tower Components**

The following facilities shall be considered to be an integral part of the tower contract and shall be supplied and erected as such. In mounting any of these auxiliary facilities, care shall be taken that the structural members of the tower are not weakened by the drilling of holes or any other means.

1.1 Ladder – The tower shall be equipped with a climbing ladder (outside climb required) complete with a CSA approved fall arrest rail centered in the ladder. The ladder shall be a separate assembly bolted to the tower and shall conform to the latest version of CSA S37-13. Provide an unobstructed climbing path and maintain the required climbing radius as per CSA S37-13.

### 1.2 Ice Protection

- 1.2.1 Bonding strap from tower to tuning unit housing, the tuning unit housing and all horizontal runs of transmission lines shall be protected from falling ice in a manner approved by the Owner.
- 1.2.2 Three U-Bolt clips are to be spaced 300 mm apart, directly above the grounding connection and guy markers on each guy.

### 1.3 Turnbuckles and Shackles

1.3.1 Install all turnbuckles so as to provide a minimum of 250 mm of take-up for future adjustment. Install the locking device for each turnbuckle including turnbuckles used on broadband array (if applicable).

### 1.4 Guy (100%) Terminations

1.4.1 The Bridge sockets shall be installed so as to provide a minimum of 760 mm of take-up for future adjustment. Contractor is to provide details of other 100% terminations.

### 1.5 Anti-climb Devices

1.5.1 The tower is to be provided with a lockable, anti-climb device approved and supplied by the Owner. The Anti-climb should incorporate a framed, heavy gauge expanded wire mesh cage bolted flush to the tower face using round headed hardware that cannot be used as a step or hand hold. The panel should be 2.5 m high (minimum) with the lower edge positioned

approximately 3 m above grade. Access should be prevented from both outside and inside the tower.

- 1.5.2 The anti-climb shall be hinged on the climbing face. Operable panels shall been framed, hinged on one vertical side, with a combined latching mechanism with a lock on the opposite vertical edge. A locking mechanism requiring removable hardware such as long steel rods to open access panels is not acceptable.
- 1.5.3 For an inside climb, the anti-climb shall be accessible through a hatch door inside the structure.
- 1.5.4 The trap door in the horizontal anti-climb should easily open up to allow safe access to the tower.
- 1.5.5 Barbed wire will not be permitted as part of the anti-climb.

### 1.6 Guy Markers

Each guy shall be equipped with yellow vinyl guy markers located at the anchor end of each guy. Install such that markers extend to mark at a point 4 m above the ground.

1.6.1 Guy markers are approximately 2 m in length and vandal resistant. Field drill 25 mm holes as 200 mm spacing to render these useless for other purposes.

### 1.7 Fall Arrest

- 1.7.1 The Contractor shall install a CSA approved Fall Arrest Rail to meet CSA S37-13 and the latest version of CSA Z259.1-1976 and CSA Z259.2-M1979. Rail system is to be Trylon type trolley compliant or approved equivalent.
- 1.7.2 The fall arrest rail shall be free from obstructions for the complete height of the tower.
- 1.7.3 The fall arrest rail shall be supported at spans not more than 1 m. Any extension beyond the top of the tower must be structurally supported for the entire height.
- 1.7.4 Proper manufactured stop hardware is to be installed at the top of the fall arrest rail to prevent accidental dislodging of the trolley from the rail.

nadian Coast Guard
--------------------

Page 3

1.7.5 Cable fall arrest systems are not acceptable.

### 2.0 Security Fence

2.1 Contractor shall install a galvanized chain link security fence around the base of the tower that is minimally 14 m X 14m, 2.5 m high with three levels of barb wire and a 1.2m wide single gate split horizontally into two independently operable sections. All fence posts, rails etc. are to be grounded.

#### **Dismantle Existing Tower**

Project: F6839-165008

### 1.0 General

- 1.1 After testing/optimization/commissioning of the new tower and Owner is satisfied with performance of the new system; the Contractor is to dismantle and clean up the existing tower and site.
- 1.2 The Contractor shall dismantle and dispose as directed by the Owner the existing tower and associated components. These components shall include, but not necessarily be limited to tower steel, guys, anchor assemblies to 300 mm below grade, conduit, lights, ladders, etc. All disposal shall be completed in a manner acceptable to the Federal, Provincial and Municipal authorities having jurisdiction.
- 1.3 The tower shall be dismantled in such a manner so as to pose no threat to the new tower, antennas or transmitter buildings. Responsibility for any and all damage to property as a result of the dismantling and disposal of the existing tower shall be the sole responsibility of the Contractor.
- 1.4 The Contractor shall provide sufficient detail to the Engineer with regard to the proposed method of dismantling the tower. Details should include measures to protect other property such as the new tower, guys and transmitter building. This method must be reviewed by the Engineer prior to the start of any work. This review shall not relieve the Contractor of his responsibilities and liabilities with the regard to the dismantling process. The Contractor shall provide these details in writing to the Engineer complete with sketches if required.
- 1.5 Contractor shall provide the Owner with a minimum notice of **ONE WEEK** prior to the proposed tower dismantling start.
- 1.6 All items, as determined by the Owner/Engineer shall be salvaged and stored on site as directed by the Owner/Engineer. Remaining items shall be disposed of by the Contractor in an approved manner. Contractor shall provide written documentation with regard to where and how material was disposed of. On site disposal is strictly prohibited.
- 1.7 Contractor is to remove existing foundations to 300mm below grade. All steel to be removed from site and recycled where possible.
- 1.8 Damaged areas to be restored to original conditions.

#### 1.0 General

- 1.1 The Contractor shall be responsible for the installation of the remaining parts of the complete permanent continuous grounding system for the MF tower system as per attached drawings.
- 1.2 Refer to Appendix B for details of grounding required for this tower system.
- 1.3 Refer to Appendix F for CCG supplied materials.
- 1.4 In rock conditions, the Contractor shall propose products and systems which shall attain the desired protection. This must be clearly shown on design drawings. All above ground runs of conductor must be securely attached to the rock at spaces not more than 3 m.
- 1.5 The Contractor will connect tower guys to the grounding systems as follows:
  - 1) to the tower-using Burndy Versatail or exothermic welding (Cadweld)
  - to the guy wires using Burndy KVSU or approved equal connectors, such that adverse reactions of different materials will not occur.
  - 3) to the ground ring by means of exothermic welding (Cadweld).
  - 4) wire to wire connections underground using exothermic welding (Cadweld).
  - 5) all connections shall be made according to manufacturer's directions. Provide Burndy Pentrox E compound on all connections.
  - 6) Before making a ground system connection, remove all paint, foreign matter or dirt.

### 2.0 Ground Rods

2.1 All ground rods shall be directly connected to the basic ground grid using thermit connectors.

A compression connection shall be installed as per the manufacturer's instructions and shall not be used to connect to more than one conductor per compression operation unless specified by the manufacturer.

Grounding

Project: F6839-165008

Page 2

### 3.0 Earth Enhancing Compounds

Earth enhancing compounds shall be considered for use at sites where the main external buried ground grid impedance to true earth cannot be reduced to the value specified in section 5.2 using metallic conductors and ground rods.

### 4.0 Standards of Acceptance

- 1) Ground Rods and Lightning Rods:
  - C.L.M. DN6CC10
  - L.C.A. 7510
  - Slater 9450
- 2) Thermit Connectors:
  - Cadwell connectors manufactured by ERICO Products Inc.
  - Compression Connectors: Burndy Hyground Compression System

### 5.0 Measurement of Ground Resistance

The Contractor shall measure the resistance to ground at a point near all anchors, the tower base and the transmission line entrance to the building. These readings shall be submitted to the Owner.

### 6.0 Transmission Line Grounding

6.1 The transmission line shall have an appropriate surge arrester installed on it before it enters the building. Subsequently, the surge arrester shall be appropriately grounded and tied into the building ground system.

### 7.0 Fencepost Grounding

7.1 All metallic fences around to be grounded every 20 ft to a Ground Rod, to the grounding electrode system or as specified by the engineer using tinned, stranded copper conductors.

Cana	dian Coast Guard	Section 16450
Grounding Project: F6839-165008		Page 3
7.2	All corner fence posts are to be CAD-welded to a tinned, #2 AWG copper conductor connected to the ground electrode system.	stranded
7.3	All gate posts are to be grounded with a tinned, #2 AWG stranded the ground electrode system.	conductor to
7.4	All fence components, chain-link, string-wires, deterrent (barbed) w bonded by flexible, stranded bonding jumpers to fence and gate pos- turn bonded to the perimeter electrode system. All bonding jumper to prevent bare copper to come into contact with galvanized steel.	sts that are in

#### Lighting and Power Supply

### 1.0 General

- 1.1 Contractor is responsible to verify requirements for obstruction lighting as per 621.19/TP382. Obstruction lights for the tower shall conform to the latest edition of Canadian Aviation Regulations 621.19/TP382 and the Nationals Electrical Manufactures Association (NEMA). The tower height shall be based on the highest intended projection of the structure.
- 1.2 All required equipment is to be installed, as specified, by Contractor.
- 1.3 The complete wiring system and lighting fixtures shall be of a waterproof type using COREFLEX CABLE or an approved equal, rigid fittings, and cast-iron or aluminum, type junction boxes.
- 1.4 All wiring shall be in accordance with CSA requirements, and type RA-90-40C wire shall be used throughout the installation. Wires shall be routed in to a junction box or fixture, and shall be routed down the tower from the top of the junction box or fixture.
- 1.5 Tower obstruction lighting shall be wired so that lamps in each double obstruction fixture will be on opposite side of a three-wire circuit. Circuits are to be wired in a flip-flop fashion and controlled by a photocell as the base of the tower.
- 1.6 The obstruction lamps shall be 130 volts long life, type 116 A21-TS or equivalent.
- 1.7 As required for Medium Frequency (hot) towers, contractor is to install base Austin (or equivalent transformer) for lighting power.
- 1.8 Lighting system to have a control system that is capable of remote monitoring and signalling operation.
- 1.9 Lighting system to operate automatically using a photovoltaic cell protected from falling ice.

### 2.0 Auxiliary Power Outlet

2.1 A weatherproof power receptacle shall be located at the base of the tower. The AC outlets will be complete with GFI protection and will be on separate circuits. 120V, 20 amps.

### 3.0 Permits and Temporary Lighting

- 3.1 The Contractor shall obtain an electrical installation permit from the appropriate agency and submit to the Owner evidence that the lighting installation has been inspected and approved by the said agency.
- 3.2 When required by Transport Canada, the tower Contractor shall make arrangements to provide temporary tower lighting until the tower is accepted, and the permanent power supply is available. These arrangements will be subject to the final approval of the Owner.

#### 4.0 Ice Protection

4.1 The Contractor shall install ice protection for all lights and lighting systems.

#### 5.0 Cable Attachment

5.1 The Contractor shall adequately secure the cables at distances not exceeding 750mm. Use of wrap-lock/tie wrap device to secure cables is unacceptable.

### 6.0 Termination of Wire and Hook Up

6.1 The Contractor shall terminate all wiring inside the building, in the existing electrical panel. The Contractor shall attach conduit to ceilings and walls so as to avoid conflict with existing equipment. All conduits shall be installed in a neat manner.

**Electrical-Antenna** 

Project: F6839-165008

### 1.0 General

- 1.0.1 Work under this section relates to the Design, Fabrication, Installation, Testing, Optimization and Commissioning of a Medium Frequency Receive antenna tower system.
- 1.0.2 Contractor is responsible for the complete installation of the antenna tower arrangement including structure, broadband elements, base insulator, guy insulators, tuning unit, ground plane and all other items required for the system to operate on the parameters identified below.

### 1.1 Antenna Specifications

- 1.1.1 The Medium Frequency Antenna Tower is required to perform as follows:
- 1.1.2 Receive MF Tower:

Frequency range: 2- 4.6 Mhz Bandwidth: 2.6 Mhz Antenna System VSWR: Not to exceed 2.5 over the specified frequency range. Radiation pattern: Omni-directional Polarization: Vertical Characteristic Impedance: Nominal 50 ohms unbalanced. Impedance matching: The ATU will consist of a "T"matching network which must consist of an input coil, shunt capacitor and an output capacitor. The "T" matching network must use variable components for optimum tuning. The ATU will also have a static drain coil going from the RF output to ground. The ATU shall not incur an insertion loss greater than 1.5 dB over the specified frequency range. Design, supply and installation of this unit is the complete responsibility of the contractor.

### 2.0 Products

- 2.1 Materials for MF Tower
- 2.2 A rain shield shall be installed over the base insulator.
- 2.3 A lighting transformer shall be incorporated into the base insulator, or supported from tower.
- 2.4 The radio frequency connection will be by means of Andrews' LDF-5-50, foam dielectric Heliax cable or approved equivalent from the new MF

Canadian Coast Guard

Project: F6839-165008

Page 2

tower ATU Enclosure to the receiver multicoupler in the existing equipment building.

2.5 Ground rods to be 19 mm by 3000 mm, copper clad. Grounding equipment to: CSA C22.2 No. 41 1950 (R1967) Copper grounding cables to: ASA G7.1 1964 Radial Ground screen: 90 radials spaced evenly 4 degrees apart consisting of #8 soft drawn solid copper wires extending a distance of 50 m from the center of the tower, including ground rods, straps, and ring as per Appendix B. (See Appendix H for CCG supplied materials).


### 3.0 Execution


### 3.1 Electrical Bonding

3.2 Special care shall be taken to ensure continuity of required electrical connections and proper bonding of electrical conduits, etc., upon initial assembly and throughout antenna structure life when subjected to salt spray conditions in coastal installation.

Appendix A


Site Location Map






Appendix B

Drawings







0 1 2	3 4 5 6 7 8 9 10 C	ENTIMETRES
FABRICATED PARTS		REV. DATE BY CHK APP
QTY PART No. RE	DESCRIPTION UNIT WT SUBTO	TAL 0 15JUL15 PJS SMM MM
4 AR028F 1	PL13x76 1-3/16 HOLE WASHER 0.6 2	2.4 DESCRIPTION:
1 BP011 0	PL 38 x 337 BASE PLATE 30.4 30	0.4 ISSUED FOR CONSTRUCTION
	TOTAL WEIGHT kg 32	2.8
HARDWARE		
QTY PART No.	DESCRIPTION	
4 1108034	1-1/8" x 3'-0" B7 ROD ASSEMBLY (4N,3FW) - HDG	
1 A-0729	BASE INSULATOR (GUYED) (90720 kg MAX. DOWNLOAD)	
		C
		STREED PROVIDE OF AND
	PROVINUE OF NELSANDLAW, AND LABRADOR PERMIT FOLDER Newforman FA	Fisheries and Oceans Canada
	Matthew Andreastants INS COMMERCOWS	
	WESTOWER COMMUNICATIONS LTD.	WESTOWED
	To protion Drational Engineering	60 South Field Drive Elmira, Ontario Canada N3B 2Z2
	To practice Professional Engineering in Newfoundland and Labrador.	Tel.: (519) 669-4144 Fax: (519) 669-1980
	Permit No. as issued by PEG 6986	DIMENSIONS ARE IN: mm
	which is valid for the year 2015	FOUNDATION - TOWER
	Ченени на после на рако на	35.3m 90AWG TOWER
GENERAL NOTES:		CANADIANI COAST CUADD
1. FOUNDATION DESIG	NED ACCORDING TO SOILS REPORT.	HOPEDALE HILL
BY: STANTEC		LABRADOR
REPORT No. F683 DATED: NOVEMBER		WESTOWER PROJECT No. SCALE:
2. REMOVE ALL LOOS	E AND WEATHERED ROCK.	50-00176 NTS
<ol><li>CALL WESTOWER E DRAWINGS.</li></ol>	NGINEERING (ELMIRA) IF CONDITIONS VARY FROM	DRAWN BY: CHECKED BY: APPROVED BY: DATE:
	ROCK SURFACE IS REQUIRED.	PJS ANT MM 15JUL15
		DRAWING NO: SHEET 500176A03 1
2		1
۷.	I	·









7 0	0	10 0510		-0				
7 8	9	10 CENT			DY			
	UNIT WT	SUBTOTAL	REV.	DATE 15JUL15	BY PJS	СНК	APP	
PLATE	25.4	76.2		RIPTION:	1100	0777	11/11	'
DMENT (250kN)	25.9	77.7		ISSUED FOR	CONSTR	NUCTION	N	
	1.1	3.3						
	3.7	22.2						
R SHAFT	12.6	75.6					8	
/ASHER)	0.6	7.2						D
ATE	2.3	13.8						
TOTAL WE	IGHT kg	276.0						
T ASSEMBLY								
SEMBLY								
T ASSEMBLY								<u> </u>
T ASSEMBLY EAD REBAR (4N, 3FV	N) CALV 70	" ONE END						
NED)	IJ GALV 30	UNE END						
IODE (17D3GG)								
(170000)								
								С
LOADS					PERSONAL COMPENSION PROFESSION PR			Ĭ
kN								
				SD PRO	PESSION	1		
				Les PE	PEA	6		
				S rature 1 Philosophia	instantis e de activitation Televisione de la companya de la companya Esta de la companya de	nn E		
			La	Mhouse	utung	E		
				N	15			
				t SIC	NATURE	-		
UNDLAND AND L	ABRADOS			Are Are	3/15	S.		
				CUN	DATE	SP.T		
PERMIT HOL					ND & LA		-	
his Permit A	llows							
MMUNICATION	IS LTD.							
nional Engla-	outer	-		Fis	heries a	nd Oce	eans	В
sional Engine and Labrador.	enng				nada		!	
ied by PEG To	286							
the year 2015								
		-						
				_				
EPORT.				VES1	ЮИ	ノヨ	2	
			60 S	<b>D M M U N</b> South Field Dri	ICAT ive	ION		
			Elm	ira, Ontario C	anada N3B		080	
DITIONS VARY F	ROM			: (519) 669-414				
			DI	MENSIONS /			mm	1
E LOCATING AND 500±.	HUK IF			TOWER				
ATE (IF REQUIRE				n 90AWG				
TENSIONED AS R N-SHRINK GROU		,		DIAN COA		ARD		А
MINIMUM) LIFTS (		955		DALE HIL	-L			
).				ADOR R PROJECT No.	SCALE.			
DIRECT TENSION				-00176	SCALE:	NTS		
ENGINEERING CONNOT ACCEPTABLE				Y: CHECKED BY:	APPROVED E	BY: DATE:		1
AUCE AUCE ABLE	-•		PJS		mm		JUL15	
			DRAWING		0.7	SHEE		
				500176A	103		2	1
			1					




						_	
7 8	9	10 CENT	IMETRI	ES			
			REV.	DATE	BY	CHK A	APP
	UNIT WT	SUBTOTAL	0	15JUL15	PJS	Sm? N	$\gamma n$
OR HEAD PLATE	4.6	55.2	DESC	RIPTION:			<u></u>
VASHER)	0.6	14.4		ISSUED FOR	CONSTR	UCTION	
LATE	2.3	27.6					
WELDMENT	10.4	124.8			1		
	6.4	153.6					
TOTAL WE		378.2					D
TOTAL WL	лопт ку	376.2					
<u> </u>							
5 BOLT							
SEMBLY							
SEMBLY							
READ REBAR (4N,3FW	/) GALV 36	'ONE END					
NED)							
NODE (17D3GG)							
PLATE SPACER)							
4.5.95							
I LOADS							
kN							C
						2	-
				OFF	SSIONAL Settored	57.50	
				CD PRO			
				8	AL.	2	
			115	nucl tab	e zarlear	E.	
			REG	na changa an	1	E	
			2	MARY	UPGE	~)]	
			{  _	11 alé	tal	]]	-
			12	SIGN	TUE	~	
				A. A.G.I	3/15	811	
				TROUNDLAN	TE BR		
CUNDLAND AND	ADDADO	5		WDLAN	0.8.1.1.		
Control Share Paris		<b>`</b>					
PERMITHO	LDER						
This Second A	Allows		1				
							в
OMMUSICATIC	MS LI		1			nd Ocean	IS
			- <b>-</b> -	Ca	nada		
anter al Frate	ooving	-					
assional Engin d and Labrador.							
sued by PEGTo	286						
or the year 201	5						
and a second		_			-		
				MEG1		7-7-7	·
REPORT.							
				South Field Driv			
				ira, Ontario Ca			
				: (519) 669-414		009-1980	
NDITIONS VARY F	ROM		DI	MENSIONS A	RE IN:	m	m
				CURTAIN	ANCI	HOR	
RE LOCATING ANG 1500±.	CHOR IF		35 3r	n 90AWG	TOWER	>	
ATE (IF REQUIRE	D).			DIAN COA			
TENSIONED AS F	REQUIRED	,		DALE HIL			A
N-SHRINK GROU		055			L		
MINIMUM) LIFTS		900	LABR				
D.					SCALE:	NTC	
DIRECT TENSION				-00176		NTS	
ENGINEERING C		Ξ	DRAWN B	T: CHECKED BY:		r: DATE: 15JUI	15
NOT ACCEPTABLI	<b>_</b> .				mm	_	
			DRAWING	™: 500176A	03	SHEET 3	
				500170A	00		
			1				




7 8 9	10 CEN	ITIMETRI	=s			
	LENGTH	REV.	DATE	BY	CHK APP	ר
5 x 3m)	4545m	0	15JUL15		Sm7 FT	
	10m	DESCF	RIPTION:	1 1		1
R HEAD (15 x 3m)	45m		ISSUED FOR	CONSTR	UCTION	1
.)	4545m	1				
C.W.)	10m	1				
I.S.C.W.)	45m					D
RODS	105					
00)	4					
	15	_				
Y	15	4				
	1515	_				
	1515	4				
	4	-				-
	15	-				
	19	-				1
'P' CLIP		1				
SELF TAPPIN	G SCREW					С
						$\mathbf{I}$
		1				
IL TYP		1				
3m)						
		1				
AIN OR R ANCHOR		1				
						в
					d Oceans	
		T 🗖 🗸	Cana	ada		
				$\sim \prime \prime$		
			VESI	ON	EK	
			South Field Drive			
			ira, Ontario Can : (519) 669-4144			
			MENSIONS AR		mm	1
			SPECIFI			1
						-
			n 90AWG			
			DIAN COAS DALE HILL		KU	A
		LABR				
				ALE:		-
			-00176		NTS	
		DRAWN B	T: CHECKED BY: AF		: DATE:	1
		PJS	8777.	FT	15JUL15	j .
<u>DRS</u>		DRAWING	™: 500176A0	4	SHEET 1	
		1	500170AU	-		-
1						





_	-										
7	8	9	10	CENT	IMETR			T	1		,
					REV. 0	DA	JL15	BY PJS	CHK	APP	
ED CONNEC	CTION					RIPTION		PJ3	811	FI	
								CONSTR	RUCTION		
- TOWE											
10.00	IN DAGL	- FLAIL									
											D
-											
SOLDE	RED CO	ONNECTI	ЛС								
_											
-											<u> </u>
└─(4) GR0	OUND S	STRAPS									
											С
										L.	
											-
(2)	/	(1)									
			-/								в
	OLDERE NNECTIO		ן ו			1. I			nd Oce	ans	Р
							Car	ada		0	
3/4	"ø x 1(	0'LG.									
	COPPE	RCLAD -	´								
	GROONL	NOD								5. 150 År (	
0m ———						/					
0111						ĹĒ	51	<b>O</b> V	77:	Rue -	-
						<b>D M M</b> South Fi			10 N		
								nada N3B Fax: (51	2Z2 9) 669-19	80	
						MENSIC		· ·		mm	
									OUND		1
								TOWE			1
								ST GU			А
					HOPE	DALE	HILL				
					LABR.						
					WESTOWE	R PROJEC		SCALE:	NTS		
								PPROVED E	BY: DATE:		1
				_	PJS	Sn			15J	UL15	<b>I</b> .
					DRAWING		176A0	14	SHEET	2	
					1	500	I / UAL	7		۷	1
I					I						



7	8	9	10	CENT	IMETR	ES					
			-		REV.	DA	TE	BY	СНК	APP	1 I
								-	-		
					0	15JU		PJS	8117	E	<b>I</b> '
						RIPTION			-		1
						ISSUED	FOR	CONST	RUCTIO	N	1
<19 BS											
											D
											I I
											I I
											W.
											l
											С
				-			NERC	SIONAL	·····(37)	7	
						OPR	Oreas	NONAL			1
						gy F	EE	EN, Č	Cr.	ŧ	
					15	The pro-	swfrauni et Eistra	ardinan sa	E		
					15	Pera C	URABIT OPTIC TO	r jensovavitrij	F		
					12	NA.	The second	UPGE	P		
						Illa	le to	T_	]		
\					12	1	SIGNA	1 WE	~		
	$\backslash$					. Au	5.13	15	511		
	1					QUN.	DAT	&LAB		z	
						-WI	LAND	82		and a second sec	
" J/E TURM	NBUCKL	-									
							Fish	neries a	nd Oce	eans	В
IDLAND AND	LABRAT	CR						ieries a iada			
							Jul				
ERMIT HO	LDER										
is Permit	Allow	s									
AUNICATI											
SCHRICHTE	ڪ ٿ <u>يون</u>										
								21			I I
ional Engi	neering						51	ОИ	<u>'/</u> ]	Ζ	
d Labrado	r				60 S	outh Fie	UN I	ICAT B	10 N	8	
d by PEGT	5286				Elm	ira, Onta	rio Ca	nada N3E			
ne year al	5				Tel.	: (519) 66	69-4144	Fax: (51	9) 669-1	980	
					DI	MENSIO	NS A	RE IN:		mm	
					TC	WER	GU	Y ASS	SEMB	LY	1
											1
								TOWE			
								ST GU	ARD		А
						DALE	HIL	_			
					LABR						
						PROJECT		SCALE:			
						-0017			NTS		
					DRAWN BY PJS			APPROVED I	BY: DATE:	JUL15	
					DRAWING	Sr.	11	FT	SHEE		1
					URAWING	<sup>ND:</sup> 5001	7640	05	SHEE	1	
-					1	2001					J
1											1







500176GB - STRUCTURAL GUY ASSEMBLY AT

PROVINCE OF NEW PEGA Newfoundland eind Lobradon Reason Reads account WESTOWER (

> To practice Pro in Newfoundia Permit No. as which is valid

2400 -

- AUSTIN INSULATOR AOA-65

3

2

5	6	7	8	9	10	CENT	IMETR	ES				
							REV.	DAT	Ē	BY	СНК	APP
							0	15JU		PJS	817	Fr
							DESC	RIPTION			0.77	
								ISSUED		CONSTR	RUCTIO	N
3/4	" 1x19	BS										
1												
$\Rightarrow$												
,												
-												
							N.					
$\rightarrow$												
									elessie		- 17° 7.	
								op pro		WALS		
								- Introv	fe as as a dirate	1		
							13	inserved Papar-stand	E est a cardra ar avait est ann	er i 🕰	剖	
ICHOR	SHACK						REGLS	MAR	AFYE	GE	R	
			<hr/>					11/20	h to	$\mathcal{D}_{-}$	1	
			$\backslash$					1 1	GNATU		~	
HIMBLE	-							Aure	5.13/	15	§]] -	
								AJC FOUNDI	DATE	LABR		
			(ĈĪ	> >			2		AND G		Sec. 2	
1/4" >	× 24" .	J/E TU	RNBUCK	LE								
									Fish	ories a	nd Oc	eans
								2	Cana			cano
								_				
ICE OF	NEWFO	UNDLA	ND AND	LABRAD	GR							
EA			IIT HO	INFR	a suite a							
obraidand	A											
NC 10 BS AND DEC	labitatis			Allows	1		_			5		
IOWE	RCO	MIMUN	ICATI	DNS LT	υ.			ľΞ	ST.	ŐĽ	11	2"
										CAT	1 0 N	
actico	Prefac	ssiona	Engin	neering	-1		Elm	South Fie Iira, Onta	rio Can			
wfoun	diand	and La	abrador					: (519) 66				980
it No.	as issu	ued by	PEGTO	286			D	MENSIO	NS AR	E IN:		mm
h is va	lid for	the ye	ar dois				T	OWER	GUY	ASS	SEMB	LY

D

С


◀-

В

A

2

35.3m 90AWG TOWER CANADIAN COAST GUARD HOPEDALE HILL LABRADOR WESTOWER PROJECT No. SCALE: 50-00176 NTS DRAWN BY: CHECKED BY: APPROVED BY: DATE: PJS Sm7 15JUL15 FI DRAWING NO: SHEET 500176A05 1



4 POUCES

4

INCHES 1

0


3


2

7	8
1	ī

1 0 1 2 3 4 5 6

PERMIT HOLDER






3

2


7	8
1	-



PERMIT HOLDER This Permit Allows WESTOWER COMMUNICATIONS LTD.

which is valid for the year 2015

INCHES 1	0	1	2	3	4 POUCES	1	
INOTILO	TTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTT		r I r	1	FOUCLS		




PART NUMBER	TOWER SHACKLE	THIMBLE	GUY GRIP	ICE BREAK	GUY STRAND SIZE	SUPPLIED GUY LENGTH	BOTTOM GUY GRIP	HOSE CLAMP	THIMBLE	J/E TURNBUCKLE SIZE	ANCHOR SHACKLE	QTY
500176GE	5/8"	7/16"H	BG-2147	5/16" G-450	3/8" EHS (1x7)	42.0m	BG-2147	HAS 8	7/16"H	3/4" x 18"	5/8"	12

#### 500176GE - CURTAIN ANTENNA ASSEMBLY (12) REQUIRED


NOTE: 1. SHACKLES: CROSBY G-209 HOT DIPPED GALVANIZED. 2. TURNBUCKLES: CROSBY JAW & EYE HG-227 HOT DIPPED GALVANIZED. 3. THIMBLES: CROSBY HEAVY G-414 HOT DIPPED GALVANIZED. 4. PREFORM BIG GRIP: PREFORM LINE PRODUCTS.


4




PEGA

REV.	DATE		BY	СНК	APP	
0	15JUL1	5	PJS	Sm	FI	
DESC	RIPTION:					
	ISSUED F	OR	CONSTR	NOITOU		
						٢
						С
	OPT	OF	ESSION	THE REAL PROPERTY OF THE PERTY		
	ALPER F	a j		CEN.		
		art Ein Russens Rocker	ita catian 🖄 Militananan Militananan	enni F		
	" M	KK J	7 <u>p</u> g	E	°	4-
	3		VALENE	æ	//	
	A.	G.	13 /15 DATE	-213/		
	Chrounn	LA	VD&LA	»//	-	
						в
			eries a	nd Oce	ans	D
		Jan	ada			
			7			
G	VES		<b>O</b> M	/E		
Ein	South Field	Car	nada N3B			
Tel	.: (519) 669-4	1144	Fax: (51			
	IMENSIONS			ASSEN	mm ABLY	
	m 90AW					
CANA	DIAN C	CAS	ST GU			Α
	EDALE H ADOR	TILL				
WESTOWE	R PROJECT No	. s	CALE:			
50- Drawn e	-00176	BY: A	PPROVED E	NTS IV: DATE:		
PJS	8m	<u> </u>	FT	15.	UL15	
DRAWING	™: 500170	5AC	)5	SHEET	5	
1						






7 8	9	10 CENT	IMETR	ES				
			REV.	DATE	BY	СНК	APP	
	UNIT WT	SUBTOTAL	0	15JUL15	PJS	8m1	FI	
	357.6	357.6	DESCR	RIPTION:				
	468.9	1875.6		ISSUED FOR	CONSTR	UCTION		
	488.4	488.4						
LDMENT	41.3	123.9						
ACE	2.7	8.1						
BRACE	4.2	12.6						D
•	10.0	30.0						
SUYS	5.9	17.7						
TOTAL WE	229.7	229.7 3143.6						
	лотт кд	5145.0						
EMBLY								
SEMBLY								
T ASSEMBLY								
T ASSEMBLY								
IBLY								
ASSEMBLY								
IBLY								
								С
								Ĩ
			REGUL	RAFIN PROPERSY REAL PROPERSY PROPERSY REAL PROPERSY REAL STORAGE REAL R	do-			-
TOWER N DETAIL				Fish Can		nd Ocea	ans	В
			Elm Tel.	VEST Jouth Field Drive ira, Ontario Car : (519) 669-4144	hada N3B Fax: (519	9) 669-198		
			DI	MENSIONS AR			nm	
				TOWER A	ASSEN	IBLY		
			CANA HOPE LABR		ST GU,			А
-			50- drawn by	-00176 /: CHECKED BY: A				
			PJS DRAWING	8m7	+1	SHEET	JL15	
			DRAWING	500176AC	)5	antti	7	
			1					
1			I					



7 8	9	10 CENT	IMETRE	ES				
		22.00	REV.	DATE	BY	СНК	APP	
	UNIT WT	SUBTOTAL	0	15JUL15	PJS	8m1	Tr	
LEG MOUNT	1.4	5.6	DESCF	RIPTION:			1	
LEG MOUNT	2.3	9.2		ISSUED FOR	CONSTR	UCTION		
LEG MOUNT	2.3	9.2						
LEG MOUNT	0.5	8.0						
MOUNT ANGLE	0.5	4.0						
GLE	17.9	17.9					1	D
T WELDMENT	3.4	3.4						
ESH	14.5	87.0						
	12.6	12.6						
-CLIMB DOOR	33.8	33.8						
LATE SPACER)	0.3	7.2						
TOTAL WE	IGHT kg	197.9						
LT ASSEMBLY								
LT ASSEMBLY								
- HDG								
BOLT ASSEMBLY)	(1N,1LV	V,1FW)					× .	
OLT ASSEMBLY (	2N,2LW,2	?FW)						
		1						С
				APD PROFESS I rest i obcome Mark FA				
	*			OFESS	10			
			1	ED PR	NAL.			
			12	f leavyfea na B	A S			
			13	nor of Ender or motocologic language	le a s 🚵 as constraints	3		
			E	MARKEN	DGE	Ę		
				Mal 1	$\mathbf{b}$			
•				SIGNAT	X.			
				AUG. 131	15	<u> </u>		
				DATE DATE	NR.			
ASS'Y w/3 FLAT	Г		1.1	WDLAND &	Re Line			
INSURE A WAS	HER							
BETWEEN ANGLI	LS.							
ETAIL				Eich	eries a		anc	В
				Can		iu Oce	ans	
NFOUNDLAND AND	LADDAP				luuu			
NETGONULAND AN	LAGKAL	UK I						
PERMIT HO	LDER							
This Permit	Allows							
COMMUNICATI	INS IT							
own:ordown		<i>D</i> .		V=e1		7-7-		
			6		GAT	101		
ofessional Engl				South Field Driv ira, Ontario Ca		272		
nd and Labrado				: (519) 669-4144			80	
ssued by PEG1			DI	MENSIONS AF	RE IN:		mm	
for the year do	10			I-CLIMB				
				n 90AWG				
		1		DIAN COAS DALE HILL		HRU		Α
			LABR		-			
					SCALE:			
				-00176		NTS		
				T: CHECKED BY: A		Y: DATE:		
			PJS		FI		UL15	
			DRAWING	NO:		SHEET		
				500176A0	)5		8	
			1					



CONFORMS TO CSA Z259.2.1-98

INFORMATION COPIED FROM TRYLON SAFETY RAIL INSTALL DRAWING NO. 000001.957.00

4


3

2


	7	8	9	10	CENT	IMETRI	ES			
						REV.	DATE	BY	СНК	APF
						0	15JUL15	PJS	8m1	Fr
						DESC	RIPTION:	<u> </u>		• •
							ISSUED FOR	CONSTR	UCTION	1
ATE										
VER										
RUN	GS				1					
DDER.										
ER										
iest Ts										
ORE										
IONS										
DF										
PEN										
STALL										
FOR										
RUNG										
None	,									
1										
E										
AFET	(				3					
ONT.										
5										
RAIL										
								eries an	ia Oce	ans
5							Can	ada		
							//_		)	
							IEST	OW	13:	2"
						6		CAT	I O N	
							South Field Drive ira, Ontario Car		772	
							: (519) 669-4144			80
						DI	MENSIONS AF	PE IN.		mm
							ETY RAIL			
										NUI
							n 90AWG			
							DIAN COAS		RD	
						HOPE	DALE HILL	-		
LAT	ION					LABR	ADOR			
002						WESTOWE	R PROJECT No. S	CALE:		
						50-	-00176		NTS	
						DRAWN B		PPROVED BY		
						PJS	8m7	FT	15J	UL1
						DRAWING			SHEET	
							500176A0	10		15
1						4				


R

INCHES 1	0	1	2	3	4 POUCES	 1 0 1	2 3 4	5 6
							South States	




1	0	1 2	3 4 5 6	7 8	9 10 CE	NTIMETRE	S				
HARD						REV.	DATE	BY		APP	1
	QTY		DESCRIPTION			0	15JUL15	PJS	8M7	MGF	1
1	1	860-6R01-002	DOUBLE OBSTRUCTION LIGHT			DESCR	IPTION:		(	. <u></u>	1
2			CONTROLLER C/W PHOTO CE				SSUED FOR	CONSTR			
3	3	FDX-2	JUNCTION BOX (4 WAY - 3			·'		Sonorr			ł
4	2		GFI RECEPTACLE								
5	2	FSK-1VDR	GFCI RECEPTACLE HINGED C								1
6	55m	THORSES	3#14 TECK 90 CABLE RW90								
7		IMC2050075A	1/2" CABLE CONNECTOR (3,	/4" OD CABLE)							D
8	8		REDUCER 3/4" TO 1/2"								
9	40		TY-WRAPS BLACK 13"								
10	1		CLOSE-UP PLUG (3/4" ALU								
12	4		COVER, GASKET & MOUNTING 3/4" x 10" NIPPLE	3 SUREWS							
13	3		3/4" PLASTIC BUSHING								
14	3		FILTER SCREEN WASHER								
15	12	333	MARRETTE CONNECTORS								
16	3		FB 9.5x102x230			1					
17	6		1/2" x 2-5/8" U-BOLT AS	SEMBLY							
18	6		3/8" x 1-1/2" U-BOLT AS								1
19	1		TRANSFORMER							2	
14											
										9	1
											1
						1					
						1					
											C
						1					
						1					
			*			1					E.
						1					
$\sim$											
(2)	)										
$\searrow$						1					
-						1					
							Ficho	rice or	nd Ocea		В
									iu Ocea	1115	
							Cana	ida			
						1					1
						1					
								-			
								21			
							7EST	ОИ	7=2	m	
						60	MMUNI	CAT	IONS		
							outh Field Drive	ida Nap	272		
							a, Ontario Cana (519) 669-4144			0	
						DIM	ENSIONS ARE			nm	
							TOWER I	_IGHT	ING		
						35 3~	90AWG				
							IAN COAS	I GUA	ARU		Α
							DALE HILL				
						LABRA	DOR				
						WESTOWER	PROJECT No. SC	ALE:			
							00176		NTS		
							CHECKED BY: API				
						PJS		AGE	15JL	JL15	
						DRAWING N			SHEET		
							500176A0	3		1	
		0		1				<i>.</i>		ſ	I .
		2		1		1					





Appendix C

Site Survey



	Fisheries Pêches
	and Oceans et Océans
	Coast Guard Garde côtière
	R
	of Land
	the rest of the second se
	LABRADOR SEA
	QUEBEC NAIN
	HOPEDALE
	Jul Mesker
	LABRADOR CARTWRIGHT
25m	COOSE BAY
3°03'19"	
	QUEBEC الماطر محسر QUEBEC
25m	
8°05`45''	
	KEY LOCATION PLAN
	NEI LUCATION FLAN
	N.E. PARROTT SURVEYS LTD.
	NEWFOUNDLAND LAND SURVEYORS
25m	GOOSE BAY, NEWFOUDLAND AND LABRADOR
3'39"	896-5019
25m	
03'04"	NEIL E. PARROTT N.L.S., C.L.S.
	LEGEND
25m	
	Cuy Wire
25m <b>05'39"</b>	Cuy Wire
	Guy Wire Image: Chain Link Fence   Proposed Cable Image: X Image: X Image: Chain Link Fence
05'39"	Cuy Wire
25m	Cuy Wire
05'39"	Cuy Wire Chain Link Fence Proposed Cable <u>NOTE:</u> ALL COORDINATES AND ELEVATIONS ARE REFERENCED TO PROVINCIAL CONTROL MONUMENT BOYDNo 4109020
25m	Cuy Wire
25m	Cuy Wire      ) CW     Chain Link Fence
25m	Cuy Wire      ) CW     Chain Link Fence
25m	Cuy Wire      ) CW     Chain Link Fence
25m	Cuy Wire      ) CW     Chain Link Fence
25m	Cuy Wire      ) CW     Chain Link Fence
25m	Cuy Wire      ) CW     Chain Link Fence
25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire      ) CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m	Guy Wire   Chain Link Fence     Proposed Cable
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire Chain Link Fence Proposed Cable <u>NOTE:</u> ALL COORDINATES AND ELEVATIONS ARE REFERENCED TO PROVINCIAL CONTROL MONUMENT BOYDNo 4109020 M.T.M. ZONE 4, NAD 83. RTK DATA COLLECTED ON OCTOBER 8, 2015 PLAN SHOWING TOPOGRAPHIC SURVEY
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire Chain Link Fence Proposed Cable <u>NOTE:</u> ALL COORDINATES AND ELEVATIONS ARE REFERENCED TO PROVINCIAL CONTROL MONUMENT BOYDNo 4109020 M.T.M. ZONE 4, NAD 83. RTK DATA COLLECTED ON OCTOBER 8, 2015 PLAN SHOWING TOPOGRAPHIC SURVEY FOR PROPOSED TOWER SITE
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire Chain Link Fence Proposed Cable <u>NOTE:</u> ALL COORDINATES AND ELEVATIONS ARE REFERENCED TO PROVINCIAL CONTROL MONUMENT BOYDNo 4109020 M.T.M. ZONE 4, NAD 83. RTK DATA COLLECTED ON OCTOBER 8, 2015 PLAN SHOWING TOPOCRAPHIC SURVEY FOR PROPOSED TOWER SITE HOPEDALE HILL (MF - RX)
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Guy Wire   Chain Link Fence     Proposed Cable
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire Chain Link Fence Proposed Cable <u>NOTE:</u> ALL COORDINATES AND ELEVATIONS ARE REFERENCED TO PROVINCIAL CONTROL MONUMENT BOYDNo 4109020 M.T.M. ZONE 4, NAD 83. RTK DATA COLLECTED ON OCTOBER 8, 2015 PLAN SHOWING TOPOCRAPHIC SURVEY FOR PROPOSED TOWER SITE HOPEDALE HILL (MF - RX)
25m 25m 25m 25m 25m 25m 25m 25m 25m	Guy Wire
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire
25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire
25m 25m 25m 25m 25m 25m 25m 25m 25m	Cuy Wire   CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m	Guy Wire   CW     Chain Link Fence   CW     Proposed Cable
25m 25m 25m 25m 25m 25m 25m 25m 25m	Guy Wire   CW     Chain Link Fence
25m 25m 25m 25m 25m 25m 25m 25m 25m 25m	Guy Wire   CW     Chain Link Fence   CW     Proposed Cable

Appendix D

Existing MF Tower Information



# T5441 Hopedale Hill

MCTS	Latitude	Longitude	AoR Travel T	ime Aof	R Distance	(km)	AoR	Cell Coverage
Goose Bay	55° 27' 52.7''	60° 13' 13.001	N/A	221	216		St. John's	
Fence Install Yea	ar	Linear Meters of I	Fence	Site Acc	ess	Helipad	·	ind
				helicopt	er, 4x4, v			
Server Link				Goog	le Maps Lir	nk		
\\dcNLnewNA01b\M	ICIEngineering\MCTS	S\T5441-Hopedale H	Hill	http://u	maps.google.	com/maps?	q= 55°+27'+52.7003	3+N,+60°+13'+13.000
Year Establish	ed Property Ar	ea (Ha) Owners	ship Year Su	irveyed	Survey	or	Site #	
1961	7.634	NavCar	า 2005		N.E. Pa	rrott Sur	veyor NA 00285	

# **MF Receive Tower**




Tower	T5441.202
Height (m)	30.5
Latitude	55° 27' 52.7'' N
Longitude	60° 13' 13'' W
Base HASL (m)	106.3
Year Installed	1986
Year Refurbished	
Year Last Inspected	2008
Design	
Structure Type	Guyed
Connection Type	All Weld
Cross Section	Triangular
Manufacturer	Leblanc & Royal
MCTS Phone #	(709) 896-2252
Inspection Zone	1
Owner	CCG
RPIS Comp #	57396
Tower Fenced	
Drawings Available	

Appendix E

Site Photos









Appendix F

List of CCG Supplied Materials

	WES	TOWER	Loc	tomer ation ver Type		S AND OCEANS Hill, Hopedale, 35.3m		339-155503	_	Proje 50-0	ect Nu 001			- "All I		Date 02 Detailed by Is 'HDG' unle	
Shi	ipping	BOM						Section 1	<b>Below Grade</b>								
														Р	age:	1	
Tow	er Found	lation		TOWER BA	SE									Pag	e Sect	ion Revisio	n: 1
Mate	ərial										Field	Line		Finish			
#	QTY	PartNo	Rev.	Description					Suggested Supplier		Supplied	Total	OR	WH	SP	Package	
1	4 pc	AR028F	1	PL13x76 x 76	5mm 1-3/16 H	OLE WASHER			Westower			5.3					
2	1 pc	BP011	0	PL 38 x 337 x	337mm BAS	E PLATE			Westower			72.8					
										SubTo	al:	78.1 lk	s				
Harc	dware										Field	Line		Finish			
#	QTY	PartNo	Rev.	Description					Suggested Supplier		Supplied	Total	OR	WH	SP	Package	
1	4 pc	1108034		1-1/8" x 3'-0" /	B7 ROD ASS	EMBLY (4N,3FW)	) - HDG		Fastenal			84.4				-	
2	1 pc	1406001		LIGHTING TF	RANSFORME	R (0.7 kVA, 115/2	230V)		Austin A-07D1			70.6					
3	1 pc	1406014		BASE INSUL	ATOR (GUYE	D) (90720 kg MA	X. DOWNL	OAD)	Austin A-0729			366.0					
4	1 pc	1406072		AUSTIN INSL	JLATOR TRA	NSFORMER MO	UNT KIT (A	-07D1 TO A-4722-B)	Austin			0.0					

> 521.0 lbs SubTotal:

ADDED TRANSFORMER AND MOUNT KIT - PJS 29-Jul-15 Hardware **Rev.** 1

	WES	Tower	Loc	stomer cation ver Type		S AND OCEANS Hill, Hopedale 35.3m		-155503	_	-	iect Nu 001			"All		Date 02-Jul Detailed by: p ls 'HDG' unless r	PJS
S	hipping	BOM					Se	ection 1	<b>Below Grade</b>								
														F	age:	4	
Be	low Grade	Grounding												Pag	e Sect	ion Revision:	1
Ha	ardware										Field	Line		Finish			
#	QTY	PartNo	Rev.	Description					Suggested Supplier		Supplied	Total	OR	WH	SP	Package	
1	1530 pc	1106148		#10-12 x 2" P	AN HEAD, S	QUARE SELF TA	PPING SCREW	V	Kerry PCT-10X2-Z		$\checkmark$	0.0					
2	1530 pc	1106225		6/6 Nylon P C	Clip - 1/8" ID V	Vhite (pkg of 100)	(3/16" fastener	not included)	SPAENAUR 086-66	60		0.0					
3	10 m	1201009		4/0 BARE ST	RANDED CC	PPER WIRE			Anixter		$\checkmark$	0.0					
4	45 m	1201017		#2 INSULATE	ED STRANDE	ED COPPER WIR	E		Anixter		$\checkmark$	0.0					
5	14 m	1201019		300mm x 1.23	3mm COPPE	R STRAP			Anixter		$\checkmark$	0.0					j
6	4545 m	1201025		#10 SOFT DF	RAWN SOLIE	COPPER WIRE			Anixter		$\checkmark$	0.0					
7	105 pc	1202004		COPPER CL	AD GROUND	ROD 19 DIA x 3	000mm		Anixter		$\checkmark$	0.0					
8	20 pc	215-0001	3	SH16 3/8" DI	A. CABLE CL	AMP ALUM #42			Astron 42			0.0					
9	6 pc	215-0003	0	SH16 5/8" DI	A. CABLE CL	AMP ALUM #45			Astron 45			0.0					
										SubTo		0.0.14	he				

SubTotal: 0.0 lbs

**Rev.** 1 06-Aug-15 Hardware (1530) 1106148 CHANGED TO 'FIELD SUPPLY' - PJS

		<b>~</b>		stomer ation		ES AND OCEANS Hill, Hopedale,		6839-155503		Proj	ect Nu	mber				Date 02-J Detailed by:	Jul-15
	WES.	TOWER		ver Type	90AWG	35.3m				50-0	001	76		"All I		s 'HDG' unles	
Sh	ipping	BOM						Section 2	Above Grade								
														Р	age:	1	
Abo	ve Grade	Grounding												Pag	e Sect	ion Revision:	0
Hard	dware										Field	Line		Finish			
#	QTY	PartNo	Rev.	Description					Suggested Supplier		Supplied	Total	OR	WH	SP	Package	
1	15 pc	1103012		5/16" x 1-1/	2" SILICONE I	BRONZE BOLT (11	N,1LW)		Kerry			0.0					
2	12 pc	402-0410		UNIVERSA	L OKLIP BUR	NDY 5/16" to 7/16"			Westburne Ruddy KVS	SU26							
3	6 pc	402-0415	0	UNIVERSA	L OKLIP BUR	NDY 3/4" to 3/4"			Westburne Ruddy KVS	SU34		0.0					
4	15 pc	1206003		4/0-2 STR.	5/16" BOLT S	ZE ILSCO			Kerry SLU-225			0.0					
										SubTo	al:	0.0 II	os				

	Customer	FISHERIES AND OCEANS Site: F6839-155503	Project Number
WESTOWER	Location	Hopedale Hill, Hopedale, NL	
COMMUNICATIONS	Tower Type	90AWG 35.3m	50-00176

Date 02-Jul-15 Detailed by: PJS "All Materials 'HDG' unless note

#### **Shipping BOM**

#### Section 3 Tower

Page: 1

									. ~g		tion Revision:	
Mate						Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	I Total	OR	WH	SP	Package	
	1 pc	500176C	1	90AWG 3m TOP SECTION x 3000mm MF CURTAIN WELDMENT	Westower		800.4			1		
	4 pc	90G00AA	3	90AWG 6m REG SECTION (51 LEG, 25 DIAG) (18) Tx-lines total	Westower		4,135.7			4		-
	1 pc	90G33AA	1	90AWG 6m GUY SECTION (51 LEG, 25 DIAG) (18) Tx-lines total	Westower		1,076.9			1		
	3 pc	90MF002	0	CURTAIN TOWER BRACE x 1355mm WELDMENT (12 CURTAINS-5/8" SHACKLE)	Westower		273.2					
	3 рс	90MF003	0	L 76x51x4.8 x 581mm STARBASE BRACE	Westower		17.9					
	3 pc	90MF006	0	L 76x51x9.5 x 480mm TOP CURTAIN BRACE	Westower		27.8					
	3 pc	90SB003	0	PL172x32 x 235mm ADAPTER PLATE	Westower		66.2					
	3 рс	90SB004	2	PL172x19 x 235mm MOUNTING PLATE	Westower		39.0					
	1 pc	90SB005	1	STAR BASE FOR CURTAIN GUYS x 1464mm	Westower		506.5					
						SubTotal:	6,943.5 II	os				
lard	ware					Field	Line		Finish			
ŧ	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	I Total	OR	WH	SP	Package	
	7 pc	202-0104	0	5/8" x 2" A325 BOLT ASSEMBLY - HDG (B20)	Kerry B20		2.9					
	6 pc	202-0108	0	5/8" x 3" A325 BOLT ASSEMBLY - HDG (B30)	Kerry B30		3.0					
	12 pc	202-0203	0	3/4" x 2-1/4" A325 BOLT ASSEMBLY - HDG (C21)	Kerry C21		7.9					
	12 pc	202-0209	0	3/4" x 3-3/4" A325 BOLT ASSEMBLY - HDG (C33)	Kerry C33		10.2					
	3 pc	202-0408	0	1" x 4-3/4" A325 BOLT ASSEMBLY - HDG (E43)	Kerry E43		5.6					
	3 pc	202-0413	0	1" x 6" A325 BOLT ASSEMBLY - HDG (E60)	Kerry E60		6.5					
	9 pc	1102109		1" x 6-1/2" A325 BOLT ASSEMBLY - HDG (E62)	Kerry E62		20.5					
	3 рс	1102110		1" x 7" A325 BOLT ASSEMBLY - HDG (E70)	Kerry E70		7.2					
	18 pc	210-0006	0	1" F-436 FLATWASHER - HDG	Kerry		1.7					_
						SubTotal:	65.4 II					

20-Jul-15 Hardware ADDED HARDWARE - PJS **Rev.** 1

**Rev.** 2

**Rev.** 1 20-Jul-15 Material 500176C REPLACES 90G33EA; ADDED 90SB005, 90SB003, 90SB004, 90MF002, 90MF003, 90MF006 - PJS

05-Aug-15 Material Added paint quantities - PJS

**Rev.** 3 06-Aug-15 Material PART 500176C WAS REVISION 0 - PJS

	Customer	FISHERIES AND OCEANS Site: F6839-1555	03	Project Number	Date 02-Jul-15
WESTOWER	Location Tower Type	Hopedale Hill, Hopedale, NL 90AWG 35.3m		50-00176	Detailed by: PJS "All Materials 'HDG' unless note
Shipping BOM			Section 4	Guys	All Matchais TIDO unicos note
					Page: 1

Guy	/ Material			Tower Guy Material					Page	e Sect	ion Revision:	0
Har	dware					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	15 m	702-0103		3/4" 1x19 BRIDGE STRAND - GALVANIZED	Unalloy	$\checkmark$	58.0					
2	313 m	702-0103	0	3/4" 1x19 BRIDGE STRAND - GALVANIZED	Unalloy		1,211.2					
3	12 pc	706-0006	0	7/8" SCREW PIN SHACKLE G-209 CROSBY	Unalloy 1018516		43.4					
4	12 pc	705-0008	0	7/8" HEAVY THIMBLE G-414 CROSBY	Unalloy 1037791		21.3					
5	6 pc	703-0262	0	1-1/4x24 JAW & EYE TURNBUCKLE HG-227 CROSBY	Unalloy 1032297		171.0					
6	18 pc	707-0007	0	5/8" WIRE ROPE CLIP G-450 CROSBY	Unalloy 1010177		19.8					
7	96 pc	704-0006	0	BIG GRIP DEAD END (BRIDGE) - GALV. STEEL - 3/4"	PLP BGMS-3690		1,268.0					
8	42 pc	1406076		GUY INSULATOR OPEN-END TYPE AOA-65 7/8" CABLE	Austin AOA-65		0.0					
9	27 pc	1408002		YELLOW GUY GUARD (44 ID x 2000 LG) IPEX	Westburne Ruddy 25504-Y		75.6					
10	54 pc	1602001		BLACK NYLON TY-RAP, 13" LONG	Home Hardware TF7X		0.0					
11	96 pc	1602003		HOSE CLAMPS HAS 8 (up to 1")	Kerry HAS-8		0.0					

SubTotal: 2,868.4 lbs

	Customer	FISHERIES AND OCEANS Site: F6839-155503	Project Number	Date 02-Jul-15
WESTOWER	Location	Hopedale Hill, Hopedale, NL	50 0017/	Detailed by: PJS
COMMUNICATIONS	Tower Type	90AWG 35.3m	50-00176	"All Materials 'HDG' unless note

## Shipping BOM

## Section 4 Guys

Page: 2

Gu	y Material			Curtain Guy Material					Page	e Sect	ion Revision:	0
Ha	rdware					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	280 m	1403003		3/8" 1x7 EHS GUY STRAND - GALVANIZED	Unalloy		250.7					
2	12 pc	706-0004	0	5/8" SCREW PIN SHACKLE G-209 CROSBY	Unalloy 1018473		16.4					
3	24 pc	705-0003	0	7/16" HEAVY THIMBLE G-414 CROSBY	Unalloy 1037693		8.3					
4	12 pc	703-0231	0	3/4x18 JAW & EYE TURNBUCKLE HG-227 CROSBY	Unalloy 1032117		84.0					
5	36 pc	707-0002	0	5/16" WIRE ROPE CLIP G-450 CROSBY	Unalloy 1010079		10.1					
6	120 pc	704-0103	0	BIG GRIP DEAD END - GALV. STEEL - 3/8"	PLP BG-2147		158.4					
7	12 pc	1405030		ANGLE SUSPENSION CLAMPS HUBBELL POWER SYSTEMS	Westburne Ruddy MS46N		25.9					
8	48 pc	1406073		STANDARD ANSI INSULATOR	Austin ST54-3		137.6					
9	120 pc	1602003		HOSE CLAMPS HAS 8 (up to 1")	Kerry HAS-8		0.0					
							004 4 11					

SubTotal: 691.4 lbs

	Customer	FISHERIES AND OCEANS Site: F6839-155503	Project Number	Date 02-Jul-15
WESTOWER	Location	Hopedale Hill, Hopedale, NL		Detailed by: PJS
COMMUNICATIONS	Tower Type	90AWG 35.3m	50-00176	"All Materials 'HDG' unless note

#### Shipping BOM

# Section 4 Guys

Page: 3 Page Section Revision:

Gu	y Material			Curtain Antenna Material					Pag	e Sect	ion Revision:	0
Ha	rdware					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	30 pc	203-0206	0	3/8" x 2" UNC GR.5 BOLT - HDG (1N,1LW)	Kerry		2.2					
2	48 m	1201022		#2 BARE STRANDED COPPER WIRE	Anixter		0.0					
3	24 pc	1205003		1-HOLE HYLUG #2 WIRE, 3/8" STUD BURNDY	Westburne Ruddy YAL2CT38		0.0					
4	24 pc	402-0410	0	UNIVERSAL OKLIP BURNDY 5/16" to 7/16"	Westburne Ruddy KVSU26		0.0					
5	13 pc	402-0712	0	BURNDY QPX-2828 CONNECTOR BURNDY	Westburne Ruddy QPX2828		0.0					Ţ.
6	560 m	1403003		3/8" 1x7 EHS GUY STRAND - GALVANIZED	Unalloy		501.3					Ţ.
7	24 pc	706-0004	0	5/8" SCREW PIN SHACKLE G-209 CROSBY	Unalloy 1018473		32.9					
8	24 pc	705-0003	0	7/16" HEAVY THIMBLE G-414 CROSBY	Unalloy 1037693		8.3					
9	12 pc	703-0231	0	3/4x18 JAW & EYE TURNBUCKLE HG-227 CROSBY	Unalloy 1032117		84.0					
10	36 pc	707-0002	0	5/16" WIRE ROPE CLIP G-450 CROSBY	Unalloy 1010079		10.1					
11	24 pc	704-0103	0	BIG GRIP DEAD END - GALV. STEEL - 3/8"	PLP BG-2147		31.7					
12	24 pc	1602003		HOSE CLAMPS HAS 8 (up to 1")	Kerry HAS-8		0.0					

SubTotal: 670.5 lbs

WESTOWER	
VESIONER	-

CustomerFISHERIES AND OCEANSSite:F6839-155503LocationHopedale Hill, Hopedale, NLTower Type90AWG35.3m

#### Project Number

# 50-00176

Date 02-Jul-15 Detailed by: PJS "All Materials 'HDG' unless note

#### **Shipping BOM**

### Section 5 Ladder

Page: 1 Page Section Revision:

Anti	-Climb			ANTI-CLIMB					Pag	e Sec	tion Revision:	0
Mat	erial					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	4 pc	90AC001A	1	L 89x89x6.4 x 158mm ANTI-CLIMB LEG MOUNT	Westower		12.3					
2	4 pc	90AC001B	1	L 89x89x6.4 x 250mm ANTI-CLIMB LEG MOUNT	Westower		20.3					
3	4 pc	90AC001C	1	L 89x89x6.4 x 250mm ANTI-CLIMB LEG MOUNT	Westower		20.3					
4	16 pc	90AC001D	1	L 64x64x6.4 x 80mm ANTI-CLIMB LEG MOUNT	Westower		17.6					
5	8 pc	90AC001E	0	L 76x76x6.4 x 60mm ANTI-CLIMB MOUNT ANGLE	Westower		8.8					
6	24 pc	S4A	3	PL6.4x51 x 51mm 9/16" HOLE PLATE SPACER	Westower S4A		15.9					
7	1 pc	90AC001F	0	L 76x76x6.4 x 2535mm ANTI-CLIMB LOCKING ANGLE	Westower		39.5					
8	1 pc	90AC001G	3	SR13 x 2446mm ANTI-CLIMB LOCKING BENT WELD'T	Westower		7.5					
9	6 pc	90AC001H	1	1-1/2"-10 ExPANDED MESH 1220x1220 ANTI-CLIMB MESH	Westower		191.8					
10	1 pc	90AC001J	4	1x3/16 W19-4 BAR 668x772 ANTI-CLIMB GRATING	Westower		27.8					
11	1 pc	90AC001K	2	FLAT BAR WELDMENT ANTI-CLIMB DOOR	Westower		74.5					
						SubTotal:	436.4 II	bs				
Hare	dware					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	22 pc	202-0001	0	1/2" x 1-1/2" A325 BOLT ASSEMBLY - HDG (A12)	Kerry A12		4.7					
2	34 pc	1102003		1/2" x 1-3/4" A325 BOLT ASSEMBLY - HDG (A13)	Kerry A13		7.7					
3	9 pc	210-0002	0	1/2" F-436 FLATWASHER - HDG	Kerry		0.2					
4	4 pc	J12-3	8	1/2" x 3" Lg J-BOLT ASSEMBLY (1N,1LW,1FW) (dwg HW001)	Martin J12-3		1.6					
5	24 pc	U12-7	6	1/2" x 2-3/8" c/c U-BOLT ASSEMBLY (2N,2LW,2FW) (dwg HW005) U12-7	Martin U12-7		12.1					

SubTotal: 26.2 lbs

	WES	TOWER	Customer Location Tower Type		S AND OCEANS Hill, Hopedale, 35.3m	Site: F6839-155 NL	503	-	Proje 50-0		<sup>imber</sup> 76		"All I	I	Date 02-Ju Detailed by: s 'HDG' unless	PJS
Shi	pping	BOM					Section	5 Ladde	r							
													Р	age:	2	
Safe	ty Rail		Safety Rail										Pag	e Secti	on Revision:	1
Hard	lware									Field	Line		Finish			
#	QTY	PartNo	Rev. Description					Suggested Supplie	r	Supplied	Total	OR	WH	SP	Package	
1	1 pc	1501023	120' SAFETY HARDWARE,	· ·	,	SPLICES, MOUNTI	NG	Trylon 4.97.0400.1	20		130.0					]
2	2 pc	1504554	TRYLON TSF	COUGAR N	IAX TROLLEY			Trylon 4.957.0037.	001		0.0					
									SubTota	al:	130.0 I	bs				

Rev. 1 05-Aug-15 Hardware Added (2) trolley - PJS

	Customer	FISHERIES AND OCEANS Site: F6839-155503	Project Number
WESTOWER	Location	Hopedale Hill, Hopedale, NL	FO 0017/
COMMUNICATIONS	Tower Type	90AWG 35.3m	50-00176

Date 02-Jul-15 Detailed by: PJS "All Materials 'HDG' unless note

Page: 1

#### **Shipping BOM**

#### Section 8 Lighting

Ligh	ting Mate	erial		Lighting Material					Pag	e Sect	ion Revision:	
Mat	erial					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
	3 pc	LT032	1	FB9.5x102 x 230mm	Westower		11.9	)				
					Sub	Total:	11.9 I	bs				
lar	dware					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
	8 pc	303-0093	0	1/2" TMC2050075A CONNECTOR APPLETON (0.5-0.76 CABLE)(was TMC5076)	Westburne Ruddy TMC2050075A		0.0	)				
	1 pc	1305011		SINGLE GANG VAPORTIGHT COVER APPLETON	Westburne Ruddy FS-100g		0.6	;				
	3 pc	302-0702	0	PLG CLOSE-UP PLUG (3/4" ALUM) APPLETON	Westburne Ruddy PLG-75R/	<i>۲</i>	0.0	)				_
	8 pc	302-0501	0	THD. REDUCER (3/4" TO 1/2") APPLETON	Westburne Ruddy RB75-50A		0.5	j				
	3 pc	1305032		3/4" PLASTIC BUSHING APPLETON	Westburne Ruddy PB-200-D		0.0	)				-
	2 pc	1305035		GFI RECEPTACLE APPLETON	Westburne Ruddy GF15LA		0.0	)				
	3 pc	1305054		FD SINGLE GANG BOX (4 PORT - 3/4" HUB) APPLETON x 1mm	Appleton FDX-2		0.0	)				
	2 pc	1305055		GFI RECEPTACLE HINGED COVER (VERTICAL MOUNT)	Appleton FSK-1VDR		0.0	)				
	55 m	301-0307	0	3#14 TECK 90 CABLE	Anixter		0.0	)				-
0	3 pc	1307003		FILTER SCREEN WASHER	Westburne Ruddy		0.0	)				
1	12 pc	1307004		MARRETTE #333	Westburne Ruddy		0.0	)				
2	4 pc	1307008		3/4" x 10" PIPE NIPPLE CONDUIT PIPE THREAD EACH END	Westburne Ruddy		0.0	)				_
3	1 pc	1308014		LIGHTING CONTROLLER WITH ALARM AND PHOTOCELL	RVA LC-AO-LED-NEMA4		0.0	)				
4	1 pc	1308023		OBSTRUCTION LIGHT, DOUBLE, RED 3/4 BOTTOM HUB	RVA 860-6R01-002		0.0	)				-
5	40 pc	1602001		BLACK NYLON TY-RAP, 13" LONG	Home Hardware TF7X		0.0	)				
6	6 pc	U12-8	6	1/2" x 2-5/8" c/c U-BOLT ASSEMBLY (2N,2LW,2FW) (dwg HW005) U12-8	Martin U12-8		2.6	;				-
17	6 pc	U38-3	7	3/8" x 1-1/2" c/c U-BOLT ASSEMBLY (2N,2LW,2FW) (dwg HW006) U38-3	Martin U38-3		1.5	j				_
					Sub	Total:	5.2	bs				

REMOVED LIGHTING TRANSFORMER A-07S1 - PJS 11-Aug-15 Hardware **Rev.** 1

WESTOWER	Location	Hopedale Hill, Hopedale,	NL	Project Number 50-00176	Detailed by: PIS
Shipping BOM	Tower Type	90AWG 35.3m	Section 10	Name Plate	"All Materials 'HDG' unless note

#### Section 10 Name Plate

									P	age:	1	
Name Plate			NAME PLATE	SECTION 10 FOR NEW TOWER				Page	e Sect	ion Revision:	0	
Mat	erial					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	1 pc	NP013	0	SH16x610 x 610mm CLIMBER WARNING SIGN	Westower		0.0					
2	1 pc	GG019	0	ALUM SH 30x76x76 ANODIZED BLANK TAG SEE REPORT	Westower		0.0					
3	1 pkg	9900IN	0	INSTALLATION PACKAGE	Westower		0.0					
					—	SubTotal:	0.0 lbs					
Har	dware					Field	Line		Finish			
#	QTY	PartNo	Rev.	Description	Suggested Supplier	Supplied	Total	OR	WH	SP	Package	
1	2 pc	1106165		#6 x 3/8" "U" DRIVE SCREW	Fastenal		0.0					
2	4 pc	215-0003	3	SH16 15/32" DIA. CABLE CLAMP ALUM #43	Astron 43							
3	5 pc	203-0203		3/8" x 1-1/4" UNC GR.5 BOLT - HDG (1N,1LW)	Kerry		0.2					
					—						-	

0.2 lbs SubTotal: