

1 General

1.1 RELATED WORK SPECIFIED ELSEWHERE

- .1 Section 01 35 29 - Health, Safety and Emergency Response Procedures.

1.2 PROTECTION

- .1 Protect existing items designated to remain. In event of damage, immediately replace such items or make repairs to approval of Consultant and at no additional cost to Owner.

1.3 DESCRIPTION OF WORK

- .1 Perform all demolition and removal as specified in this Section and indicated on the Drawings.

1.4 DEMOLITION

- .1 Demolish the following items and dispose of off site:
 - .1 Planters.
 - .2 Decking, sleepers, blocking and miscellaneous deck supports.
 - .3 Gravel ballast.
 - .4 Roof membrane.
 - .5 Insulation.
 - .6 Support boards.
 - .7 Vapor barrier.

End Of Section