

Part 1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures and 01 74 21 - Construction/Demolition Waste Management Disposal.

1.2 SITE CONDITIONS

- .1 If material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Departmental Representative immediately.
 - .1 Proceed only after receipt of written instructions have been received from Departmental Representative.
- .2 Notify Departmental Representative before disrupting building access or services. Refer to Section 01 14 01 – Contractor health, safety and environmental policy handbook.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 EXAMINATION

- .1 Inspect building with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.

3.2 PREPARATION

- .1 Protection of In-Place Conditions:
 - .1 Prevent movement, settlement, or damage to adjacent structures, utilities, and parts of building to remain in place. Provide bracing and shoring required.
 - .2 Keep noise, dust, and inconvenience to occupants to minimum.
 - .3 Protect building systems, services and equipment.
 - .4 Provide temporary dust screens, covers, railings, supports and other protection as required.
 - .5 Do Work in accordance with Section 01 35 29.06 - Health and Safety Requirements.
- .2 Demolition/Removal:
 - .1 Remove items as indicated.

- .1 Square up adjacent surfaces to remain in place by saw cutting or other method approved by Departmental Representative.
- .2 Protect adjacent joints and load transfer devices.
- .2 Remove parts of existing building to permit new construction.
- .3 Trim edges of partially demolished building elements to tolerances as defined by Departmental Representative to suit future use. .
- .4 Remove the following parts shown on the drawings to be recovered and stored as directed by the Departmental Representative:
 - .1 Tile carpeting;

3.3

CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Refer to demolition drawings and specifications for items to be salvaged for reuse.
- .4 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION