



ADDENDUM # 1

Date: 2016, July 5

Project: Pigsty Walls and Ceiling Finishes Improvements – G building, Sherbrook

Bidders must make sure that their bids are based on the latest version of the tender documents published and take into consideration the following amendments and information, including any information provided in amendments or Q&As previously published for this project.

Bidders that do not comply with this requirement will be discarded.

In Appendix E « TECHNICAL SPECIFICATIONS & PLANS»

1. Intervention legend, G building, p.23

REPLACE :

36. In order to remove the garage door, rails, the door opener and all attached equipment, supply and install temporary exterior protections in order to protect against rodents and bad weather, for the duration of work (see picture 18, annex B). Temporarily remove door, rails, hardware and equipment. Demolish existing wood frame around opening. Supply and install massive plastic pieces to replace frame. Reconnect all equipment and test to make sure everything is functional

BY:

36. In order to remove the garage door, rails, the door opener and all attached equipment, supply and install temporary exterior protections in order to protect against rodents and bad weather, for the duration of work (see picture 18, annex B). Temporarily remove door, rails, hardware and equipment. Keep and paint the existing door frame and seal the contour. Reconnect all equipment and test to make sure everything is functional. The space behind the door frame at the top, where pass two pipes shall be closed and sealed to prevent accumulating dust, water and bacteria.
-

All other terms and conditions remain the same