

PART 1 GENERAL

1.1 RELATED REQUIREMENT

- .1 Section 01 35 29.07 – Health and Safety.

1.2 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, if necessary, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.3 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of adjacent buildings, occupants of these buildings and the public. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing utilities services to building and provide access for professionals and vehicles.
- .3 Where security is reduced by work provide temporary means to maintain security of goods and people on the premises.
- .4 Install and maintain sanitary facilities for the personnel.

1.4 MODIFICATIONS, REPAIRS

- .1 Execute work with least possible interference or disturbance to normal use of adjacent buildings, occupants of these buildings and the public. Make arrangements with Departmental Representative to facilitate work as stated.

1.5 EXISTING SERVICES

- .1 Notify Departmental Representative and utility companies of intended interruption of services and obtain required permission before proceeding.
- .2 Notify Departmental Representative of any interruption of services at least 48 hours ahead of electrical service interruptions and minimise duration.
- .3 Provide for personnel, pedestrian and vehicular traffic.
- .4 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

1.6 SPECIAL REQUIREMENTS

- .1 Carry out noise generating work Monday to Friday, from 7 a.m. to 6 p.m.
- .2 Submit schedule in accordance with Section 01 32 16.07 - Construction Progress Schedule.
- .3 Ensure personnel working on the site are familiar and comply with fire safety, vehicular circulation and work safety regulations.
- .4 Remain within work and access boundaries.
- .5 Work schedule and site access by Contractor's vehicles is between 7 a.m. and 6 p.m. Equipment maintenance is not allowed outside the work schedule. Waiting vehicles must turn off engines.
- .6 Deliver materials outside peak traffic periods, i.e., between 9 a.m. and 3 p.m., unless indicated otherwise by Departmental Representative. Deliveries outside the work schedule are not allowed.

1.7 RESTRICTIONS TO CIRCULATION

- .1 The access leading to the parking can't be completely block during work and allow circulation in both directions. If circulation must be partially blocked, obtain authorization from the Departmental Representative and approval for signage plan before proceeding. The signage plan must be adapted to MTQ signage, signed and stamped by an engineer who is a member of the OIQ and submitted at least seven days before signs are put in place, as indicated in previous articles of this specification.

PART 2 PRODUCT

2.1 NOT USED.

- .1 Not used.

PART 3 EXECUTION

3.1 NOT USED.

- .1 Not used.

END OF SECTION