

PART 1 GENERAL

1.1 RELATED REQUIREMENTS

- .1 Not used.

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
 - .2 CAN/CGSB 1.189 00, Exterior Alkyd Primer for Wood.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA-O121-FM1978(C2003), Douglas Fir Plywood.

1.3 INSTALLATION AND REMOVAL

- .1 Provide, put in place or develop temporary accesses and protections works in order to execute the Works expeditiously.
- .2 Remove from site all such work after use.

1.4 PALISADES

- .1 Erect around the site temporary site enclosures consisting of 2.40 metre snow fence, attached with metal wire to T post spaced 2.40 centre, with lockable access gates to construction site.
- .2 Maintain snow fence throughout work period.
- .3 Install fences around trees and vegetation to protect them from against damage caused by construction material or operations.
- .4 Fence in excavation not backfilled at the end of the work day to the satisfaction of the Departmental Representative.

1.5 GUARD RAILS AND BARRICADES

- .1 Provide and install secure, rigid guard rails and barricades around deep excavations and steep slopes.

1.6 ACCESS TO SITE

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

1.7 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators and necessary devices required to perform Work and protect public in compliance with Volume V of the Québec Road safety code.

1.8 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.9 PROTECTION FOR NEIGHBOURING PRIVATE AND PUBLIC PROPERTIES

- .1 Protect surrounding private and public properties from any damages that could occur as a result from performance of Work.
- .2 As case may occur, assume entire responsibility for caused damages.

1.10 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and /or recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 2 PRODUCT

2.1 NOT USED

- .1 Not Used.

PART 3 EXÉCUTION

3.1 NOT USED

- .1 Not Used.

END OF SECTION