

Upland Reconstruction
River of Ponds, NL
R.082409.001

Page 1
2016-05-05

- | | |
|--|---|
| <u>1.1 ACCESS</u> | <ul style="list-style-type: none">.1 Provide and maintain adequate access to project site..2 Maintain access roads for duration of contract and make good damage resulting from Contractors' use of roads. |
| <u>1.2 CONTRACTOR'S SITE OFFICE</u> | <ul style="list-style-type: none">.1 Be responsible for and provide own site office, if required, including electricity, heat, lights and telephone. Locate site office as directed by Departmental Representative. |
| <u>1.3 DEPARTMENTAL REPRESENTATIVE'S SITE OFFICE</u> | <ul style="list-style-type: none">.1 Provide or construct a separate site office for the use of the Departmental Representative and the Site Representative. The building must be in place prior to commencement of work..2 Provide heating system to maintain 22°C inside temperature at -20°C outside temperature..3 The building will be approximately 2400 mm x 3600 mm. It will have a suitable frame covered with a weatherproof siding and lined with plywood or other approved material. The floor will be of 19 mm thick material. It will be provided with suitable window with at least 1 m² of glass and arranged to provide at least 0.5 m² of screened opening. The door will be fitted with a lockset and 2 keys..4 The office will be equipped with a drafting chair and a 900 mm x 1500 mm table having a hinged, smooth wooden top suitable for drafting..5 Install electrical lighting system to provide minimum 750 lux using surface mounted, shielded commercial fixtures with 10% upward |

Upland Reconstruction
River of Ponds, NL
R.082409.001

Page 2
2016-05-05

light component.

- .6 Maintain office in clean condition.
- .7 Arrange and pay for telephone and facsimile machine in the Departmental Representative's Office for Site Representative's exclusive use. Long distance calls or faxes placed on this phone by the Departmental Representative or the Site Representative, as part of normal monitoring activities will be paid by the Contractor.
- .8 Contractor may, on approval of Departmental Representative, provide cellular or mobile phone. If approval to use cellular or mobile phone is granted, be responsible for all services, airtime, license and network access fees, and all other fees or charges required to utilize the phone as intended by the manufacturer.

1.4 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.5 POWER

- .1 Arrange, pay for and maintain temporary electrical power supply in accordance with governing regulations and ordinances.
- .2 Supply and install all temporary facilities for power such as pole lines and underground cables to approval of local power supply authority.

1.6 WATER SUPPLY

- .1 Arrange, pay for and maintain temporary water supply in accordance with governing

Upland Reconstruction
River of Ponds, NL
R.082409.001

Page 3
2016-05-05

regulations and ordinances.

1.7 SCAFFOLDING

- .1 Design, construct and maintain scaffolding in rigid, secure and safe manner in accordance with CSA797-09.
- .2 Erect scaffolding independent of walls. Remove when no longer required.

1.8 CONSTRUCTION
SIGN AND NOTICES

- .1 Contractor or subcontractor advertisement signboards are not permitted on site.
- .2 Only notices of safety or instructions are permitted on site.
- .3 Safety and Instruction Signs and Notices:
 - .1 Signs and notices for safety and instruction shall be in both official languages.
- .4 Maintenance and Disposal of Site Signs:
 - .1 Maintain approved signs and notices in good condition for duration of project and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.9 REMOVAL OF
TEMPORARY
FACILITIES

- .1 Remove temporary facilities from site when directed by Departmental Representative.