

**Part 1            General**

**1.1                WORK COVERED BY CONTRACT DOCUMENTS**

- .1        Work of this Contract comprises upgrades for Penthouse Roof Access, located at 745 Logan Avenue, Winnipeg Manitoba; and further identified as Project No. R.067961.001.
- .2        Work of this Contract includes, but is not limited to:
  - .1            Cast in place concrete pad
  - .2            Precast concrete roof pavers
  - .3            Rooftop portable railing

**1.2                CONTRACT METHOD**

- .1        Construct Work under single stipulated price contract.

**1.3                CONTRACTOR USE OF PREMISES**

- .1        Limit use of premises for Work, to allow:
  - .1            Owner occupancy.
  - .2            Public usage.
- .2        Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .3        Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .4        Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by the Departmental Representative.
- .5        At completion of operations condition of existing work: equal to or better than that which existed before new work started.

**1.4                OWNER OCCUPANCY**

- .1        Owner will occupy premises during entire construction period for execution of normal operations.
- .2        Co-operate with Departmental Representative in scheduling operations to minimize conflict and to facilitate Owner usage.

**1.5                ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING**

- .1        Execute work with least possible interference or disturbance to second floor tenant. Arrange with Departmental Representative to facilitate execution of work.

**1.6                EXISTING SERVICES**

- .1        Notify Departmental Representative and utility companies of intended interruption of services and obtain required permission.

- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 5 days notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to pedestrian traffic, vehicular traffic and second floor tenant operations.
- .3 Provide alternative routes for personnel, pedestrian and vehicular traffic if normal routes are blocked.
- .4 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .5 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .6 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .7 Provide adequate bridging over trenches which cross sidewalks or roads to permit normal traffic.
- .8 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .9 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .10 Record locations of maintained, re-routed and abandoned service lines.
- .11 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

## **1.7 DOCUMENTS REQUIRED**

- .1 Maintain at job site, one copy each document as follows:
  - .1 Contract Drawings.
  - .2 Specifications.
  - .3 Addenda.
  - .4 Reviewed Shop Drawings.
  - .5 List of Outstanding Shop Drawings.
  - .6 Change Orders.
  - .7 Other Modifications to Contract.
  - .8 Field Test Reports.
  - .9 Copy of Approved Work Schedule.
  - .10 Health and Safety Plan and Other Safety Related Documents.
  - .11 Other documents as specified.

**Part 2            Products**

**2.1                NOT USED**

.1            Not used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not used.

**END OF SECTION**

**Part 1            General**

**1.1            ACCESS AND EGRESS**

- .1    Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

**1.2            USE OF SITE AND FACILITIES**

- .1    Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2    Maintain existing services to building and provide for personnel and vehicle access.
- .3    Where security is reduced by work provide temporary means to maintain security.
- .4    Closures: protect work temporarily until permanent enclosures are completed.

**1.3            ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING**

- .1    Execute work with least possible interference or disturbance to building operations, occupants, public and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

**1.4            SPECIAL REQUIREMENTS**

- .1    Carry out noise generating Work Monday to Friday from 18:00 to 07:00 hours and on Saturdays, Sundays and statutory holidays.
- .2    Submit schedule in accordance with Section 01 32 16.07 Construction Progress Schedules - Bar (GANTT) Charts.
- .3    Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
- .4    Keep within limits of work and avenues of ingress and egress.
- .5    Ingress and egress of Contractor vehicles at site is limited.
- .6    Become familiar with the project site and obtain local information as required.
- .7    Construction will be performed during the full operation of the facility during normal working hours (7:00 am to 4:30 pm). Project phasing may need to be considered to ensure that disruption to the daily operation of the facilities is kept to a minimum. Sound generating work should be reviewed in advance to determine whether or not it must be carried out after hours.
- .8    All work can be completed during normal business hours with the exception of hot work, excessive noisy work, and work that will produce offensive or harmful odors/fumes.
- .9    Environmental conditions must be kept under control during all phases of the work.

**1.5 SECURITY**

- .1 No security requirements are necessary for the contractor while working on the exterior of the facility.
- .2 The contractors must be escorted when they need to access the roof. PHAC will provide this service at no cost.
- .3 Contractor to provide exterior roof access during construction work to minimize facility access.
- .4 Roof access through the facility is limited to mobilization, inspections, emergency situations and de-mobilization.

**1.6 BUILDING SMOKING ENVIRONMENT**

- .1 Comply with smoking restrictions. Smoking is not permitted.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1 General**

**1.1 APPOINTMENT AND PAYMENT**

- .1 Departmental Representative will appoint and pay for services of testing laboratory except follows:
  - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
  - .2 Inspection and testing performed exclusively for Contractor's convenience.
  - .3 Testing, adjustment and balancing of conveying systems, mechanical and electrical equipment and systems.
  - .4 Mill tests and certificates of compliance.
  - .5 Tests specified to be carried out by Contractor under supervision of Departmental Representative.
- .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental Representative to verify acceptability of corrected work.
- .3 All testing required in specifications is Quality Control testing to be carried out by certified material testing laboratory engaged and paid by contractor. No separate payment will be made to contractor for Quality Control testing. Include cost in lump sum price.
- .4 Departmental Representative may engage an independent Testing laboratory to carry out additional random Quality assurance testing. Departmental Representative will pay for this to the lab directly.

**1.2 CONTRACTOR'S RESPONSIBILITIES**

- .1 Provide labour, equipment and facilities to:
  - .1 Provide access to Work for inspection and testing.
  - .2 Facilitate inspections and tests.
  - .3 Make good Work disturbed by inspection and test.
  - .4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
- .2 Notify Departmental Representative 48 hours minimum sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test.
- .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
- .4 Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative.

**Part 2            Products**

**2.1                NOT USED**

.1            Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**

**Part 1            General**

**1.1                ADMINISTRATIVE**

- .1     Schedule and administer project meetings throughout the progress of the work at the call of Departmental Representative.
- .2     Prepare agenda for meetings.
- .3     Distribute written notice of each meeting four days in advance of meeting date to Departmental Representative.
- .4     Meetings will be held at PHAC. Coordination for meeting space with Departmental Representative is required.
- .5     Preside at meetings.
- .6     Record the meeting minutes. Include significant proceedings and decisions. Identify actions by parties.
- .7     Reproduce and distribute copies of minutes within three days after meetings and transmit to meeting participants and, affected parties not in attendance.
- .8     Representative of Contractor, Subcontractor and suppliers attending meetings will be qualified and authorized to act on behalf of party each represents.

**1.2                PRECONSTRUCTION MEETING**

- .1     Within 15 days after award of Contract, request a meeting of parties in contract to discuss and resolve administrative procedures and responsibilities.
- .2     Departmental Representative, Contractor, major Subcontractors, field inspectors and supervisors will be in attendance.
- .3     Establish time and location of meeting and notify parties concerned minimum 5 days before meeting.
- .4     Incorporate mutually agreed variations to Contract Documents into Agreement, prior to signing.
- .5     Agenda to include:
  - .1     Appointment of official representative of participants in the Work.
  - .2     Schedule of Work: in accordance with Section 01 32 16.07 - Construction Progress Schedules - Bar (GANTT) Chart.
  - .3     Schedule of submission of shop drawings, samples, colour chips. Submit submittals in accordance with Section 01 33 00 - Submittal Procedures.
  - .4     Requirements for temporary facilities, site sign, offices, storage sheds, utilities, fences in accordance with Section 01 52 00 - Construction Facilities.
  - .5     Delivery schedule of specified equipment.
  - .6     Site security in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.
  - .7     Proposed changes, change orders, procedures, approvals required, mark-up percentages permitted, time extensions, overtime, administrative requirements.

- .8 Owner provided products.
- .9 Record drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .10 Maintenance manuals in accordance with Section 01 78 00 - Closeout Submittals.
- .11 Take-over procedures, acceptance, warranties in accordance with Section 01 78 00 - Closeout Submittals.
- .12 Monthly progress claims, administrative procedures, photographs, hold backs.
- .13 Appointment of inspection and testing agencies or firms.
- .14 Insurances, transcript of policies.

### **1.3 PROGRESS MEETINGS**

- .1 During course of Work and 8 days prior to project completion, schedule progress meetings every 2 weeks.
- .2 Contractor, major Subcontractors involved in Work, Departmental Representative and Consultants are to be in attendance.
- .3 Notify parties minimum 14 days prior to meetings.
- .4 Record minutes of meetings and circulate to attending parties and affected parties not in attendance.
- .5 Agenda to include the following:
  - .1 Review, approval of minutes of previous meeting.
  - .2 Review of Work progress since previous meeting.
  - .3 Field observations, problems, conflicts.
  - .4 Problems which impede construction schedule.
  - .5 Review of off-site fabrication delivery schedules.
  - .6 Corrective measures and procedures to regain projected schedule.
  - .7 Revision to construction schedule.
  - .8 Progress schedule, during succeeding work period.
  - .9 Review submittal schedules: expedite as required.
  - .10 Maintenance of quality standards.
  - .11 Review proposed changes for effect on construction schedule and on completion date.
  - .12 Other business.

## **Part 2 Products**

### **2.1 NOT USED**

- .1 Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**

## **Part 1 General**

### **1.1 DEFINITIONS**

- .1 Activity: element of Work performed during course of Project. Activity normally has expected duration, and expected cost and expected resource requirements. Activities can be subdivided into tasks.
- .2 Bar Chart (GANTT Chart): graphic display of schedule-related information. In typical bar chart, activities or other Project elements are listed down left side of chart, dates are shown across top, and activity durations are shown as date-placed horizontal bars. Generally Bar Chart should be derived from commercially available computerized project management system.
- .3 Baseline: original approved plan (for project, work package, or activity), plus or minus approved scope changes.
- .4 Construction Work Week: Monday to Friday, inclusive, will provide five day work week and define schedule calendar working days as part of Bar (GANTT) Chart submission.
- .5 Duration: number of work periods (not including holidays or other nonworking periods) required to complete activity or other project element. Usually expressed as workdays or workweeks.
- .6 Master Plan: summary-level schedule that identifies major activities and key milestones.
- .7 Milestone: significant event in project, usually completion of major deliverable.
- .8 Project Schedule: planned dates for performing activities and the planned dates for meeting milestones. Dynamic, detailed record of tasks or activities that must be accomplished to satisfy Project objectives. Monitoring and control process involves using Project Schedule in executing and controlling activities and is used as basis for decision making throughout project life cycle.
- .9 Project Planning, Monitoring and Control System: overall system operated by Departmental Representative to enable monitoring of project work in relation to established milestones.

### **1.2 REQUIREMENTS**

- .1 Ensure Master Plan and Detail Schedules are practical and remain within specified Contract duration.
- .2 Plan to complete Work in accordance with prescribed milestones and time frame.
- .3 Limit activity durations to maximum of approximately 10 working days, to allow for progress reporting.
- .4 Ensure that it is understood that Award of Contract or time of beginning, rate of progress, Interim Certificate and Final Certificate as defined times of completion are of essence of this contract.

### **1.3 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit to Departmental Representative within working days of Award of Contract Bar (GANTT) Chart as Master Plan for planning, monitoring and reporting of project progress.
- .3 Submit Project Schedule to Departmental Representative within 5 working days of receipt of acceptance of Master Plan.

### **1.4 PROJECT MILESTONES**

- .1 Project milestones form interim targets for Project Schedule.
  - .1 Interim Certificate (Substantial Completion) by March 31, 2016.
  - .2 Milestones to be included but not limited to:
    - .1 Contract Award
    - .2 Site Survey
    - .3 Concrete Work
    - .4 Roof Safety Restrain Work
    - .5 Precast Concrete Unit Paving Work
    - .6 O&M manual submission
    - .7 Record Drawing Submission
    - .8 Site Mobilization
    - .9 Substantial Completion

### **1.5 MASTER PLAN**

- .1 Structure schedule to allow orderly planning, organizing and execution of Work as Bar Chart (GANTT).
- .2 Departmental Representative will review and return revised schedules within 5 working days.
- .3 Revise impractical schedule and resubmit within 5 working days.
- .4 Accepted revised schedule will become Master Plan and be used as baseline for updates.

### **1.6 PROJECT SCHEDULE**

- .1 Develop detailed Project Schedule derived from Master Plan.
- .2 Ensure detailed Project Schedule includes as minimum milestone and activity types as follows:
  - .1 Award.
  - .2 Shop Drawings, Samples.
  - .3 Permits.
  - .4 Mobilization.
  - .5 Testing.

- .6 Supplied equipment long delivery items.

## **1.7 PROJECT SCHEDULE REPORTING**

- .1 Update Project Schedule on weekly basis reflecting activity changes and completions, as well as activities in progress.
- .2 Include as part of Project Schedule, narrative report identifying Work status to date, comparing current progress to baseline, presenting current forecasts, defining problem areas, anticipated delays and impact with possible mitigation.

## **1.8 PROJECT MEETINGS**

- .1 Discuss Project Schedule at regular site meetings, identify activities that are behind schedule and provide measures to regain slippage. Activities considered behind schedule are those with projected start or completion dates later than current approved dates shown on baseline schedule.
- .2 Weather related delays with their remedial measures will be discussed and negotiated.

## **Part 2 Products**

### **2.1 NOT USED**

- .1 Not used.

## **Part 3 Execution**

### **3.1 NOT USED**

- .1 Not used.

**END OF SECTION**

**Part 1            General**

**1.1            ADMINISTRATIVE**

- .1      Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2      Do not proceed with Work affected by submittal until review is complete.
- .3      Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4      Where items or information is not produced in SI Metric units converted values are acceptable.
- .5      Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6      Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7      Verify field measurements and affected adjacent Work are co-ordinated.
- .8      Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9      Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10     Keep one reviewed copy of each submission on site.

**1.2           SHOP DRAWINGS AND PRODUCT DATA**

- .1      The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2      Submit drawings stamped and signed by professional engineer registered or licensed in Manitoba.
- .3      Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .4      Allow 7 days for Departmental Representative's review of each submission.
- .5      Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.

- .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
- .7 Accompany submissions with transmittal letter containing:
  - .1 Date.
  - .2 Project title and number.
  - .3 Contractor's name and address.
  - .4 Identification and quantity of each shop drawing, product data and sample.
  - .5 Other pertinent data.
- .8 Submissions include:
  - .1 Date and revision dates.
  - .2 Project title and number.
  - .3 Name and address of:
    - .1 Subcontractor.
    - .2 Supplier.
    - .3 Manufacturer.
  - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
  - .5 Details of appropriate portions of Work as applicable:
    - .1 Fabrication.
    - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
    - .3 Setting or erection details.
    - .4 Capacities.
    - .5 Performance characteristics.
    - .6 Standards.
    - .7 Operating weight.
    - .8 Relationship to adjacent work.
- .9 After Departmental Representative's review, distribute copies.
- .10 Submit one (1) electronic copy of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .11 Submit one (1) electronic copy of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.
- .12 Submit one (1) electronic copy of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
  - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
  - .2 Testing must have been within 3 years of date of contract award for project.

- .13 Submit one (1) electronic copy of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
  - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
  - .2 Certificates must be dated after award of project contract complete with project name.
- .14 Submit one (1) electronic copy of manufacturers' instructions for requirements requested in specification Sections and as requested by Departmental Representative.
  - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .15 Submit one (1) electronic copy of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
- .16 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .17 Submit one (1) electronic copy of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .18 Delete information not applicable to project.
- .19 Supplement standard information to provide details applicable to project.
- .20 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .21 The review of shop drawings by Departmental Representative is for sole purpose of ascertaining conformance with general concept.
  - .1 This review shall not mean that Departmental Representative approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
  - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

### **1.3 PHOTOGRAPHIC DOCUMENTATION**

- .1 Submit electronic copy of digital photography in jpg format, fine resolution monthly with progress statement and as directed by Departmental Representative.
- .2 Project identification: name and number of project and date of exposure indicated.
- .3 Number of viewpoints: 2 locations.

- .1 Viewpoints and their location as determined by Departmental Representative.
- .4 Frequency of photographic documentation: weekly and as directed by Departmental Representative.
  - .1 Also, upon completion of Work, before concealment.

**1.4 CERTIFICATES AND TRANSCRIPTS**

- .1 Immediately after award of Contract, submit Workers' Compensation Board of Manitoba status.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

## **Part 1 General**

### **1.1 REFERENCES**

- .1 Definitions:
  - .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humans; or degrade environment aesthetically, culturally and/or historically.
  - .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction.
- .2 Reference Standards:
  - .1 U.S. Environmental Protection Agency (EPA)/Office of Water
    - .1 EPA 832/R-92-005-92, Storm Water Management for Construction Activities, Chapter 3.

### **1.2 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Submit copies of WHMIS MSDS.
- .3 Before commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review and approval by Departmental Representative.
- .4 Environmental Protection Plan must include comprehensive overview of known or potential environmental issues to be addressed during construction.
- .5 Address topics at level of detail commensurate with environmental issue and required construction tasks.
- .6 Include in Environmental Protection Plan:
  - .1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
  - .2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
  - .3 Names and qualifications of persons responsible for training site personnel.
  - .4 Descriptions of environmental protection personnel training program.
  - .5 Spill Control Plan to include procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
  - .6 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
  - .7 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, are contained on project site.

- .8 Contaminant Prevention Plan identifying potentially hazardous substances to be used on job site; intended actions to prevent introduction of such materials into air, water, or ground; and detailing provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.

### **1.3 FIRES**

- .1 Fires and burning of rubbish on site is not permitted.

### **Part 2 Products**

#### **2.1 NOT USED**

- .1 Not Used.

### **Part 3 Execution**

#### **3.1 CLEANING**

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

**END OF SECTION**

**Part 1            General**

**1.1                REFERENCES AND CODES**

- .1        Perform Work in accordance with National Building Code of Canada (NBC), complete with Manitoba Amendments and compliance with City of Winnipeg as the Authority having Jurisdiction, including amendments up to tender closing date and other codes of provincial or local application provided that in case of conflict or discrepancy, more stringent requirements apply.
- .2        Meet or exceed requirements of:
  - .1            Contract documents.
  - .2            Specified standards, codes and referenced documents.

**1.2                HAZARDOUS MATERIAL DISCOVERY**

- .1        Asbestos: demolition of spray or trowel-applied asbestos is hazardous to health. Stop work immediately when material resembling spray or trowel-applied asbestos is encountered during demolition work. Notify Departmental Representative.
- .2        PCB: Polychlorinated Biphenyl: stop work immediately when material resembling Polychlorinated Biphenyl is encountered during demolition work. Notify Departmental Representative.
- .3        Mould: stop work immediately when material resembling mould is encountered during demolition work. Notify Departmental Representative.

**1.3                BUILDING SMOKING ENVIRONMENT**

- .1        Comply with smoking restrictions and municipal by-laws.
- .2        No smoking allowed on premises.

**Part 2            Products**

**2.1                NOT USED**

- .1        Not Used.

**Part 3            Execution**

**3.1                NOT USED**

- .1        Not Used.

**END OF SECTION**

**Part 1            General**

**1.1                INSPECTION**

- .1      Allow Departmental Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2      Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Departmental Representative instructions, or law of Place of Work.
- .3      If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4      Departmental Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, Departmental Representative shall pay cost of examination and replacement.

**1.2                INDEPENDENT INSPECTION AGENCIES**

- .1      Independent Inspection/Testing Agencies will be engaged by Departmental Representative for purpose of inspecting and/or testing portions of Work. Cost of such services will be borne by Departmental Representative.
- .2      Provide equipment required for executing inspection and testing by appointed agencies.
- .3      Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4      If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to Departmental Representative. Pay costs for retesting and re-inspection.
- .5      All testing required in specifications is Quality Control testing to be carried out by certified material testing laboratory engaged and paid by contractor. No separate payment will be made to contractor for Quality Control testing. Include cost in lump sum price.
- .6      Departmental Representative may engage an independent Testing laboratory to carry out additional random Quality assurance testing. Departmental Representative will pay for this to the lab directly.

**1.3                ACCESS TO WORK**

- .1      Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2      Co-operate to provide reasonable facilities for such access.

#### **1.4 PROCEDURES**

- .1 Notify appropriate agency and Departmental Representative in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

#### **1.5 REJECTED WORK**

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Departmental Representative as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Departmental Representative, it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by .

#### **1.6 REPORTS**

- .1 Submit 4 copies of inspection and test reports to Departmental Representative.
- .2 Provide copies to subcontractor of work being inspected or tested.

#### **1.7 TESTS AND MIX DESIGNS**

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Departmental Representative and may be authorized as recoverable.

#### **1.8 MOCK-UPS**

- .1 Prepare mock-ups for Work specifically requested in specifications. Include for Work of Sections required to provide mock-ups.
- .2 Construct in locations as specified in specific Section and as acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative review with reasonable promptness and in orderly sequence, to not cause delays in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing schedule fixing dates for preparation.

- .6 Specification section identifies whether mock-up may remain as part of Work or if it is to be removed and when.

**1.9 MILL TESTS**

- .1 Submit mill test certificates as required of specification Sections.

**1.10 EQUIPMENT AND SYSTEMS**

- .1 Submit adjustment and balancing reports for mechanical, electrical and building equipment systems.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1            General**

**1.1                ACTION AND INFORMATIONAL SUBMITTALS**

- .1        Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

**1.2                INSTALLATION AND REMOVAL**

- .1        Provide temporary utilities controls in order to execute work expeditiously.
- .2        Remove from site all such work after use.

**1.3                DEWATERING**

- .1        Provide temporary drainage and pumping facilities to keep excavations and site free from standing water.

**1.4                WATER SUPPLY**

- .1        Hose bibs are available to the contractor and are located on the exterior of the facility close to the proposed construction site area. Contractor to take measures (heating and hoarding, pipe tracing heating cables etc.) to prevent pipes from freezing.

**1.5                TEMPORARY HEATING AND VENTILATION**

- .1        Provide temporary heating required during construction period, including attendance, maintenance and fuel.
- .2        Solid fuel salamanders are not permitted.
- .3        Provide temporary heat and ventilation in enclosed areas as required to:
  - .1        Facilitate progress of Work.
  - .2        Protect Work and products against dampness and cold.
  - .3        Prevent moisture condensation on surfaces.
  - .4        Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
  - .5        Provide adequate ventilation to meet health regulations for safe working environment.
- .4        Maintain temperatures of minimum 10 degrees C in areas where construction is in progress.
- .5        Ventilating:
  - .1        Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.
  - .2        Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
  - .3        Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
  - .4        Ventilate storage spaces containing hazardous or volatile materials.

- .5 Ventilate temporary sanitary facilities.
- .6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.
- .6 Pay costs for maintaining temporary heat.
- .7 Maintain strict supervision of operation of temporary heating and ventilating equipment to:
  - .1 Conform with applicable codes and standards.
  - .2 Enforce safe practices.
  - .3 Prevent abuse of services.
  - .4 Prevent damage to finishes.
  - .5 Vent direct-fired combustion units to outside.
- .8 Be responsible for damage to Work due to failure in providing adequate heat and protection during construction.

#### **1.6 TEMPORARY POWER AND LIGHT**

- .1 Exterior junction boxes are available for Contractor to use hand tools and lighting.
- .2 Provide and maintain temporary lighting throughout project.

#### **1.7 TEMPORARY COMMUNICATION FACILITIES**

- .1 Provide and pay for temporary telephone, fax and data hook up, lines and equipment necessary for own use and use of Departmental Representative.

#### **1.8 FIRE PROTECTION**

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

### **Part 2 Products**

#### **2.1 NOT USED**

- .1 Not Used.

### **Part 3 Execution**

#### **3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1 General**

**1.1 REFERENCES**

- .1 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
  - .2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
- .2 Canadian Standards Association (CSA International)
  - .1 CSA-0121-M1978(R2003), Douglas Fir Plywood.
  - .2 CAN/CSA-S269.2-M1987(R2003), Access Scaffolding for Construction Purposes.
  - .3 CAN/CSA-Z321-96(R2001), Signs and Symbols for the Occupational Environment.

**1.2 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

**1.3 INSTALLATION AND REMOVAL**

- .1 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, number of trailers to be used, avenues of ingress/egress to fenced area and details of fence installation.
- .2 Identify areas which have to be gravelled to prevent tracking of mud.
- .3 Indicate use of supplemental or other staging area.
- .4 Provide construction facilities in order to execute work expeditiously.
- .5 Remove from site all such work after use.

**1.4 SITE STORAGE/LOADING**

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.
- .3 5 parking stalls located on the far east side of the parking lot will be reserved for the contractor as staging area. Staging area to be used for storing materials, site trailer, parking equipment etc. but not for parking cars.

**1.5 CONSTRUCTION PARKING**

- .1 Parking will not be permitted on site.
- .2 No contractor parking is available on-site. Parking is available on side streets.

**1.6 SECURITY**

- .1 Provide and pay for responsible security personnel to guard site and contents of site after working hours and during holidays.

**1.7 SANITARY FACILITIES**

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.
- .3 Locate sanitary facilities at exterior building and as directed by Departmental Representative.

**1.8 EQUIPMENT, TOOL AND MATERIALS STORAGE**

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

**1.9 PROTECTION AND MAINTENANCE OF TRAFFIC**

- .1 Protect travelling public from damage to person and property.
- .2 Contractor's traffic on roads selected for hauling material to and from site to interfere as little as possible with public traffic.
- .3 Contractor: responsible for repair of damage to roads caused by construction operations.
- .4 Provide necessary lighting, signs, barricades, and distinctive markings for safe movement of traffic.
- .5 Dust control: adequate to ensure safe operation at all times.
- .6 Provide snow removal during period of Work.

**1.10 HEATING, HOARDING & SNOW REMOVAL**

- .1 Ensure all heating, hoarding and snow removal is provided for winter/spring construction to complete Work.

**1.11 CLEAN-UP**

- .1 Remove construction debris, waste materials, packaging material from work site daily.
- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

**Part 2            Products**

**2.1                NOT USED**

.1            Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**

**Part 1 General**

**1.1 INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

**1.2 ACCESS TO SITE**

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

**1.3 FIRE ROUTES**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

**1.4 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

**1.5 PROTECTION OF BUILDING FINISHES**

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

**1.6 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for recycling.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1            General**

**1.1            EXISTING SERVICES**

- .1        Before commencing work, establish location and extent of service lines in area of Work and notify Departmental Representative of findings.

**1.2            LOCATION OF EQUIPMENT AND FIXTURES**

- .1        Location of equipment, fixtures and outlets indicated or specified are to be considered as approximate.
- .2        Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3        Inform Departmental Representative of impending installation and obtain approval for actual location.
- .4        Submit field drawings to indicate relative position of various services and equipment when required by Departmental Representative.

**1.3            RECORDS**

- .1        Maintain a complete, accurate log of control and survey work as it progresses.
- .2        On completion of foundations and major site improvements, prepare a certified survey showing dimensions, locations, angles and elevations of Work.
- .3        Record locations of maintained, re-routed and abandoned service lines.

**1.4            ACTION AND INFORMATIONAL SUBMITTALS**

- .1        Submit name and address of Surveyor to Departmental Representative.
- .2        On request of Departmental Representative, submit documentation to verify accuracy of field engineering work.

**Part 2            Products**

**2.1            NOT USED**

- .1        Not Used.

**Part 3            Execution**

**3.1            NOT USED**

- .1        Not Used.

**END OF SECTION**

**Part 1            General**

**1.1            ACTION AND INFORMATIONAL SUBMITTALS**

- .1        Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Submit written request in advance of cutting or alteration which affects:
  - .1        Structural integrity of elements of project.
  - .2        Integrity of weather-exposed or moisture-resistant elements.
  - .3        Efficiency, maintenance, or safety of operational elements.
  - .4        Visual qualities of sight-exposed elements.
  - .5        Work of Owner or separate contractor.
- .3        Include in request:
  - .1        Identification of project.
  - .2        Location and description of affected Work.
  - .3        Statement on necessity for cutting or alteration.
  - .4        Description of proposed Work, and products to be used.
  - .5        Alternatives to cutting and patching.
  - .6        Effect on Work of Owner or separate contractor.
  - .7        Written permission of affected separate contractor.
  - .8        Date and time work will be executed.

**1.2            MATERIALS**

- .1        Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

**1.3            PREPARATION**

- .1        Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2        After uncovering, inspect conditions affecting performance of Work.
- .3        Beginning of cutting or patching means acceptance of existing conditions.
- .4        Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.
- .5        Provide protection from elements for areas which are to be exposed by uncovering work; maintain excavations free of water.

**1.4            EXECUTION**

- .1        Execute cutting, fitting, and patching including excavation and fill, to complete Work.
- .2        Fit several parts together, to integrate with other Work.
- .3        Uncover Work to install ill-timed Work.

- .4 Remove and replace defective and non-conforming Work.
- .5 Remove samples of installed Work for testing.
- .6 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.
- .7 Employ original installer to perform cutting and patching for weather-exposed and moisture-resistant elements, and sight-exposed surfaces.
- .8 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools not allowed on masonry work without prior approval.
- .9 Restore work with new products in accordance with requirements of Contract Documents.
- .10 Refinish surfaces to match adjacent finishes: Refinish continuous surfaces to nearest intersection. Refinish assemblies by refinishing entire unit.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1            General**

**1.1                PROJECT CLEANLINESS**

- .1        Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Owner or other Contractors.
- .2        Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site.
- .3        Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4        Provide on-site containers for collection of waste materials and debris.
- .5        Dispose of waste materials and debris off site.
- .6        Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.

**1.2                SUBSTANTIALLY PERFORMED CLEANING**

- .1        When Work is to be reviewed for substantial performance, ensure Work area is completely cleaned for proper review.
- .2        All tools and equipment are to be removed.
- .3        All surfaces of the Work are to be cleaned for proper review.

**1.3                FINAL CLEANING**

- .1        When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2        Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3        Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4        Remove waste products and debris other than that caused by Owner or other Contractors.
- .5        Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site.
- .6        Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7        Replace broken, scratched or disfigured glass.
- .8        Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds.
- .9        Remove dirt and other disfiguration from exterior surfaces.

**Part 2            Products**

**2.1                NOT USED**

.1            Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**

**Part 1 General**

**1.1 ADMINISTRATIVE REQUIREMENTS**

- .1 Acceptance of Work Procedures:
  - .1 Contractor's Inspection: Contractor: conduct inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
    - .1 Notify Departmental Representative in writing of satisfactory completion of Contractor's inspection and submit verification that corrections have been made.
    - .2 Request Departmental Representative inspection.
  - .2 Departmental Representative Inspection:
    - .1 Departmental Representative and Contractor to inspect Work and identify defects and deficiencies.
    - .2 Contractor to correct Work as directed.
  - .3 Completion Tasks: submit written certificates in English that tasks have been performed as follows:
    - .1 Work: completed and inspected for compliance with Contract Documents.
    - .2 Defects: corrected and deficiencies completed.
    - .3 Equipment and systems: tested, adjusted, balanced and fully operational.
    - .4 Certificates required by Fire Commissioner and Utility companies: submitted.
    - .5 Operation of systems: demonstrated to Owner's personnel.
    - .6 Work: complete and ready for final inspection.
  - .4 Final Inspection:
    - .1 When completion tasks are done, request final inspection of Work by Departmental Representative, and Contractor.
    - .2 When Work incomplete according to Departmental Representative, complete outstanding items and request re-inspection.

**1.2 FINAL CLEANING**

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**

**Part 1            General**

**1.1            ADMINISTRATIVE REQUIREMENTS**

- .1    Pre-warranty Meeting:
  - .1    Convene meeting one week prior to contract completion with Departmental Representative, in accordance with Section 01 31 19 - Project Meetings to:
    - .1    Verify Project requirements.
    - .2    Review warranty requirements and manufacturer's installation instructions.
  - .2    Departmental Representative to establish communication procedures for:
    - .1    Notifying construction warranty defects.
    - .2    Determine priorities for type of defects.
    - .3    Determine reasonable response time.
  - .3    Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.
  - .4    Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.

**1.2            ACTION AND INFORMATIONAL SUBMITTALS**

- .1    Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2    Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative, four final copies of operating and maintenance manuals in English.
- .3    Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4    Provide evidence, if requested, for type, source and quality of products supplied.

**1.3            FORMAT**

- .1    Organize data as instructional manual.
- .2    Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3    When multiple binders are used correlate data into related consistent groupings.
  - .1    Identify contents of each binder on spine.
- .4    Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.
- .5    Arrange content by systems, under Section numbers and sequence of Table of Contents.
- .6    Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7    Text: manufacturer's printed data, or typewritten data.

- .8 Drawings: provide with reinforced punched binder tab.
- .1 Bind in with text; fold larger drawings to size of text pages.

#### **1.4 CONTENTS - PROJECT RECORD DOCUMENTS**

- .1 Table of Contents for Each Volume: provide title of project;
  - .1 Date of submission; names.
  - .2 Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
  - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
  - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data.
  - .1 Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions specified in Section 01 45 00 - Quality Control.

#### **1.5 AS -BUILT DOCUMENTS AND SAMPLES**

- .1 Maintain, in addition to requirements in General Conditions, at site for Departmental Representative one record copy of:
  - .1 Contract Drawings.
  - .2 Specifications.
  - .3 Addenda.
  - .4 Change Orders and other modifications to Contract.
  - .5 Reviewed shop drawings, product data, and samples.
  - .6 Field test records.
  - .7 Inspection certificates.
  - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
  - .1 Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
  - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition.
  - .1 Do not use record documents for construction purposes.

- .5 Keep record documents and samples available for inspection by Departmental Representative.

## **1.6 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS**

- .1 Record information on set of black line opaque drawings.
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
  - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
  - .1 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
  - .2 Field changes of dimension and detail.
  - .3 Changes made by change orders.
  - .4 Details not on original Contract Drawings.
  - .5 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
  - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
  - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, field test records, required by individual specifications sections.
- .7 Provide digital photos, if requested, for site records.

## **1.7 MATERIALS AND FINISHES**

- .1 Building products, applied materials, and finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
  - .1 Provide information for re-ordering custom manufactured products.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-protection and weather-exposed products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .4 Additional requirements: as specified in individual specifications sections.

## **1.8 DELIVERY, STORAGE AND HANDLING**

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.

- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

## **1.9 WARRANTIES AND BONDS**

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.
- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.
- .6 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
  - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
  - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
  - .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
  - .4 Verify that documents are in proper form, contain full information, and are notarized.
  - .5 Co-execute submittals when required.
  - .6 Retain warranties and bonds until time specified for submittal.
- .7 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .8 Conduct 9 month warranty inspection, measured from time of acceptance, by Departmental Representative.
- .9 Include information contained in warranty management plan as follows:
  - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
  - .2 Listing and status of delivery of Certificates of Warranty for extended warranty items, to include roofs, HVAC balancing, pumps, motors, transformers, commissioned systems, fire protection, alarm systems, sprinkler systems, lightning protection systems.
  - .3 Provide list for each warranted equipment, item, feature of construction or system indicating:
    - .1 Name of item.

- .2 Model and serial numbers.
- .3 Location where installed.
- .4 Name and phone numbers of manufacturers or suppliers.
- .5 Names, addresses and telephone numbers of sources of spare parts.
- .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
- .7 Cross-reference to warranty certificates as applicable.
- .8 Starting point and duration of warranty period.
- .9 Summary of maintenance procedures required to continue warranty in force.
- .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
- .11 Organization, names and phone numbers of persons to call for warranty service.
- .12 Typical response time and repair time expected for various warranted equipment.
- .4 Contractor's plans for attendance at 4 and 9 month post-construction warranty inspections.
- .5 Procedure and status of tagging of equipment covered by extended warranties.
- .6 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.
- .10 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .11 Written verification to follow oral instructions.
  - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

#### **1.10 WARRANTY TAGS**

- .1 Tag, at time of installation, each warranted item. Provide durable, oil and water resistant tag approved by Departmental Representative.
- .2 Attach tags with copper wire and spray with waterproof silicone coating.
- .3 Leave date of acceptance until project is accepted for occupancy.
- .4 Indicate following information on tag:
  - .1 Type of product/material.
  - .2 Model number.
  - .3 Serial number.
  - .4 Contract number.
  - .5 Warranty period.
  - .6 Inspector's signature.
  - .7 Construction Contractor.

**Part 2            Products**

**2.1                NOT USED**

.1            Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**