



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving - PWGSC / Réception des soumissions
- TPSGC

11 Laurier St./11 rue Laurier

Place du Portage, Phase III

Core 0B2 / Noyau 0B2

Gatineau, Québec K1A 0S5

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Construction Services Division/Division des services de
construction

11 Laurier St./11 Rue Laurier

3C2, Place du Portage

Phase III

Gatineau, Québec K1A 0S5

Title - Sujet Roadway Resurfacing Project	
Solicitation No. - N° de l'invitation 39903-170144/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client 39903-170144	Date 2016-07-21
GETS Reference No. - N° de référence de SEAG PW-\$\$\$FG-359-71146	
File No. - N° de dossier fg359.39903-170144	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-08-11	Time Zone Fuseau horaire Eastern Daylight Saving Time EDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Benoit, Marie-Eve	Buyer Id - Id de l'acheteur fg359
Telephone No. - N° de téléphone (819) 420-0720 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Canadian Food Inspection. 59 rue Camelot Drive Ottawa, ON, K1A 0Y9 ATT: Celine Tremblay	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

39903-170144/A

Amd. No. - N° de la modif.

002

Buyer ID - Id de l'acheteur

FG359

Client Ref. No. - N° de réf. du client

39903-170144

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

THE PURPOSE OF THIS AMENDMENT IS TO ISSUE THE FOLLOWING:

1. EXTENSION TO BID CLOSING DATE

Please note that the tender closing date for this project is hereby EXTENDED from **August 9, 2016 at 2:00 p.m. to August 11, 2016 at 2:00 p.m.**

2. Appendix 1 – Combined Price Form (1 Page)

Delete in its entirety

and

Replace with Appendix 1 attached.

3. Addendum 001 attached.

When submitting a bid, please ensure that the updated Appendix 1 – Combined Price Form (2 Pages) is used.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME.

APPENDIX 1 - COMBINED PRICE FORM (2 pages)

- 1) The prices per unit shall govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

LUMP SUM

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.

	LUMP SUM AMOUNT (LSA) Excluding applicable tax(es)	
--	--	--

CASH ALLOWANCE (Section 01 21 00)

	CASH ALLOWANCE (CA) Excluding applicable tax(es)	\$18,500.00
--	--	-------------

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
- (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price Item.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(e)s extra (PU)	Extended amount (EQ x PU) applicable tax(e)s extra
Grading and Excavation						
1	31 22 13	Grading and Compaction of Granular Base	m2	35,259		
In-situ pulverization Light Duty pavement						
2	32 12 16	Superpave 12.5 mm for Light Duty Pavement	t	596		
3	32 12 16	Superpave 19 mm for Light Duty Pavement	t	596		
4	32 11 16.01	Granular A- 50mm leveling layer over all pulverized materials	t	730		
In-situ pulverization Heavy Duty pavement						
5	32 12 16	Superpave 12.5 mm for Heavy Duty Pavement	t	2535		
6	32 12 16	Superpave 19 mm for Heavy Duty Pavement	t	3,169		
7	32 11 16.01	Granular A- 50mm leveling layer over all pulverized materials	t	3,104		
Proposed Light Duty Pavement						

Solicitation No. - N° de l'invitation
39903-170144/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur
FG359

Client Ref. No. - N° de réf. du client
39903-170144

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(s) extra (PU)	Extended amount (EQ x PU) applicable tax(s) extra
8	32 12 16	Superpave 12.5 mm	t	58		
9	32 12 16	Superpave 19 mm	t	58		
10	32 11 16.01	Granular A	t	213		
11	32 11 23	Granular B Type II	t	391		
Proposed Heavy Duty Pavement						
12	32 12 16	Superpave 12.5 mm	t	27		
13	32 12 16	Superpave 19 mm	t	34		
14	32 11 16.01	Granular A	t	101		
15	32 11 23	Granular B Type II	t	231		
TOTAL EXTENDED AMOUNT (TEA) Excluding applicable tax(s)						

TOTAL BID AMOUNT (LSA + CA + TEA) Excluding applicable tax(s)	
---	--

The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.

DRAWINGS

Drawing C502 - Storm Manhole Schedule 'Ditch Inlet CB 34'

- 1 **DELETE:** 600X600mm. OPSD 705.010
- 2 **REPLACE with:** 600x1200mm. OPSD 705.040 type A

Drawing C502 - Storm Manhole Schedule 'CBMH 30'

- 1 **DELETE:** 1200mmØ. OPSD 701.010
- 2 **REPLACE with:** 2400mmØ. OPSD 701.013

Drawing C502 - Storm Manhole Schedule 'CBMH 11'; 'CBMH 13'; 'CBMH 21', and 'MHST 20A'

- 1 **DELETE:** 1200mmØ. OPSD 701.010
- 2 **REPLACE with:** 1500mmØ. OPSD 701.011

Drawing C501 – 101.0m - 600mm STORM SEWER @ 0.55% from MHST 20A to MHST 20C

- 1 **DELETE:** 101.0m – 600mm Storm Sewer @ 0.55%
- 2 **REPLACE with:** 86.0 m – 600mm Storm Sewer @ 0.58%

Drawing C501 - MHST 20C

- 1 **DELETE:** T/G = 93.81, INV (W) = 93.08, INV (E) =93.02
- 2 **REPLACE with:** T/G = 94.63, INV (W) = 93.13, INV (E) =93.10

Drawing C501 - 1050mm STORM SEWER @ 0.90% from MHST 20C to OUTLET 2

- 1 **DELETE:** 5.0 m – 1050 mm STORM SEWER @ 0.90%
- 2 **REPLACE with:** 20.0 m – 1050 mm STORM SEWER @ 0.65%

Drawing C401 and C402

- 1 Refer to revised drawings for line painting information.
- 2 **DELETE:** Drawing C401 issue for tender
- 3 **REPLACE with:** Drawing C401 issue for addendum 1

Drawing C101, C401, C402, C403

- 1 Refer to revised drawings for modification to extent of in-situ heavy duty pavement within entrance ways to existing buildings.
- 2 **DELETE:** Drawing C101 issue for tender
- 3 **REPLACE with:** Drawing C101 issue for addendum 1
- 4 **DELETE:** Drawing C401 issue for tender
- 5 **REPLACE with:** Drawing C401 issue for addendum 1
- 6 **DELETE:** Drawing C402 issue for tender
- 7 **REPLACE with:** Drawing C402 issue for addendum 1
- 8 **DELETE:** Drawing C403 issue for tender
- 9 **REPLACE with:** Drawing C403 issue for addendum 1

Drawing C404

- 1 **ADD:** Drawing C404 Grading Plan 4, detailing the grading within the guard house area.

Drawing C101 – Typical Pavement Structure for Works

- 1 **DELETE:** HL3
- 2 **DELETE:** HL8
- 3 **DELETE:** Surface Course, Heavy Duty Pavement 50 mm
- 4 **REPLACE with:** Surface Course, Heavy Duty Pavement 40 mm
- 5 **DELETE:** Binder Course, Heavy Duty Pavement 40 mm
- 6 **REPLACE with:** Binder Course, Heavy Duty Pavement 50 mm

Drawing C101 – Typical Pavement Structure for In-situ Pulverization

- 1 **DELETE:** HL3
- 2 **DELETE:** HL8

Drawing C601 – Typical New Road “D” Detail

- 1 **DELETE:** 50 mm Superpave 12.5
- 2 **REPLACE with:** 40 mm Superpave 12.5
- 3 **DELETE:** 40 mm Superpave 19.0
- 4 **REPLACE with:** 50 mm Superpave 19.0

Drawing C402 – Basketball Area

- 1 Refer to revised drawing C402 for reinstatement of basketball area.
- 2 **DELETE:** Drawing C402 issue for tender
- 3 **REPLACE with:** Drawing C402 issue for addendum 1

Drawing C202

- 1 **DELETE:** Reference to existing concrete slab and underground power lines at building 141.

Drawing C201, C202, C203, C204 - LEGEND

- 1 **DELETE:** Asphalt Removal
- 2 **REPLACE with:** Asphalt Removal (full depth)

Drawing C401 and C402

- 1 Road D - Refer to revised drawing C401 and C402. Road D is a new road with Heavy Duty Pavement.
- 2 **LEGEND: ADD:** Heavy duty pavement
- 3 **DELETE:** Drawing C401 issue for tender
- 4 **REPLACE with:** Drawing C401 issue for addendum 1
- 5 **DELETE:** Drawing C402 issue for tender
- 6 **REPLACE with:** Drawing C402 issue for addendum 1

Drawings C502 – Storm Piping Schedule - Material

From CBMH 4 TO CBMH 5

- 1 **DELETE:** PVC
- 2 **REPLACE with:** PVC/CONC

From CBMH 5 TO CBMH 6

- 1 **DELETE:** PVC
- 2 **REPLACE with:** PVC/CONC

From CBMH 6 TO CBMH 7

- 1 **DELETE:** PVC

2 **REPLACE with:** PVC/CONC

From CBMH 7 TO CBMH 11

1 **DELETE:** PVC

2 **REPLACE with:** PVC/CONC

From MHST 19 TO CBMH 30

1 **DELETE:** PVC

2 **REPLACE with:** PVC/CONC

From CBMH 30 TO CBMH 13

1 **DELETE:** PVC

2 **REPLACE with:** PVC/CONC

From CB 23 TO OUTLET 3

1 **DELETE:** PVC

2 **REPLACE with:** PVC/CONC

Drawing C305, C306, C308, C309 – Sta 1+290; Sta 1+330; Sta 1+350; Sta 1+380; Sta 1+400; Sta 1+630; Sta 1+980; Sta 2+020; Sta 2+050; Sta 2+090; Sta 2+110; Cross Culvert Sta 2+130; Cross culvert Sta 2+232; Cross Culvert Sta 2+291

1 **DELETE:** Culvert

2 **REPLACE with:** New Culvert

Drawing C101–

1 **ADD:** Typical Pavement Structure for In-Situ Pulverization - Light Duty Pavement – (Traffic Level B)

2 **ADD:** Typical Pavement Structure for In-Situ Pulverization - Heavy Duty Pavement – (Traffic Level B)

3 **ADD:** Typical Pavement Structure for Works - Light Duty Pavement – (Traffic Level B)

4 **ADD:** Typical Pavement Structure for Works – Heavy Duty Pavement – (Traffic Level D)

5 **DELETE:** Drawing C101 issue for tender

6 **REPLACE with:** Drawing C101 issue for addendum 1

Drawing C201 through C204 – General Notes

- 1 **ADD:** Remove and dispose of existing culverts off site. Promptly replace with new proposed culvert in order to continue access to the existing building area

SPECIFICATIONS**Section 32 91 19.13**

- 1 **DELETE:** In its entirety 1.1 Material Supplied by Department Representative / DCC Representative
- 2 **DELETE:** In its entirety 1.2 Measurement Procedures
- 3 **DELETE:** In its entirety 1.3 Basis of Payment

Section 01 14 25

- 1 Refer to attached sketch SK - 1 for location of asbestos containing pipe.

Section 32 93 10

- 1 **ADD:** 2.1.7 New trees: container grown or balled and burlapped, with a minimum height of 1.5 metres and single stem.

Section 01 21 00

- 1 **ADD:** 1.2 Cash Allowance .9 Amount of allowance of \$14,900.00 for purchase of and installation of miscellaneous signage located within the limit of scope (including stops signs, yield signs, no parking signs, handicap parking signs, etc.). The allowance also includes stop bar and tail marking, centerline of road painting, handicapped parking stall painting, and cross walk painting.

END OF ADDENDUM