



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

**Bid Receiving - PWGSC / Réception des soumissions
- TPSGC**

11 Laurier St. / 11, rue Laurier

Place du Portage, Phase III

Core 0B2 / Noyau 0B2

Gatineau, Québec K1A 0S5

Bid Fax: (819) 997-9776

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

**Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution

Electrical & Electronics Products Division
11 Laurier St./11, rue Laurier
7B3, Place du Portage, Phase III
Gatineau, Québec K1A 0S5

Title - Sujet CCTV AT ATLANTIC INSTITUTIONS	
Solicitation No. - N° de l'invitation 21120-169589/A	Amendment No. - N° modif. 009
Client Reference No. - N° de référence du client 21120-16-2209589	Date 2016-07-25
GETS Reference No. - N° de référence de SEAG PW-\$\$HN-461-70697	
File No. - N° de dossier hn461.21120-169589	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-08-04	Time Zone Fuseau horaire Eastern Daylight Saving Time EDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Hallman, Patti	Buyer Id - Id de l'acheteur hn461
Telephone No. - N° de téléphone (819) 420-0339 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Amendment 009 is issued to add additional questions to Attachment 002 – Questions and Answers

ATTACHMENT 2

QUESTIONS AND ANSWERS cont'd

- Q96** Nova Institute-There are some rear perimeter cameras that it was mentioned during site walk that are on fibre not copper due to length. Can we confirm this?
- A96** The breakdown of perimeter or PIDS cameras fibre and Cat 6 cabling is as detailed in the attached file "Nova PIDS Cameras Wiring"
- Q97** All sites- From looking at existing housings some are connected with Flex from box. Will this still be approved?
- A97** The existing flex conduit from a junction box to the existing camera housings is approved for reuse for camera replacements.
- Q98** All sites- In respect to new cameras and replacements with Dome cameras. Need confirmation we can transition from Rigid and junction box to Camera. There will not be sufficient space in the dome camera to install Cat6 Jack and patch cord. We will need a transition box to terminate in and then patch to camera.
- A98** Transition from rigid conduit to a junction box and then a patch cord to the camera is confirmed. The patch cable shall be installed in rigid conduit in inmate accessible areas.
- Q99** Springhill- Cameras 28 and 29 along fence line will have to be fibre due to excessive length. Are we going with Single mode to these as well and how will we transition from fibre to Copper?
- A99** Springhill cameras 28 and 29 shall use fibre meeting the specifications, the bidders are to determine how to transition from fibre to copper, generally this is done via the use of media converters.
- Q100** The documentation indicates that all of the workstations are to be rack mounted in the TER rooms; with extenders for the keyboard, monitor, mouse and PTZ controller (where indicated). Can you please confirm this or can the work stations be located locally at the desired location? Or if there is a mix, can you please indicated how many are to be rack mounted or local?
- A100** Confirmed, all workstations are to be mounted in the TER rooms.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED

NOVA PIDS Camera # Wiring

C-1	FIBRE AND THEN 100' OF COPPER
C-10	FIBRE
C-11	FIBRE
C-12	FIBRE
C-13	FIBRE
C-14	FIBRE
C-15	FIBRE
C-16	FIBRE
C-17	FIBRE
C-18	FIBRE
C-19	FIBRE
C-2	CAT-6
C-20	FIBRE
C-21	CAT-6
C-22	CAT-6
C-23	CAT-6
C-24	CAT-6
C-25	CAT-6
C-26	CAT-6
C-27	CAT-6
C-28	CAT-6
C-29	CAT-6
C-3	CAT-6
C-30	CAT-6
C-31	CAT-6
C-32	CAT-6
C-33	CAT-6
C-34	CAT-6
C-35	CAT-6 FROM FENCE MOUNTED SWITCH
C-4	CAT-6
C-49	CAT-6 FROM FENCE MOUNTED SWITCH
C-5	FIBRE
C-6	CAT-6 FROM FENCE MOUNTED SWITCH
C-7	CAT-6 FROM FENCE MOUNTED SWITCH
C-8	CAT-6 FROM FENCE MOUNTED SWITCH
C-9	FIBRE