



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British Columbia  
V6Z 0B9  
Bid Fax: (604) 775-9381

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution  
Public Works and Government Services Canada -  
Pacific Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> Fire Alarm System Replacement	
<b>Solicitation No. - N° de l'invitation</b> EZ899-170601/A	<b>Amendment No. - N° modif.</b> 003
<b>Client Reference No. - N° de référence du client</b>	<b>Date</b> 2016-07-26
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-019-7815	
<b>File No. - N° de dossier</b> PWY-6-39061 (019)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-08-12</b>	<b>Time Zone</b> Fuseau horaire Pacific Daylight Saving Time PDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Ngan, Ken (PWY)	<b>Buyer Id - Id de l'acheteur</b> pwy019
<b>Telephone No. - N° de téléphone</b> (604) 658-2755 ( )	<b>FAX No. - N° de FAX</b> (604) 775-6633
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> CSC - William Head institution - Metchosin, BC	


Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm (type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

This Solicitation Amendment 003 is raised to incorporate Questions and Answers received.

All other terms and conditions remain unchanged.

Q1: Building 29 balcony floor plan has a symbol  not indicated on the electrical schedules. Please confirm what it represents.

A1: The symbol consisting of a circle and rectangle at the top of the stairs is a fire extinguisher. There is no work associated with the fire extinguisher.

Q2: Test and inspection report lists two Duct smoke detectors for Building 103 but Four are shown on plan – with no indication any are new. Please confirm all four Duct Detectors are existing.

A2: All four duct smoke detectors are existing.

Q3: Drawing E06 Building 110 indicates flow switches will be added by others. Please confirm new flow / tampers required for buildings 30 & 105 are to be installed by the successful electrical contractor.

A3: The design of the new flow switches and associated piping has not been completed for Building 110. For that reason, the flow switches will be provided by others within Building 110. Provide sprinkler flow and tamper switches for other buildings including buildings 30 & 105 as indicated.

Q4: Please confirm if PWGSC will provide a staff member to cycle the existing sprinkler valves to verify the flows and tampers.

A4: Provide qualified workers as required to perform all tests including cycling of valves.

Q5: Please confirm security caulking notes for Building 109 – drawing E09 apply to new devices and rough in only.

A5: Provide security caulking for new work within cells. There is no requirement to provide security caulking for existing conduit or devices within the cells.

Q6: Please confirm if a fifteen or thirty foot service loop length should be provided at each of the fiber enclosures.

A6: Provide a 9-metre fully-jacketed service loop at each end of the fibre optic cables.

Q7: Appendix I recommends abatement (by a qualified contractor) of the asbestos in the kitchen building. From the information provided it appears that the potential impact to the contamination during the fire alarm project will be minimal. Please confirm there is no requirement under this tender package to carry an abatement contractor.

A7: Appendix A, "Project Specific Hazardous Building Materials Assessment" identifies hazardous materials and protocols to deal with the hazardous materials if impacted by work under this Contract. The intent of Appendix A is not to identify a requirement for abatement of asbestos containing material (ACM), unless abatement is required to complete the work under this Contract. As specified, where ACM will be impacted, provide an Asbestos Management Plan (AMP). An abatement contractor is required where abatement of ACM is necessary.