



- IDENTIFICATION(S):**
- NEW SLEEPERS FOR FAN TO BE PROVIDED AND INSTALLED.
 - REPLACE WITH NEW STAINLESS STEEL ONES ONCE ENVELOPE WORK IS COMPLETED.
 - 2500 EXHAUST BREECING CONNECTED TO DISCHARGE OF FAN TO BE REMOVED CW ALL SUPPORTS. REINSTALL EXHAUST DUCTWORK AND SUPPORT ONCE ENVELOPE WORK IS COMPLETED. EXHAUST DUCT WORK AND INSULATION TO BE EXTENDED TO RELOCATED FAN.
 - CONDUIT FEEDING FAN AND ROUTED INTO BUILDING THROUGH EXTERIOR WALL.
 - ROOF MOUNTED EXHAUST FAN TO BE TEMPORARILY REMOVED. RELOCATE EXHAUST FAN A MINIMUM OF 600mm FROM THE EDGE OF ROOF. REINSTATE SYSTEM ONCE ENVELOPE WORK IS COMPLETED. USE LONGITUDINAL AND LATERAL RESTRAINTS TO SECURE EXHAUST FAN TO EXTERIOR WALL. ROOF PENETRATIONS NOT PERMITTED.
 - DEMOLISH WOODEN SLEEPERS SUPPORTING FAN AND CONCRETE PATIO STONE.
 - WALL MOUNTED METAL STRAP HANGERS SUPPORTING FAN TO BE REMOVED.
 - WALL MOUNTED EXHAUST FAN TO BE REMOVED ALONG WITH SUPPORTS, ELECTRICAL CONNECTIONS AND ACCESSORIES. OPENING TO BE CLOSED. COORDINATE WITH ARCHITECTURAL DRAWINGS.
 - 610x610 EXTERIOR WALL LOUVER TO BE REMOVED AND REPLACED WITH NEW LOUVER.
 - 630x630 EXTERIOR WALL LOUVER TO BE REMOVED AND REPLACED WITH NEW LOUVER.
 - 710x710 EXTERIOR WALL LOUVER TO BE REMOVED AND REPLACED WITH NEW LOUVER.
 - REMOVE LOUVER AND DISCARD.
 - ELECTRICAL CONDUIT TO BE DISCONNECTED AND REMOVED BY DIVISION 26.
 - JUNCTION BOX ON WALL TO BE DISCONNECTED AND REMOVED BY DIVISION 26.
 - WALL MOUNTED EXHAUST FAN TO BE REMOVED ALONG WITH SUPPORTS AND ASSOCIATED ACCESSORIES.
 - EXISTING 75mm GAS PIPING THROUGH WALL INTO BUILDING TO REMAIN. CONNECTS INSIDE THE BUILDING TO BOTTLES AND OTHER EQUIPMENT.
 - 810x810 EXTERIOR WALL LOUVER TO BE REMOVED AND REPLACED WITH NEW.
 - WALL MOUNTED NATURAL GAS PIPING, 75mm. REFER TO NATURAL GAS PIPING DETAIL 1 AND 2 ON M-205 DRAWING FOR WORK TO BE DONE.
 - OVERHANG DRAIN PIPING, 50, TO BE REMOVED. REINSTALL AND EXTEND PIPING TO OTHER SIDE OF OVERHANG STRUCTURAL SUPPORT. INSTALL MESH SCREEN AT TERMINAISON OF PIPE AND PROVIDE NEW PIPING SUPPORT UNDER BUILDING OVERHANG.
 - BUILDING OVERHANG EXTENSION.
 - SUPPORT STRUCTURE FOR BUILDING OVERHANG.
 - WALL.
 - 4500 INSULATED DUCTWORK CONNECTED TO LOUVER TO REMAIN.
 - 700x700 EXTERIOR WALL LOUVER TO BE REMOVED AND REPLACED WITH NEW.
 - 500x500 EXTERIOR WALL LOUVER TO BE REMOVED AND REPLACED WITH NEW.
 - 500x500 PANEL IN OBSOLETE WALL PENETRATION WITH WOODEN BOARD INSIDE BUILDING TO BE REMOVED AND PATCH BY GENERAL CONTRACTOR. REFER TO ARCHITECTURAL DRAWINGS.
 - BUILDING STRUCTURAL BRACING.
 - 1500 UNINSULATED METAL DUCT THROUGH WALL.
 - 250x250 UNINSULATED DUCT THROUGH FLOOR. DUCT IS OPEN TO CEILING SPACE ABOVE FIRST FLOOR ROOMS.
 - 500 INSULATED CHILLED WATER PIPING THROUGH SPACE TO REMAIN.
 - EXISTING 150 CHILLED WATER PIPING FROM COOLING TOWER TO BE DISCONNECTED AT BUILDING PENETRATION. REINSTALL NEW PIPE AND INSULATION AT BUILDING PENETRATION AFTER BUILDING ENVELOPE IS REINSTALLED. INSTALL NEW SLEEVE FOR PIPE PENETRATION.
 - 50 WATER PIPING FROM COOLING TOWER TO BE DISCONNECTED AT BUILDING PENETRATION. REINSTALL NEW PIPE AND INSULATION AT BUILDING PENETRATION AFTER ENVELOPE WORK IS COMPLETED.
 - HOSE BIBB WITH LOCK KEY OPERATOR WALL MOUNTED AND FED FROM BUILDING INTERIOR. TO BE REMOVED AND REPLACED WITH NEW WALL HYDRANT.
 - WALL MOUNTED ELECTRICAL PANEL TO REMAIN. ASSOCIATED CONDUIT TO REMAIN. REFER TO ELECTRICAL DRAWINGS.
 - 250 DOMESTIC WATER PIPING THROUGH WALL TO EXTERIOR HOSE BIBB. PIPING IS ISOLATED BY BALL VALVE IN ROOM. LOWER HOSE BIBB IS EQUIPPED WITH BACKFLOW PREVENTER AND STRAINER ASSEMBLY.
 - CONDUIT TO ELECTRICAL PANEL TO BE REMOVED/DISCONNECTED. REFER TO ELECTRICAL DRAWINGS.
 - EXISTING GAS METER ASSEMBLY TO BE DEMOLISHED BY GAS UTILITY. REFER TO DETAIL 1 ON M-205.
 - 750 ISOLATED VALVE FOR GAS PIPING.

Public Works and Government Services Canada

Canadian Space Agency

PAGEAUMOREL

Cleland Jardine Engineering Limited

COLE+Associates ARCHITECTS

2.	ADDENDUM No 1	2016.07.28									
1.	ISSUED FOR TENDER	2016.05.01									
No.	Revision	Date									
PROFESSIONAL STAMP											
<table><tr><td>A</td><td>A detail no. du detail</td><td>A</td></tr><tr><td>C</td><td>C location drawing no. sur dessin no.</td><td>B</td></tr><tr><td></td><td>C drawing no. dessin no.</td><td>C</td></tr></table>			A	A detail no. du detail	A	C	C location drawing no. sur dessin no.	B		C drawing no. dessin no.	C
A	A detail no. du detail	A									
C	C location drawing no. sur dessin no.	B									
	C drawing no. dessin no.	C									
project											
DAVID FLORIDA LABORATORY											
BUILDING No. 65, SHIRLEY'S BAY, ONTARIO											
BUILDING ENVELOPE REFIT											
PROJECT- CSA15-G1											
drawing											
MECHANICAL DETAILS											
designed	S. JOANISSE / Z. FETTAKA	conçu									
date	2016.04.07										
drawn	D. VÉZINA	dessiné									
date	2016.04.07										
reviewed	F. DIONNE	examiné									
date	2016.04.07										
approved	F. DIONNE	approuvé									
date	2016.04.07										
scale											
project no.		no. du projet									
CSA15-G1											
drawing no.		no. du dessin									
M-205											