

Partie 1 General

1.1 INSTALLATION AND REMOVAL

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.2 WATER SUPPLY

- .1 Departmental Representative will not provide continuous supply of potable water.
- .2 Arrange for connection with appropriate utility company and pay costs for installation, maintenance and removal.
- .3 Pay for water consumption charges at prevailing rates.

1.3 TEMPORARY POWER AND LIGHT

- .1 Provide the service and pay costs associated with the temporary power supply for lighting and operation of power tools during construction.
- .2 Arrange for connecting the construction trailer and other equipment, and bear all costs of installation, maintenance, disconnection and removal.
- .3 Any electrical connection to the existing network must be performed by a qualified electrician.

1.4 TELECOM FACILITIES

- .1 The Contractor shall provide temporary telecommunications facilities, including telephones, fax machines, the Internet including any lines and the necessary equipment for his own use and for use by the Departmental Representative. Provide the connection of these installations to major networks and pay costs of all these services.

1.5 FIRE PROTECTION

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction, governing codes, applicable regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

Partie 2 Product

2.1 NOT USED

- .1 Sans objet.

CARLETON
Riprap consolidation of the commercial wharf
Project: R.082610.001

Section 01 51 00
TEMPORARY UTILITIES
Page 2

Partie 3 Execution

3.1 NOT USED

.1 Sans objet.

END OF SECTION